

FILE NAME = S:\Projects\082B-VHY_IL_3_GraFton\ dgn\CADD_Sheets\082B-VHY-ent-schedule.dgn

ENTRANCE CULVERT SCHEDULE																	
LOCATION		EXISTING CULVERT			PIPE CULVERT REMOVAL	REMOVAL OF EXISTING STRUCTURE	PIPE CULVERTS									PRECAST REINFORCED CONCRETE FLARED END SECTIONS	
STATION	SIDE LT/RT	MATERIAL	SIZE INCHES	HEADWALL NUMBER	FOOT		CLASS A, TYPE 1			CLASS D, TYPE 1			CLASS D, TYPE 2			30" EACH	36" EACH
							30" FOOT	36" FOOT	15" FOOT	18" FOOT	24" FOOT	30" FOOT	15" FOOT	18" FOOT	48" FOOT		
103+10.00	RT																
103+15.72	LT	CMP	12	2	40.2												
108+57.47	RT	CMP	12	2	16.73												
111+40.73	RT	CMP	12	2	20.77												
116+22.84	RT	CMP	12	2	107.33												
118+28.89	LT	CMP	18	2	38.33												
118+28.89	RT	CMP	15	2	54.25												
124+40.00	RT	CMP	12	2	24.67												
141+47.00	RT	CMP	12	2	25.61												
146+42.00	RT	CMP	15	2	36.55												
147+43.00	RT	CMP	15	2	39.23												
147+59.85	LT																
148+08.00	LT	CMP	15	2	25.71												
156+44.00	LT	CMP	12	0	30.42												
156+45.00	RT	CMP	18	2	19.25												
157+83.00	RT	CMP	15	2	29.34												
158+84.86	RT	CMP	15	2	25.47												
160+83.88	RT																
169+54.50	LT																
169+74.45	RT																
173+15.36	LT	CMP	48	0	41.88												
174+13.73	RT	CMP	18	2	43.02												
175+91.24	LT																
176+03.04	RT	CMP	24	2	43.29												
176+55.25	LT																
179+38.00	LT																
185+00.00	RT	CMP	18	0	17.57												
185+00.00	RT	RCP	18	0	50.00												
185+45.56	LT	CMP	12	2	29.12												
194+19.00	RT	VC	12	0	27.94												
201+74.12	RT	CMP	12	2	26.49												
203+17.00	RT	CMP	15	2	21.4												
209+46.00	LT	CONC	15	2		5											
211+08.26	RT	CMP	18	2	24.78												
212+73.94	RT	CONC	18	2		6											
214+29.34	RT	CMP	18	2	17.91												
214+61.00	LT	CMP	18	2	26.41												
215+16.94	RT	CMP	18	0	14.05												
219+15.00	LT	CMP	12	2	19												
220+77.00	RT	CONC	12	2		8											
225+53.00	LT	CMP	15	0	15.23												
227+06.10	LT	CMP	12	2	19.65												
230+90.00	RT	CMP	18	2	43.79												
233+80.00	LT	CMP	18	0	20.44												
233+80.00	RT	CMP	15	0	38.23												
234+92.00	LT	CMP	24	2	59.17												
235+58.24	LT	CMP	15	2	28.75												
235+75.00	RT	CMP	18	2	26.66												
247+32.00	RT	CMP	15	2	23.97												
273+89.00	RT	CMP	12	0	19.42												
278+91.36	LT	CONC	12	2		11											
278+91.36	RT	CONC	12	2		12											
279+30.79	LT	CMP	15	2	23.18												
281+54.00	LT	STEEL	12	2	32.99												
283+76.61	LT	CMP	18	2	30.26												
288+57.07	LT	CMP	12	0	20.47												
291+73.00	LT	CMP	12	2	30.39												
297+48.00	LT																
301+46.00	LT	CMP	18	2	21.24												
304+20.33	RT																
316+87.00	RT																
320+50.00	RT																
323+72.00	LT	CMP	15	2	25.43												
326+99.00	RT	RCP	12	2	27.16												
332+37.07	LT	CMP	15	2	61.84												
334+90.00	LT	CMP	20	0	30.34												

SEE STORM SEWER SCHEDULE
SEE STORM SEWER SCHEDULE

CONTINUED ON NEXT SHEET



USER NAME = l.jackson	DESIGNED - ACM	REVISED -
MODEL NAME = Schedule 05	DRAWN - EDW	REVISED -
PLOT SCALE = 2.0000' / 1"	CHECKED - LWJ	REVISED -
PLOT DATE = 8/22/2014	DATE - 8-11-14	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES	
FAS ROUTE 749/752 (IL RTE 3)	
SCALE:	SHEET 5 OF 26 SHEETS

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	101-2RS-1	JERSEY	438	26
• 749/752			CONTRACT NO. 76789	
ILLINOIS FED. AID PROJECT				