

FILE NAME = S:\Projects\082B-VHY\_IL\_3\_Graf\Task\Sign\CADD\_Sheets\082B-VHY\_IL\_3\_Sign\_Schedule.dgn

SIGN SCHEDULE														
LOCATION		SIGN				SIGN PANEL	SIGN PANEL	WOOD SIGN SUPPORT	TELESCOPING STEEL SIGN SUPPORT	METAL POST - TYPE A	RELOCATE SIGN PANEL ASSEMBLY TYPE A	RELOCATE SIGN PANEL ASSEMBLY TYPE B	DELINEATORS	COMMENTS
STATION	SIDE	CODE NUMBER	SIZE			TYPE 1	TYPE 2	FOOT	FOOT	FOOT	EACH	EACH	EACH	
	LT/RT		WIDTH INCH	X	HEIGHT INCH	SQ FT	SQ FT							
335+54.73	LT											1	DELINEATORS	
335+54.73	RT											1	DELINEATORS	
341+21.00	RT	W14-3				5.56		18.9					NO PASSING ZONE 48 X 48 X 36	
343+84.53	LT											1	DELINEATORS	
343+84.53	RT											1	DELINEATORS	
345+60.25	RT	D3-1	36	X	12				14.47		1		CRONIN LN	
		D3-1	36	X	12								SIGN 2 - CONIN LN	
346+31.29	RT	W2-2	36	X	36	9.00		12.4					CROSS ROAD	
		W16-8a	30	X	15	3.13							SIGN 2- NEWBERN RD CEMETERY RD	
349+98.07	LT									7	1		042	
349+98.07	RT									7	1		SIGN 2 - 2474	
													042	
													SIGN 2 - 2474	
351+00.29	LT		18	X	18				15.7	1			COUNTY ROAD SIGN	
352+54.00	LT	W14-3				5.56		17.4					NO PASSING ZONE 48 X 48 X 36	
353+25.00	RT	D1-2	72	X	30		15.00	18.1					GREEN BOARD SIGN - NEWBERN RD CEMETERY RD	
								19.2					2ND POST	
354+11.67	LT											1	DELINEATORS	
354+11.67	RT											1	DELINEATORS	
354+42.07	LT	R1-1	30	X	30	6.25		15.0					STOP AT NEWBERN ROAD	
		W4-1100	24	X	12	2.00							SIGN 2 - CROSS TRAFFIC DOES NOT STOP	
355+05.90	RT	R1-1	30	X	30	6.25		15.0					STOP AT CEMETERY ROAD	
		W4-1100	24	X	12	2.00							SIGN 2 - CROSS TRAFFIC DOES NOT STOP	
355+15.34	LT	D1-1	48	X	12				17.5		1		NEWBERN RD W/ARROW UP	
		D3-1	48	X	12								SIGN 2 - NEWBERN RD	
		D1-1	48	X	12								SIGN 3 - NEWBERN RD W/ ARROW RIGHT	
		D1-1	48	X	12								SIGN 4 - NEWBERN RD W/ ARROW LEFT	
		D3-1	54	X	12								SIGN 5: STATE HIGHWAY 3	
		D3-1	54	X	12								SIGN 6 - STATE HIGHWAY 3	
		D1-1	48	X	12								SIGN 7 - CEMETERY RD W/ ARROW LEFT	
		D1-1	48	X	12								SIGN 8 - CEMETERY RD W/ ARROW RIGHT	
357+15.00	LT	D1-2	72	X	30		15.00	17.3					GREEN BOARD SIGN - NEWBERN RD W/ARROW CEMETERY RD W/ARROW	
								16.3					2ND WOOD POST	
363+25.00	LT	W2-2	36	X	36	9.00		16.6					CROSS ROAD	
		W16-8a	36	X	15	3.75							SIGN 2 - NEWBERN RD CEMETERY RD	
370+51.35	LT											1	DELINEATORS	
370+51.35	RT											1	DELINEATORS	
371+04.61	LT											1	DELINEATORS	
371+04.61	RT											1	DELINEATORS	
379+24.68	LT											1	DELINEATORS	
379+24.68	RT											1	DELINEATORS	
387+50.59	LT											1	DELINEATORS	
387+50.59	RT											1	DELINEATORS	
397+30.51	LT											1	DELINEATORS	
397+30.51	RT											1	DELINEATORS	
404+47.75	LT		18	X	18				13.0	1			COUNTY ROAD SIGN	
405+67.37	LT								7	1			042	
405+67.37	RT								7	1			SIGN 2 - 2475	
													042	
													SIGN 2 - 2475	
408+52.00	RT	W14-3				5.56		16.7					NO PASSING ZONE 48 X 48 X 36	
409+27.00	LT	W14-3				5.56		18.2					NO PASSING ZONE 48 X 48 X 36	
411+43.66	LT											1	042	
411+43.66	RT											1	SIGN 2 - 2476	
													042	
													SIGN 2 - 2476	
413+36.86	RT	W3-1	36	X	36	9.00		15.6					TRIANGLE SIGN WITH STOP SIGN AND ARROW ON IT	
416+33.00	RT	M2-1	21	X	15	2.19		17.3					JCT	
		M1-1100	24	X	24	4.00							SIGN 2- ILLINOIS 109	
416+85.00	LT	R2-1	30	X	36	7.50		16.3					SPEED LIMIT 55	
419+40.00	RT	M1-1100	24	X	24	4.00		15.1					ILLINOIS 3	
		M5-1 R	21	X	15	2.19							SIGN 2- RIGHT TURN ARROW	
420+20.00	LT	D2-1	48	X	18	6.00		14.9					GREEN BOARD SIGN - GRAFTON 8	
420+78.00	LT	D3-1	36	X	12				14.33				ROBERTS LN	
		D3-1	36	X	12						1		SIGN 2 - ROBERTS LN	
		D3-1	54	X	12								SIGN 3 - STATE HIGHWAY 3	
		D3-1	54	X	12								SIGN 4 - STATE HIGHWAY 3	
420+86.00	LT	R1-1	30	X	30	6.25		13.8					STOP ON ROBERTS ROAD ADDED	
		W4-1100	24	X	12	2.00							SIGN 2 - CROSS TRAFFIC DOES NOT STOP	
421+12.00	RT	D1-2	72	X	30		15.00	15.1					GREEN BOARD SIGN - JERSEYVILLE W/ARROW LEFT	
								16.1					ALTON W/ARROW RIGHT	
													2ND WOOD POST	

CONTINUED ON NEXT SHEET



USER NAME = ljackson  
 MODEL NAME = Schedule 24  
 PLOT SCALE = 2.0000' / in.  
 PLOT DATE = 8/22/2014

DESIGNED - ACM  
 DRAWN - EDW  
 CHECKED - LWJ  
 DATE - 8-11-14

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES  
 FAS ROUTE 749/752 (IL RTE 3)

SCALE: SHEET 24 OF 26 SHEETS

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	101-2RS-1	JERSEY	438	45
• 749/752			CONTRACT NO. 76789	
ILLINOIS FED. AID PROJECT				