

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
				ROADWAY 0004 RURAL	BOX CULVERT 0011 S.N. 041-2021
20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25	
20200100	EARTH EXCAVATION	CU YD	1678	1678	
25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5	
25000350	SEEDING, CLASS 7	ACRE	0.5	0.5	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	65	65	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45	45	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	45	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1	1	
25100115	MULCH, METHOD 2	ACRE	0.5	0.5	
25100630	EROSION CONTROL BLANKET	50 YD	1279	1279	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	50 YD	420	420	
25100900	TURF REINFORCEMENT MAT	50 YD	66	66	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100	
28000305	TEMPORARY DITCH CHECKS	FOOT	20	20	

- SEE SPECIAL PROVISIONS
- △ DENOTES SPECIALTY ITEM

FILE NAME : D:\78210-11-500.dgn
 USER : twalker
 PLOT DRIVER : 1001.PDF.plt



QUIGG ENGINEERING INC

USER NAME : twalker	DESIGNED - MCV	REVISED -
FILE NAME : D:\78210-11-500.dgn	DRAWN - CMM	REVISED -
PLOT SCALE : 40.0000 / in.	CHECKED - MTM	REVISED -
PLOT DATE : 5/29/2014	DATE - 4/25/2014	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 1 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
849	113B-1	JEFFERSON	36	3
				CONTRACT NO. 78210
ILLINOIS FED. AID PROJECT				