



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

November 21, 2024

SUBJECT FAI Route 57 (I-57)
Project NHFP-NHPP-60UH(363)
Section (X1-8,X1-7-1,X1-7,X1-6-1)R-2
Williamson County
Contract No. 78798

Item No. 14, December 13th, 2024 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised schedule of prices.
2. Revised pages i-iii of the Table of Contents of the Special Provisions.
3. Revised page 41 of the Special Provisions.
4. Revised Sheet 10 of the plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
3D MODEL – CONTRACTOR SUPPLIED	1
AVAILABILITY OF ELECTRONIC FILES	2
UTILITIES.....	2
COOPERATION BETWEEN CONTRACTORS.....	4
NOTIFICATION PRIOR TO STARTING WORK.....	6
COMPLETION DATE PLUS WORKING DAYS.....	6
EXCESS EXCAVATION	7
STAGING AREAS.....	7
EXISTING MEDIAN DITCH TREATMENT	7
SUBGRADE TREATMENT	8
SUBGRADE DAMAGE	9
STRINGLINE GRADE CONTROL	9
TRENCH BACKFILL	9
PAVEMENT REMOVAL.....	10
PAVED SHOULDER REMOVAL	10
PIPE UNDERDRAINS 4” (SPECIAL).....	11
PIPE UNDERDRAINS TYPE 2, 4 INCH	11
DRAINAGE HOLE FOR DRAINAGE STRUCTURE TYPE 4 WITH TYPE 20 FRAME AND GRATES	11
CONCRETE FILL FOR DRAINAGE STRUCTURES TYPE 4	12
DELINEATORS.....	12
HMA WEDGE REMOVAL	12
SHOULDER RUMBLE STRIPS, 16 INCH	13
HIGH TENSION CABLE MEDIAN BARRIER – DRIVEN LINED POSTS	13
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	13
TRAFFIC CONTROL PLAN.....	15
TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	17
TRAFFIC CONTROL STAGING	18
I-57 WEIGH STATION CLOSURE NOTIFICATION	18
WEIGH STATION RAMP CLOSURES	18
WEIGH STATION RAMP RENTAL.....	19
RAMP CLOSURES	20
RAMP RENTAL.....	21

TEMPORARY CLOSURE OF ALL LANES.....	21
DROP-OFF NEAR THE EDGE OF TRAVELED WAY	22
CHANGEABLE MESSAGE SIGNS	23
RODENT SHIELDS.....	23
TIMBER CURB REMOVAL.....	24
MOWING.....	24
REMOVE EXISTING RIPRAP	25
COARSE AGGREGATE	25
HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH.....	26
CONCRETE BARRIER REMOVAL, DOUBLE FACE.....	26
CONCRETE COLLAR (SPECIAL).....	26
INLETS, SPECIAL NO. 1	27
INLETS, SPECIAL NO. 2	27
INLETS TO BE RECONSTRUCTED (SPECIAL)	28
MEMBRANE WATERPROOFING SYSTEM FOR BURIED STRUCTURES	28
FILLING INLETS (SPECIAL)	30
TYPE F INLET BOX, STANDARD 610001 (SPECIAL)	31
DELINEATOR REMOVAL.....	32
CENTER LINE – RUMBLE STRIP – 8”	32
REMOVE IMPACT ATTENUATORS, NO SALVAGE.....	32
REMOVE IMPACT ATTENUATOR SAND MODULE.....	33
PREFORMED THERMOPLASTIC PAVEMENT MARKING SHIELD.....	33
FURNISHING AND INSTALLING WEIGH-IN-MOTION COMPONENTS	35
PIPE UNDERDRAIN AND HEADWALL REMOVAL.....	38
REMOVING AND REPLACING EXPANSION JOINT	39
ROCK FILL - FOUNDATION.....	39
SLOPE WALL SLURRY PUMPING.....	40
UNDERDRAIN CONNECTION TO STRUCTURE.....	40
RELOCATE SIGN SPECIAL.....	41
ENGINEER’S FIELD LABORATORY	41
DECK SLAB REPAIR.....	42
BRIDGE DECK LATEX CONCRETE OVERLAY.....	47
STRUCTURAL REPAIR OF CONCRETE	57
DIAMOND GRINDING AND SURFACE TESTING BRIDGE SECTIONS	66
BRIDGE DECK GROOVING (LONGITUDINAL)	71
DRILLED SHAFTS.....	72
PREFORMED PAVEMENT JOINT SEAL.....	81

BAR SPLICERS, HEADED REINFORCEMENT	87
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE)	89
CEMENT, TYPE IL (BDE).....	90
COMPENSABLE DELAY COSTS (BDE).....	90
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	94
FUEL COST ADJUSTMENT (BDE).....	102
HIGH TENSION CABLE MEDIAN BARRIER REMOVAL (BDE).....	105
HOT-MIX ASPHALT (BDE).....	105
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE).....	106
MATERIAL TRANSFER DEVICE (BDE)	107
PERFORMANCE GRADED ASPHALT BINDER (BDE).....	109
PORTLAND CEMENT CONCRETE (BDE)	113
PREFORMED PLASTIC PAVEMENT MARKING (BDE)	114
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	115
SEEDING (BDE)	116
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	121
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	124
SPEED DISPLAY TRAILER (BDE).....	125
STEEL COST ADJUSTMENT (BDE).....	126
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	128
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	129
SUBMISSION OF PAYROLL RECORDS (BDE)	129
SURFACE TESTING OF PAVEMENTS – IRI (BDE)	130
TRAFFIC SPOTTERS (BDE).....	136
TRAINING SPECIAL PROVISIONS (BDE)	137
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION.....	140
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)	142
WEEKLY DBE TRUCKING REPORTS (BDE).....	142
WOOD SIGN SUPPORT (BDE).....	142
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	143
PROJECT LABOR AGREEMENT	145
STORM WATER POLLUTION PREVENTION PLAN.....	163

RELOCATE SIGN SPECIAL

Description. This work shall consist of relocating the existing fiber optic open-closed sign from the existing break-away wide flange steel signposts to the proposed break-away wide flange steel signposts. This work shall include any necessary splices, cables, wiring, conduit, and hardware.

Basis of Payment. This work will be paid at the contract unit price per EACH for RELOCATE SIGN SPECIAL.

ENGINEER'S FIELD LABORATORY

Revise Article 670.05 of the Standard Specifications to read:

670.05 Engineer's Field Laboratory. The field laboratory shall have a ceiling height of not less than 7 ft (2 m) and a floor space of not less than 380 sq ft (35 sq m). The laboratory shall be provided with sufficient heat, natural and artificial light, and air conditioning. Sanitary facilities as specified for Engineer's Field Office Type A shall also be included. Doors and window shall be equipped with locks.

Adequate all weather parking shall be available to accommodate a minimum of six vehicles.

In addition, the following equipment and furniture meeting the approval of the Engineer shall be furnished:

- (a) One desk and non-folding chair
- (b) Table and chairs capable of seating 6 people
- (c) One file cabinet, letter size, two drawer
- (d) One first-aid cabinet fully equipped
- (e) One service sink and water supply for testing purposes
- (f) One work bench 3 x 10 x 3 ft (1 x 3 x 1m) high with drawers and cabinets below and three 110 volt, 20 amp outlets above the bench.
- (g) Internet Connection. An internet service connection with a wireless router capable of providing service to a minimum of five devices. The internet service shall be for unlimited data with a minimum internet data download speed of 25 megabits per second. For areas where this minimum download speed is not available, the maximum speed available for the area shall be provided.
- (h) One electric water cooler dispenser.