

MODEL: Summary of Quantities 06
FILE NAME: c:\volkert_pw_working\pbetsy_witt\40326115\0978798-ah1-SOO.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				ROADWAY	ROADWAY	BRIDGE	BRIDGE	CULVERT
				80% FED/20% STATE NHFP 0003	80% FED/20% STATE NHPP 0003	SN 100-0076 (NB) SN 100-0077 (SB) 90% FED/10 % STATE NHPP 0047	SN 100-0060 90% FED/10 % STATE NHPP 0047	SN 100-7074 90% FED/10 % STATE NHPP 0003
63700805	CONCRETE BARRIER TRANSITION	FOOT	10	8.30	1.70			
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	185599	154047	31552			
64300260	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	0.83	0.17			
64401100	HIGH TENSION CABLE MEDIAN BARRIER	FOOT	43789	36345	7444			
64401300	HIGH TENSION CABLE MEDIAN BARRIER TERMINALS	EACH	24	20	4			
66201120	CONCRETE SHOULDER CURB	FOOT	760	631	129			
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	4455	3698	757			
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	3	2.49	0.51			
* 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1	0.83	0.17			
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	0.83	0.17			
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA	12	10	2			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	38	32	6			
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	38	32	6			
67100100	MOBILIZATION	L SUM	1	0.83	0.17			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	1095	909	186			
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	105	87	18			
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.83	0.17			

* SPECIALTY ITEM

 REVISED 11-20-2024



USER NAME =	betsy.witt	DESIGNED -	REVISED -
		DRAWN -	REVISED -
PLOT SCALE =	\$\$CALE\$	CHECKED -	REVISED -
PLOT DATE =	8/27/2024	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
INTERSTATE 57

SCALE: SHEET 6 OF 12 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(X1-6,X1-7-1,X1-7,X1-6-1)R-2	WILLIAMSON	614	10
CONTRACT NO. 78798				
ILLINOIS FED. AID PROJECT				