• (0203.1 & 0312-708W) R-3 CONTRACT NO. 62108

F.A.I. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	•	COOK	870	12
STA.		TO STA.		
FED ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

	CODE	PAY ITEM	UNIT	TOTAL	ACNHI 90% FED. 10% STATE URBAN	ACNHF 80% FED. 20% STATE			ACNHI 90% FED. 10% STATE						ACNHF 80% FED. 20% STATE	ACNHI 90% FED. 10% STATE	ACNHF 80% FED. 20% STATE		ISTHA-ACNHF	ACNHI	
					ROADWAY I-94	ROADWAY IL 394	IL 394 SB OVER I-80 SN-016-2796	IL 394 SB OVER CNRR SN-016-2798	IL 394 SB OVER THORN CREEK SN-016-2800	OVER THORN CREEK SN-016-2807	I-94 EB RETAINING WALL SN-016-W866	CULVERT SN-016-C012	LIGHTING I-94	LIGHTING IL 394	SIGNING I-94	SIGNING IL 394	RAMP F	THORN CREEK OVER IL 394 SB SN-016-2845	VILLAGE OF SOUTH HOLLAND
					CONSTRUCTION TYPE CODE																
*	M7290100	METAL POST - TYPE A	METER	12.3	J000-2A	J000-2A	X271-2A	X181-2A	X071-2A	X071-2A	Y007	Y007	Y030-1E	Y030-1E	Y002-1C	Y002-1C	J000-2A	X071-2A	Y102		
*	M7300100	WOOD SIGN SUPPORT	METER	128.7											48.8	79.9					
*	M7330010	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (1.22M X 1.37M)	METER	25.2											25.2						
*	M7330020	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (1.37M X 1.60M)	METER	78.0											50.0	28.0					
*	M7330235	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (0.90M X 1.68M)	METER	16.3											16.3						
*	M7330255	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (0.90M X 2.14M)	METER	23.9											23.9						
*	M7330400	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	METER	7.0												7.0					
*	M7330500	OVERHEAD SIGN STRUCTURE WALKWAY	METER	94.5											77.9	16.6					
*	M7340200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU M	109.5											94.2	15.3					
*	M7800105	THERMOPLASTIC PAVEMENT MARKING - LINE 100MM	METER	3656	1100	2556															
*	M7800120	THERMOPLASTIC PAVEMENT MARKING - LINE 200MM	METER	476	476																
*	M7800125	THERMOPLASTIC PAVEMENT MARKING - LINE 300MM	METER	60	60																
	M7800410	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 125MM	METER	711	391	320															
*	M7800605	EPOXY PAVEMENT MARKING - LINE 100MM	METER	11312	4208	7104															
*	M7800610	EPOXY PAVEMENT MARKING - LINE 125MM	METER	1215	993	222															
*	M7800620	EPOXY PAVEMENT MARKING - LINE 200MM	METER	302	65	237															
*	M7800625	EPOXY PAVEMENT MARKING - LINE 300MM	METER	49		49															
*	M7802000	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ M	28	28																
*	M7802010	POLYUREA PAVEMENT MARKING TYPE I - LINE 100MM	METER	17270	7307	9963															
*	M7802020	POLYUREA PAVEMENT MARKING TYPE I - LINE 200MM	METER	7289	4462	2827															
*	M7802030	POLYUREA PAVEMENT MARKING TYPE I - LINE 300MM	METER	2039	801	1238															
	M7830100	PAVEMENT MARKING REMOVAL	SQ M	1745	757	988															
*	MX033557	CONDUIT IN TRENCH, 3-100MM DIA., GALVANIZED STEEL, PVC COATED	METER	30.5										30.5							
*	MX033565	CONDUIT ENCASED, REINFORCED CONCRETE, 30MM DIA., CNC, 4 WIDE BY 2 HIGH	METER	283.9									283.9								
*	M8120130	CONDUIT EMBEDDED IN STRUCTURE, 65MM DIA., GALVANIZED STEEL	METER	36									31.5	4.5							
*	MX033569	CONDUIT EMBEDDED IN CONCRETE, 100MM., COILABLE NON-METALLIC, 1 HIGH X 1 WIDE	METER	4									4								
*	MX033570	CONDUIT ENCASED, REINFORCED CONCRETE, 100MM DIA., PVC, 3 WIDE BY 2 HIGH	METER	27										27							
*	M8120280	CONDUIT EMBEDDED IN STRUCTURE, 100MM DIA., RIGID GALVANIZED STEEL	METER	16									16								

• SPECIALTY ITEM
•• SFTY-3N
△ Y080
△△ Y220 NOISE ABATEMENT WALL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-94 EAST BOUND / IL 394 SOUTH BOUND

SUMMARY OF QUANTITIES

HORIZ SCALE: NONE
VERT SCALE: NONE
DATE: JULY 18, 2005
DRAWN BY: JYMC
CHECKED BY: JES

HNTB

J:@34562@cadd@t1@cds@Contract19_SB@sq190084a.dgn
slauer 15-SEP-2005 15:10