• (0203.1 & 0312-708W) R-3 CONTRACT NO. 62108

F.A.I. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	•	COOK	870	14
STA.		TO STA.		
FED ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

	CODE	PAY ITEM	UNIT	TOTAL	ROADWAY I-94 (URBAN, ACNHI 90% FED. 10% STATE)	ROADWAY IL 394 (ACNHF 80% FED. 20% STATE)	IL 394 SB OVER I-80 SN-016-2796 (ACNHF 80% FED. 20% STATE)	IL 394 SB OVER CNRR SN-016-2798 (ACNHF 80% FED. 20% STATE)	IL 394 SB OVER THORN CREEK SN-016-2800 (ACNHF 80% FED. 20% STATE)	IL 394 SB OVER THORN CREEK SN-016-2807 (ACNHF 80% FED. 20% STATE)	I-94 EB RETAINING WALL SN-016-W866 (ACNHI 90% FED. 10% STATE)	CULVERT SN-016-C012 (ACNHI 90% FED. 10% STATE)	LIGHTING I-94 (ACNHF 80% FED. 20% STATE)	LIGHTING IL 394 (ACNHI 90% FED. 10% STATE)	SIGNING I-94 (ACNHF 80% FED. 20% STATE)	SIGNING IL 394 (ACNHF 80% FED. 20% STATE)	RAMP F (ISTHA-ACNHF)	THORN CREEK SN-016-2845 (ACNHI)	IL 394 SB OVER SOUTH HOLLAND (ACNHI)	VILLAGE OF HOLLAND (ACNHI)
					CONSTRUCTION TYPE CODE																
					J000-2A	J000-2A	X271-2A	X181-2A	X071-2A	X071-2A	Y007	Y007	Y030-1E	Y030-1E	Y002-1C	Y002-1C	J000-2A	X071-2A	Y102		
•	MX030301	CONDUIT ATTACHED TO STRUCTURE,100MM DIA. GALVANIZED STEEL, PVC COATED	METER	3									3								
△△	MX030355	NOISE ABATEMENT WALL, GROUND MOUNTED	SQ M	2181	2181																
△△	MX030356	NOISE ABATEMENT WALL, STRUCTURE MOUNTED	SQ M	6408	6408																
	MX030504	TEMPORARY PAVEMENT (INTERSTATE)	SQ M	1581	608	973															
	MX030507	STORM SEWERS AND CULVERTS TO BE GROUTED	CU M	92		92															
	MX030523	ERECTING FLOATING BEARINGS, FIXED 1500 KN	EACH	12						12											
•	MX032160	CONDUIT ENCASED, REINFORCED CONCRETE, 100MM DIA. PVC, 2 WIDE X 1 HIGH	METER	280									157	123							
•	MX032161	CONDUIT ENCASED, REINFORCED CONCRETE, 100MM DIA. PVC, 2 WIDE X 2 HIGH	METER	55										55							
	MX032178	TEMPORARY INFORMATION SIGNING	SQ M	135.46	61.61	73.85															
	MX032651	MULCH-PLACEMENT 100MM	SQ M	8370		8370															
	MX032708	STRIP SEAL EXPANSION JOINT ASSEMBLY	METER	44.7			29.4		15.3												
	MX033141	BRIDGE JOINT SYSTEM (EXPANSION), 25MM	METER	15.4				15.4													
	MX033183	SOIL STABILIZERS	KG	2256428	417093	1839335															
	MX033276	TEMPORARY SOIL RETENTION SYSTEM	SQ M	1380.5		775				544		61.5									
	MX033290	SEDIMENT CONTROL, SILT FENCE	METER	2877	1814	1063															
	MX033291	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	METER	1239	707	532															
	MX033292	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ M	900	900																
	MX033303	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ M	900	900																
	MX033387	CONDUIT ATTACHED TO STRUCTURE, 25MM DIA., RIGID GALVANIZED STEEL, PVC COATED	METER	3									3								
	MX355150	BITUMINOUS BASE COURSE SUPERPAVE, 150MM	SQ M	33	33																
	MX406012	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	M TON	5	5																
	MX406078	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N105	M TON	104	72	32															
	MX406210	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-25.0, N105	M TON	42	28	14															
	MX407440	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 290MM	SQ M	258	258																
	MX482460	BITUMINOUS SHOULDERS SUPERPAVE 330MM	SQ M	492	492																
	MX602310	CATCH BASINS, 1.2M BY 0.9M, TYPE 20 FRAME AND GRATE	EACH	7	7																
	MX637150	CONCRETE BARRIER, SINGLE FACE, 1065 MM HEIGHT, REINFORCED	METER	1061	550	511															
	MX704200	REMOVE TEMPORARY CONCRETE BARRIER	METER	8937.4	4094.20	4843.20															

• SPECIALTY ITEM
•• SFTY-3N
△ Y080
△△ Y220 NOISE ABATEMENT WALL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-94 EAST BOUND / IL 394 SOUTH BOUND

SUMMARY OF QUANTITIES

HORIZ SCALE: NONE
VERT SCALE: NONE
DATE: JULY 18, 2005
DRAWN BY: JYMC
CHECKED BY: JES

HNTB

J:\345628\cadd\t18\ods\Contract19_SB\eq190104a.dgn
slauer 15-SEP-2005 15:09