

SIGNING AND PAVEMENT MARKING SCHEDULE

F.A.I. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	*	COOK	870	46
STA.		TO STA.		
FED ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LOCATION	SHOULDER RUMBLE STRIP	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	THERMOPLASTIC PAVEMENT MARKING - LINE 100MM	THERMOPLASTIC PAVEMENT MARKING - LINE 200MM	THERMOPLASTIC PAVEMENT MARKING - LINE 300MM	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 125 MM	POLYUREA PAVEMENT MARKING, TYPE 1 - LETTERS AND SYMBOLS	POLYUREA PAVEMENT MARKING, TYPE 1 - LINE 100MM	POLYUREA PAVEMENT MARKING, TYPE 1 - LINE 125MM	
	METER	EACH	EACH	METER	METER	METER	METER	SQ M	METER	METER	
I-94	Begin TO 18+725	831	280	0	1100	476	37	391	0	1156	214
	18+725 TO 19+000	885	141	0	0	0	23	0	7	698	329
	19+000 TO 19+350	1400	172	0	0	0	0	0	7	1050	438
	19+350 TO 19+700	1400	175	0	0	0	0	0	7	1190	442
	19+700 TO 20+000	1200	151	0	0	0	0	0	0	1199	301
IL 394	Begin TO 38+875	1238	160	0	2556	0	0	320	0	1282	196
	38+875 TO 39+240	794	96	0	0	0	0	0	0	1460	288
	39+240 TO 39+600	470	154	0	0	0	0	0	0	1236	298
	39+600 TO 39+825	105	62	19	0	0	0	0	0	854	163
	39+825 TO 440+200	562	84	8	0	0	0	0	0	1838	189
IL-394/ I-94	440+200 TO 440+525	429	27	31	0	0	0	0	0	1376	172
	440+525 TO 440+900	1084	82	70	0	0	0	0	0	2010	271
	440+900 TO 441+167.161	965	128	0	0	0	0	0	0	1172	256
RAMP F	110+400 TO 110+750	0	0	0	0	0	0	0	0	0	0
TOTAL		11363	1712	128	3656	476	60	711	21	16521	3557

LOCATION	METAL POST - TYPE A	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	REMOVE GROUND - MOUNTED SIGN SUPPORT	REMOVE CONCRETE FOUNDATION - OVERHEAD	TUBULAR TRAFFIC SIGN POST
	EACH	EACH	EACH	EACH	EACH	EACH
I-94	18+400 TO 19+880	0.0	0	0	2	5
IL 394/I-94	39+463 (IL 394) TO 19+880 (I-94)	12.3	2	1	4	0
IL 394	37+800 TO 39+463	0.0	0	0	0	0
TOTAL		12.3	2	1	6	5

LOCATION	POLYUREA PAVEMENT MARKING, TYPE 1 - LINE 200MM	POLYUREA PAVEMENT MARKING, TYPE 1 - LINE 300MM	
	METER	METER	
I-94	BEGIN TO 18+725	697	181
	18+725 TO 19+000	709	50
	19+000 TO 19+350	420	40
	19+350 TO 19+700	575	42
	19+700 TO 20+000	1201	228
IL 394	BEGIN TO 38+875	0	52
	38+875 TO 39+240	0	88
	39+240 TO 39+600	515	139
	39+600 TO 39+825	607	252
	39+825 TO 440+200	382	209
IL-394/ I-94	440+200 TO 440+525	0	119
	440+525 TO 440+900	899	181
	440+900 TO 441+167.161	846	401
RAMP F	110+400 TO 110+750	0	0
TOTAL		6851	1982

LOCATION	SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	SIGN PANEL - TYPE 3	REMOVE SIGN PANEL - TYPE 1	REMOVE SIGN PANEL - TYPE 2	REMOVE SIGN PANEL - TYPE 3
	SQ M	SQ M	SQ M	SQ M	SQ M	SQ M
I-94	18+400 TO 19+880	19.55	3.60	183.38	0.00	1.44
IL 394/I-94	39+463 (IL 394) TO 19+880 (I-94)	1.38	11.16	93.78	0.75	5.40
IL 394	37+800 TO 39+463	2.16	4.68	10.26	0.00	4.65
TOTAL		23.09	19.44	287.42	0.75	6.84

LOCATION	WOOD SIGN SUPPORT	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (1.22M X 1.37M)	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (1.37M X 1.60M)	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (0.90M X 2.14M)	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	OVERHEAD SIGN STRUCTURE WALKWAY	DRILLED SHAFT CONCRETE FOUNDATIONS
	METER	METER	METER	METER	METER	METER	CU M
I-94	18+400 TO 19+880	15.0	25.2	50.0	12.1	0.0	64.4
IL 394/I-94	39+463 (IL 394) TO 19+880 (I-94)	74.7	0.0	28.0	11.8	7.0	27.6
IL 394	37+800 TO 39+463	39.0	0.0	0.0	0.0	0.0	0.0
TOTAL		128.7	25.2	78.0	23.9	7.0	92.0

NOTE:  
THE SCHEDULES ON THIS PAGE MAY NOT REFLECT ITEMS QUANTIFIED BETWEEN:  
☺ I-94 EB STA. 20+657.900 TO STA. 21+222.210,  
☺ I-94 WB STA. 30+785.473 TO STA. 31+020.000, AND  
MDTPE94 STA. 25+178.451 TO STA. 25+516.450

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
I-94 EAST BOUND / IL 394 SOUTH BOUND

SCHEDULE OF QUANTITIES

HORIZ SCALE:  
VERT SCALE:  
DATE: JULY 18, 2005

DRAWN BY: BJM  
CHECKED BY: JES

