

F.A.L. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	•	COOK	870	47
STA.		TO STA.		
FED ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

MAINTENANCE OF TRAFFIC SCHEDULE

LOCATION		MODULAR GLARE SCREEN SYSTEM			MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR			PAVEMENT MARKING TAPE, TYPE III 100MM			PAVEMENT MARKING TAPE, TYPE III 125MM			PAVEMENT MARKING TAPE, TYPE III 200MM			PAVEMENT MARKING TAPE, TYPE III 300MM			WORK ZONE PAVEMENT MARKING REMOVAL					
		METER			EACH			METER			METER			METER			METER			SQ M					
		STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3			
IL 394	37+700 TO 38+000	0	0	0	0	0	0	350	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	38
	38+000 TO 38+550	115	0	0	30	0	0	579	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	177
	38+550 TO 39+100	550	0	0	114	0	0	1100	0	270	0	0	68	0	0	0	0	0	0	0	0	0	0	0	259
	39+100 TO 39+600	500	0	0	82	0	0	1000	111	0	0	0	0	384	100	0	83	0	0	0	0	0	0	9	280
	39+600 TO 39+850	250	0	0	51	0	0	500	434	0	0	0	0	94	98	0	0	16	0	0	0	0	0	68	119
	39+850 TO 440+150	300	0	0	60	0	0	600	142	0	0	0	0	0	0	0	0	0	0	0	0	0	0	14	120
	440+150 TO 440+425	275	0	0	57	0	0	550	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	110
	440+425 TO 440+775	350	0	0	72	0	0	1400	506	0	0	63	0	343	0	0	42	0	0	0	0	0	0	59	140
I-94	440+775 TO 441+100	325	0	0	58	19	0	650	752	196	0	81	49	480	0	381	95	0	0	0	0	0	0	85	261
	19+825 TO 441+100	240	0	0	54	10	0	653	480	240	0	60	60	354	259	480	36	29	9	0	0	0	0	110	261
	19+275 TO 19+825	550	0	0	143	0	0	1100	336	281	0	60	48	0	0	198	0	0	5	0	0	0	0	72	324
	18+725 TO 19+275	550	0	0	135	0	0	1208	489	18	0	0	5	284	299	18	0	0	0	0	0	0	0	118	252
	18+375 TO 18+725	275	0	0	61	0	0	706	550	661	0	0	88	431	0	146	61	0	51	0	0	0	0	55	352
	18+253 TO 18+375	0	0	0	0	0	0	645	0	141	0	0	0	330	0	0	9	0	0	0	0	0	0	0	160
TOTAL		4280	0	0	917	29	0	11041	3800	1807	0	264	318	2700	756	1223	326	45	65	0	0	0	0	590	2850

LOCATION		RELOCATE TEMPORARY CONCRETE BARRIER (SPECIAL)			EPOXY PAVEMENT MARKING - LINE 100MM			EPOXY PAVEMENT MARKING - LINE 125MM			EPOXY PAVEMENT MARKING - LINE 200MM			EPOXY PAVEMENT MARKING - LINE 300MM			PAVEMENT MARKING REMOVAL			TEMPORARY PAVEMENT (INTERSTATE)					
		METER			METER			METER			METER			METER			SQ M			SQ M					
		STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3			
IL 394	37+700 TO 38+000	0	0	0	27	0	0	0	0	0	0	0	0	0	0	0	14	0	0	0	0	0	0	0	0
	38+000 TO 38+550	290	0	0	1189	0	0	0	0	0	0	0	0	0	0	0	154	0	0	0	0	0	0	0	0
	38+550 TO 39+100	550	0	0	1100	0	0	24	0	0	0	0	0	0	0	0	130	0	0	158	0	0	0	0	0
	39+100 TO 39+600	614	76	0	851	0	0	69	0	0	0	0	0	0	0	0	191	0	0	435	0	0	0	0	0
	39+600 TO 39+850	234	130	0	500	0	0	0	0	0	0	0	0	0	0	0	63	0	0	0	0	0	0	0	0
	39+850 TO 440+150	150	19	0	600	0	0	0	0	0	0	0	0	0	0	0	69	4	0	0	0	0	0	0	0
	440+150 TO 440+425	0	0	0	550	0	0	0	0	0	0	0	0	0	0	0	64	0	0	0	0	0	0	0	0
	440+425 TO 440+775	48	0	0	1427	0	0	84	0	0	237	0	0	49	0	0	161	0	0	0	0	0	0	0	0
I-94	440+775 TO 441+100	225	282	0	860	0	0	45	0	0	0	0	0	0	0	0	138	0	0	380	0	0	0	0	0
	19+825 TO 441+100	629	377	27	621	0	0	111	0	0	65	0	0	0	0	0	167	0	0	506	0	0	0	0	0
	19+275 TO 19+825	380	275	27	1121	0	0	276	0	0	0	0	0	0	0	0	162	0	0	0	0	0	0	0	0
	18+725 TO 19+275	373	185	155	962	0	0	276	0	0	0	0	0	0	0	0	149	0	0	102	0	0	0	0	0
	18+375 TO 18+725	392	0	268	956	0	0	175	0	0	0	0	0	0	0	0	127	0	0	0	0	0	0	0	0
	18+253 TO 18+375	0	0	0	15	0	0	88	0	0	0	0	0	0	0	0	90	0	0	0	0	0	0	0	0
TOTAL		3885	1344	477	10779	0	0	1148	0	0	302	0	0	49	0	0	1678	4	0	1581	0	0	0	0	0

LOCATION		TEMPORARY INFORMATION SIGNING			IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2			IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3			IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3		
		SQ M			EACH			EACH			EACH		
		STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3
IL 394	37+700 TO 38+000	0.00	0.00	0.00	0	0	0	0	0	0	0	0	0
	38+000 TO 38+550	0.00	0.00	0.00	0	0	0	0	0	0	1	0	0
	38+550 TO 39+100	2.43	0.00	0.00	0	0	0	0	0	0	0	0	0
	39+100 TO 39+600	0.81	0.00	0.00	0	0	0	0	0	0	1	0	0
	39+600 TO 39+850	0.00	0.00	0.00	0	0	0	0	0	0	0	1	0
	39+850 TO 440+150	0.00	0.00	0.00	0	0	0	0	0	0	0	0	0
	440+150 TO 440+425	0.00	0.00	0.00	0	0	0	0	0	0	0	0	0
	440+425 TO 440+775	5.67	0.00	4.32	0	0	0	0	0	0	1	0	0
I-94	440+775 TO 441+100	5.67	0.00	0.00	0	0	0	0	0	0	2	0	0
	19+825 TO 441+100	5.67	0.00	0.00	0	0	0	0	0	1	1	1	0
	19+275 TO 19+825	0.00	0.00	9.18	0	0	0	0	0	1	0	0	0
	18+725 TO 19+275	4.19	0.00	3.51	2	0	0	0	1	1	1	1	0
	18+375 TO 18+725	0.00	0.00	0.00	0	0	0	0	0	0	1	0	0
IL 394	RAMP G DETOUR	33.06	0.00	0.00									
IL 394	RAMP F DETOUR	0.00	0.00	44.69									
AIS		10.26	0.00	0.00									
TOTAL		57.50	0.00	61.70	2	0	0	0	1	3	8	3	0

IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE) TL-3 STAGE 1, AT TEMPORARY LIGHT POLE LOCATIONS (1 EACH LOCATION)			
STATION	OFFSET	STATION	OFFSET
38+511	16.8 RT	39+194	27.4 RT
38+561	16.8 RT	39+244	27.4 RT
38+611	16.4 RT	39+294	27.4 RT
38+661	17.0 RT	39+344	27.6 RT
38+711	18.5 RT	39+448	25.7 RT
38+761	20.2 RT	39+497	28.3 RT
38+811	22.0 RT		
38+861	23.3 RT		
39+094	27.4 RT		
39+144	27.4 RT		

TOTAL NEEDED FOR TEMPORARY LIGHT POLE PROTECTION PRIOR TO SHIFT TO STAGE 1

16

REVISIONS	
NAME	DATE

NOTE: THE SCHEDULES ON THIS PAGE MAY NOT REFLECT ITEMS QUANTIFIED BETWEEN: I-94 EB STA. 20+657.900 TO STA. 21+222.210, I-94 WB STA. 30+785.473 TO STA. 31+020.000, AND MDTP E94 STA. 25+178.451 TO STA. 25+516.450

ILLINOIS DEPARTMENT OF TRANSPORTATION I-94 EAST BOUND / IL 394 SOUTH BOUND

SCHEDULE OF QUANTITIES

HORIZ SCALE: VERT SCALE: DATE: JULY 18, 2005

DRAWN BY: BJM CHECKED BY: JES

