GENERAL NOTES

- 1. Reinforcement bars shall conform to the requirements of AASHTO M 31M or M 322M Grade 400.
- 2. The contractor shall drive 4-356 \$\phi\$ Metal Shell test piles in a permanent location. One each at the East and West Abutments and Piers 1 and 2 as directed by the Engineer before ordering the remainder of piles.
- 3. When deck pour is stopped for the day at one or more of the transverse Bonded Construction Joints in the deck Pouring Sequence as shown, the next pour shall not be made until both of the following requirements are met.
 - 1. At least 72 hours shall have elapsed from the end of the previous pour.
 - 2. The concrete strength shall have attained a minimum modulus of rupture of 4.5 MPa or a minimum compressive strength of 24 MPa.
- 4. The existing structural steel coating contains lead. The Contractor should take appropriate precautions to deal with the presence of lead on this project. No additional compensation will be made to properly dispose of the existing structure containing lead.
- 5. All construction joints shall be bonded.
- 6. All dimensions are in millimeters (mm) except as noted.
- 7. All new structural steel shall be shop painted with an inorganic zinc rich primer per AASHTO M 300, Type 1.

INDEX OF SHEETS

S-1 General Plan General Notes, Index of Sheets and Total Bill of Material

Stage Construction Details - Substructure Stage Construction Details - Superstructure

Top of Deck Elevations - Layout Top of Deck Elevations (1 of 7) S-8

Top of Deck Elevations (5 of 7)

S-12 S-13 Top of Deck Elevations (6 of 7)

S-16 Deck Plan - Westbound

Diaphragm at Abutments

S-18 Diaphragm at Piers

S-21 Superstructure Details

S-22 Framing Plan

S-31 Abutment Details

S-32 Piers 1 and 2 - Eastbound

S-34 Pier Details

S-36 Concrete Pile Details

S-39 Boring Logs (3 of 4)

Temporary Concrete Barrier for Stage Construction

Substructure Layout

S-7

Top of Deck Elevations (2 of 7)

Top of Deck Elevations (3 of 7)

Top of Deck Elevations (4 of 7)

Top of Deck Elevations (7 of 7) 5-14

Deck Plan - Eastbound S-15

S-19 Interior Diaphragms & Details S-20 Parapet Elevations

S-23 1.219 m PPC I-Beam - Spans 1 & 3 S-24 1.219 m PPC I-Beam - Span 2

S-25 Bearing Details
S-26 Anchor Bolt Details

S-27 West Abutment - Eastbound

S-28 West Abutment - Westbound

S-29 East Abutment - Eastbound

S-30 Fast Abutment - Westbound

S-33 Piers 1 and 2 - Westbound

S-35 Bar Splicer (Coupler) Details

S-37 Boring Logs (1 of 4)

S-38 Boring Logs (2 of 4)

S-40 Boring Logs (4 of 4)

JEHA SHEET NO. 5-2 1207 581 40 SHEETS

CONTRACT NO. 62114 INDOT DES. NO. 0100987

TOTAL RILL OF MATERIAL

- 1	ITEM	UNIT	SUPER	SUB	TOTAL
IN)	Present Structure, Str. No. I-80-1-8459, Remove Portions	L. Sum	1		
N)	Slopewall, Concrete, 100 mm	m ²		1,856	1,856
	Furnishing and Erecting Precast Prestressed Concrete I-Beams, 1219 mm	m	1272.0		1272.0
v) [Surface Seal	L. Sum	0.18		0.18
- [Bearing Assembly, Elastomeric Type I	Each	48		48
0	Excavation, Foundation, Unclassified	m³		1,876	1,876
<i>0</i> [Structure Backfill	m³		623	623
0	Test Pile, 356 mm	Each		4	4
0	Pile, Concrete, Steel Shell Encased, 6.35 mm, 356 mm	т		3,324.0	3,324.0
v [Concrete, A, Substructure	m ³		940.0	940.0
V) [Concrete, C. Superstructure	m ³	938.1		938.1
v) [Reinforcing Bars, Epoxy Coated	kg	117,310	56,690	174,000
- [Noise Abatement Wall Anchor Rod Assembly	Each	36		36
W)	Threaded Tie Bar Assembly, Epoxy Coated	Each	844	112	956
Ø [Anchor Bolt	Each	104		104
υF	Masonry Coating	L. Sum	0.10		0.10

(IN) Indiana Pay Items, denoted by "(Indiana)" in Special Provisions and Summary of Quantities.

DESIGNED BHS KFA CHECKED DRAWN MJB CHECKED

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. ROUTE 80/94 (BORMAN EXPRESSWAY)
OVER HOHMAN AVENUE
GENERAL NOTES, INDEX OF SHEETS AND TOTAL BILL OF MATERIAL SECTION 2626.2-R-2 LAKE COUNTY, INDIANA STATION 8+225.132 STRUCTURE NO. 1-80-1-8459 (EB & WB) DATE 09/05 (016-1001 & 016-1002)

AMERICAN