

Ą

and the second

-	ROUTE NO.	SECTION	col	ату	TOTAL SHEETS	SHEET NO.	SHEET NO. S-2
	F. A. I. 85/94			ITY, INDIANA	1207	918	29 SHEETS
าม		ILLINOIS	FED. ALD PROJECT-				
ί	CONTRAC	T NO.	62114	IND	OT DES	. NO. O	100987

TOTAL BILL OF MATERIAL

	ITEM	UNIT	QUANTITY
(IN)	Test Pile, 356 mm	Each	3
(IN)	Excavation, Foundation, Unclassified	т ^з	1,879.3
(IN)	Concrete, A, Substructure	т ³	1,635.6
	Rustication Finish	m²	758
(IN)	Reinforcing Bars, Epoxy Coated	kg	127,720
(IN)	Surface Seal	L Sum	0.08
(IN)	Pile, Concrete, Steel Shell Encased, 6.35 mm, 356 mm	т	1.421.5
	Geocomposite Wall Drain	m²	700
(IN)	Pipe, Underdrain, Perf., 1.63 mm, 150 mm	т	282.7
	Noise Abatement Wall Anchor Rod Assembly	Each	43
(IN)	Overhead Sign Structure Span Anchor Rod Assembly	Each	2
(IN)	B Borrow	m ³	620.3
(IN)	Structural Backfill	m ³	1,997.7
	Remove Mechanically Stabilized Earthwall	m²	161
(IN)	Masonry Coating	L Sum	0.20

(IN) Indiana Pay Items, denoted by "(Indiana)" in Special Provisions and Summary of Quantities.

