


80' (24 m) O.C.

SEE NOTE A —

40' (12 m) O.C.

MULTI-LANE/UNDIVIDED




MULTI-LANE/DIVIDED


SEE FIGURE 3B-14 MUTCD

LANE REDUCTION TRANSITION

 $\Rightarrow$ 

3 @ 40' (12 m) O.C.





**SYMBOLS** 

■ ONE-WAY AMBER MARKER

◆ TWO-WAY AMBER MARKER

◆ ONE-WAY CRYSTAL MARKER (W/O)

YELLOW STRIPE

WHITE STRIPE

## **GENERAL NOTES**

- 1. MARKERS USED WITH DASHED LINES SHALL BE CENTERED IN THE GAP BETWEEN SEGMENTS.
- 2. MARKERS USED ADJACENT TO SOLID LINES SHALL BE OFFSET 2 TO 3 (50 TO 75) TOWARD TRAFFIC AS SHOWN.
- 3. MARKERS THROUGH TANGENTS LESS THAN 500' (150 m) IN LENGTH BETWEEN CURVES SHALL BE INSTALLED AT THE LESSER OF THE TWO CURVE SPACINGS.
- 4. MARKERS ARE TO BE USED ADJACENT TO BOTH SOLID WHITE LINES IN DUAL LEFT TURN LANES

## LANE MARKER NOTES

- A. USE DOUBLE LANE LINE MARKERS SPACED AS SHOWN.
- B. REDUCE TO 40' (12 m) O.C. ON CURVES WHERE ADVISORY SPEEDS ARE 10 M.P.H (20 km/h) LOWER THAN POSTED SPEEDS.

## **DESIGN NOTES**

- 1. DOUBLE LANE LINE MARKERS SHALL BE USED UNLESS SPECIFIED OTHERWISE.
- 2. EXCEPT AS SHOWN ON THE LANE REDUCTION TRANSITION AND FREEWAY EXIT RAMP DETAIL, MARKERS ARE NOT TO BE SPECIFIED ON RIGHT EDGE LINES.
- 3. THE EXACT MARKER LIMITS, SPACING, AND COLOR SHALL BE INCLUDED IN THE PLANS WHEN STANDARD SPECIFICATIONS ARE NOT BEING USED.
- 4. MARKERS SHOULD NOT BE USED ALONGSIDE CURBS EXCEPT FOR EXTREMELY SHORT SECTIONS OF CURBS WHERE NOT MORE THAN TWO MARKERS WOULD BE INVOLVED.

All dimensions are in inches (millimeters) unless otherwise shown.

pw:	USER NAME = footemj	DESIGNED -	REVISED - T. RAMMACHER 03-12-99		TYPICAL APPLICATIONS	F.A.	SECTION	COUNTY TOTAL SHI
AME		DRAWN -	REVISED - T. RAMMACHER 01-06-00	STATE OF ILLINOIS		TOTE:		STILLIS
	PLOT SCALE = 50.0000 ' / in.	CHECKED -	REVISED - C. JUCIUS 09-09-09	DEPARTMENT OF TRANSPORTATION	RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)		C–11	CONTRACT NO.
. E	PLOT DATE = $3/4/2019$	DATE -	REVISED - C. JUCIUS 07-01-13		SCALE: NONE SHEET 1 OF 1 SHEETS STA. TO STA.		ILLINOIS FED.	AID PROJECT