

50103d

501.03

Designer Note: Use for similar type and size headwall removal to simplify documentation of quantities. Use on locations where the headwall is tied to the pipe culvert and a section of pipe must be removed with the headwall for ease of construction.

CONCRETE HEADWALL REMOVAL

Effective July 1, 1990

This work shall consist of the removal of existing concrete headwalls at various locations as shown on the plans and shall be done in accordance with the applicable portions of Section 501 of the Standard Specifications.

The above work shall include the removal of the first section of pipe with the headwall. The removal of the first section of pipe will not be paid for separately but shall be included in the unit price Each for CONCRETE HEADWALL REMOVAL, and no additional compensation will be allowed due to the various sizes of pipes and headwalls.