




ADJUSTABLE TIE








CANOPY TIE




U BOLT TIE

540-22

THE CULVERT TIES SHALL BE INCLUDED IN THE COST OF THE CONCRETE PIPE CULVERTS OR THE PRECAST CONCRETE BOX CULVERT. THE MECHANICAL TIES SHALL BE ON THE OUTSIDE OF THE CULVERT. THE NUTS AND WASHERS SHALL BE PLACED ON THE INSIDE OF THE CULVERT AND COVERED WITH MASTIC JOINT SEALER CONFORMING TO ARTICLES 1055 OR 1056 IN THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.






PLACEMENT OF HOLES					
BOX CULVERT	PIPE SIZE	THREAD			
		DIAMETER			
FEET	INCHES	INCHES			
	12	5/8			
	15	ROLLED			
	18	THREADS			
	21	(SEE			
	24	NOTE 4)			
	27	,			
	30				
3 x 2	33				
3 x 3	36	3/4			
4 x 2	42	CUT			
4 x 3	48	OR			
4 x 4	54	ROLLED			
5 x 3	60				
5 x 4	66				
5 x 5	72				
6 x *	78				
7 x *	84	1			
8 x *	90	CUT			
9 x *	96	OR			
10 x *	102	ROLLED			
	108				
	120				
	132				
11 x *	138	1 1/4			
AND GREATER	AND GREATER				

NOTES:

- 1. HOLES SHALL BE CAST-IN OR DRILLED 16" FROM OUTSIDE EDGE OF JOINT.
- 2. NUTS AND WASHERS ARE NOT REQUIRED ON INSIDE OF 27" DIAMETER PIPE OR LESS.
- 3. TIES ARE NOT REQUIRED FOR BELL PIPE 24" AND SMALLER. ON OTHER SIZES TIE MAY BE INSERTED FROM INSIDE.
- 4. CUT THREADS MAY BE USED IF WASHER AND NUT ARE USED.
- 5. PIPE SIZE LISTED IS INSIDE DIAMETER OF ROUND PIPE OR EQUIVALENT DIAMETER OF PIPE ARCH OR ELLIPTICAL.
- 6. GALVANIZING OF TIES IS REQUIRED.







JSER NAME = ronald pohar DESIGNED -REVISED DRAWN REVISED CHECKED REVISED PLOT DATE = 3/18/2024 REVISED DATE

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

ME			OINTS BOX C		ONCRETE RTS
	SHEET	OF	SHEETS	STA.	TO STA.

SCALE:

F.A. RTE	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.	
			CONTRACT NO.			
ILLINOIS FED. A		ID PROJECT				