



QUANTITY OF CONCRETE
 SECTION A-A = 0.07 CU YD/FT
 8' SECTION OF CURB & GUTTER UP TO
 SECTION A-A = 0.75 CU YD

NOTE:
 CLASS SI CONCRETE SHALL BE USED THROUGHOUT.
 CURB AND GUTTER OUTLET SHALL BE TIED TO
 PAVEMENT SLAB WITH 2 TIE BARS, 30" LONG -
 30" CENTERS. OUTLET SHALL BE TIED TO CURB AND
 GUTTER AT CONTRACTION JOINTS AS SHOWN. GUTTER
 OUTLET AND PAVED DITCH SHALL BE REINFORCED WITH
 WIRE MESH HAVING A WEIGHT OF AT LEAST 58 LBS/SQ FT
 COST TO BE INCLUDED IN THE UNIT PRICE PER CU YD
 FOR CLASS SI CONCRETE (OUTLET).

CURB & GUTTER OUTLET, SPECIAL 606-8

MODEL: det 3 041616
 FILE: \\miller\paw\beventy.com\PI\DOT\Documents\DOT_offices\chicago\Detail\03_Detail\Revisions_2023\606-899_INCIDENTAL_CONSTRUCTION.dgn

USER NAME = anthony.grunstad	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100,000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 10/3/23	DATE -	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
										CONTRACT NO.	
										ILLINOIS FED. AID PROJECT	