

Effective July 1, 2016

Designer Note: Use on projects where traffic may be shifted to the shoulders or may choose to drive on shoulders and there are bridge approach pavements or paved shoulders with drainage structure frames and grates that may come loose when driven on.

SECURING DRAINAGE STRUCTURE GRATES

Prior to routing traffic onto the shoulders as shown in the staging plans, the Contractor shall secure gratings on shoulder inlets as directed by the Engineer. This work will not be paid for separately, but shall be included in the cost of the traffic control pay item.