

60200j

602.00j

Designer Note: Designer to include District CADD Standard for "Inlet-Manhole, G-1 Special and Modified" for precast slab top details. Designer to include special details in the plans.

**MANHOLE TO BE ADJUSTED WITH NEW TYPE G-1 FRAME AND GRATE**

Effective October 1, 1995

Revised January 1, 2007

This work shall consist of furnishing equipment, labor and material to remove the top of existing drainage structure, to place a precast slab, to mount a new G-1 frame and grate, and to construct Combination Concrete Curb and Gutter.

This work shall be completed in accordance with the applicable portions of Sections 602 and 606 of the Standard Specifications and details in the plans.

Add "Manhole to be Adjusted with New Type G-1 Frame and Grate" to Article 602.16 of the Standard Specifications. Delete the first paragraph of Articles 606.14 and 606.15 of the Standard Specifications.

Payment for transitional Combination Concrete Curb and Gutter will be included in "Manhole to be Adjusted with New Type G-1 Frame and Grate" in accordance with details in the plans.

This work will be paid for at the contract unit price Each for MANHOLE TO BE ADJUSTED WITH NEW TYPE G -1 FRAME AND GRATE.