

73300

733.00

Designer Note: Include in contracts with cantilever sign structures.

**RE-TIGHTENING ANCHOR BOLTS FOR CANTILEVER SIGN STRUCTURES**

Effective: April 25, 2014

After the cantilever sign structure has been installed with all required signs for a minimum of 30 calendar days, the Contractor shall re-tighten the anchor bolts to the original specifications shown on the plan details and/or Standard Specifications.