



Illinois Department of Transportation

To:	Studies and Plans Squads	PPM 80-01
From:	C. D. Latham	Revised By: Scott Neihart
Subject:	Conduit-Highway Lighting	
Date:	September 9, 1985	Revised Date: April 1, 2016

PLAN PREPARATION MEMORANDUM 80-01

On projects which have highway lighting included as part of the contract, quantities should be included in the plans for UNDERGROUND CONDUIT, PVC, 2" DIAMETER, for placement under Portland Cement Concrete Driveway Pavements where wiring is to be installed.

The conduit should be a minimum of 2 feet deep and extend a minimum of 2 feet beyond the edges of the driveway

A note should be included making the Contractor aware that when a driveway is built half at a time, the conduit will have to be placed half at a time.

80-01.doc