



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 7, 2026

SUBJECT: Route FAU 1373 (Belmont Avenue)
Section 17-00083-02-PV (Franklin Park)
Cook County
Contract No. 61K16
Item 002
January 16, 2026 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices.**
- 2. Revised Sheets 3, 8, 15 and 24 of the Plans.**
- 3. Revised page 2 of the Table of Content to the Special Provisions.**
- 4. Added page 143A to the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

LIGHT EMITTING DIODE (LED) SIGNAL HEAD AND OPTICALLY PROGRAMMED LED SIGNAL HEAD.....	122
LED SIGNAL FACE, LENS COVER.....	125
LIGHT EMITTING DIODE (LED) PEDESTRIAN SIGNAL HEAD.....	126
TRAFFIC SIGNAL BACKPLATE.....	128
DETECTOR LOOP	128
VIDEO VEHICLE DETECTION SYSTEM.....	130
RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT....	131
RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	132
ACCESSIBLE PEDESTRIAN SIGNALS.....	132
TEMPORARY TRAFFIC SIGNAL INSTALLATION	135
TEMPORARY TRAFFIC SIGNAL TIMING	142
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	142
CONCRETE MEDIAN REMOVAL.....	143
CHAIN LINK GATES (SPECIAL)	143A
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION.	144
LR 107-4 SPECIAL PROVISION FOR INSURANCE	146
LR 1030-2 LOCAL QUALITY ASSURANCE/QUALITY MANAGEMENT QC/QA.....	147
STORM WATER POLLUTION PREVENTION PLAN	149
D1 OP0042 TRAFFIC MANAGEMENT PLAN FORM	160
ILLINOIS ENVIRONMENTAL PROTECTION AGENCY LPC-663 FORMS	161

CHAIN LINK GATES (SPECIAL)

Description. This work shall be done in accordance with Section 664 of the Standard Specifications except as modified herein and by the details in the plans.

This work involves installing new chain link fence gates and posts.

The chain link fence gate will consist of 6ft tall sliding gates, rollers, counterweights, and all necessary components for the sliding gates. The Contractor shall submit proposed shop drawings for the gate to the Engineer for approval. An acceptance letter from the Engineer will be required before the new gates can be installed. The gates shall be installed per the manufacturer's recommendations. The Contractor shall provide temporary gates and fencing during the time between the removal of the existing fence and gates and installation of the new fence. The Contractor will be responsible for maintaining the temporary fence.

Method of Measurement: This work will not be paid for separately but included in the unit price per EACH for CHAIN LINK GATES (SPECIAL).

Basis of Payment: All labor, equipment, and materials required for this work shall be paid for at the contract unit price per each for CHAIN LINK GATES (SPECIAL) and no additional compensation will be allowed.

