

MODEL: Default
FILE NAME: c:\pwwork\pwwork\minder\bid1108322172415 Summary of Quantities.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	6-01211-0000	6-01211-0100
				NHPP FUNDING 80% FEDERAL 20% STATE	HSIP FUNDING 90% FEDERAL 10% STATE
				ROADWAY 0005	ROADWAY 0021
				RURAL	RURAL
* 78009024	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	94	94	
* 78011000	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	122	122	
* 78011030	GROOVING FOR RECESSED PAVEMENT MARKING 6"	FOOT	40,877	40,877	
* 78011125	GROOVING FOR RECESSED PAVEMENT MARKING 25"	FOOT	94	94	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	169	169	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	169	169	
					⚠
* X2020060	EXCAVATING AND GRADING EXISTING SHOULDER, (SPECIAL)	UNIT	267		267
* X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	5	5	
* X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3	3	
* Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
∅ Z0076600	TRAINEES	HOUR	1000	1000	
∅ Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	1000	1000	

* - INDICATES PAY ITEM REQUIRES A SPECIAL PROVISION

* SPECIALTY ITEM

∅ 0042

⚠ REVISED 1-2-2026

REV - MS

	USER NAME = brian.minder	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUNATITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -						322	43RS-10,SR	CHRISTIAN	23	5
		CHECKED -	REVISED -						CONTRACT NO. 72415				
	PLOT DATE = 10/17/2025	DATE -	REVISED -		SCALE: N/A		SHEET 3	OF 3	SHEETS	STA.	TO STA.		
									ILLINOIS		FED. AID PROJECT		

MODEL: Default
FILE NAME: c:\pwworking\minder\td110832272415 Schedules.dgn

PAVEMENT MARKING SCHEDULE																
				70300100 SHT TERM PVT MKG (FOOT)	70300150 SHT TERM PVT MKG REM (SQ FT)	78009000 MOD URETHANE PVT MKG- LT & SYMB (SQ FT)	78009005 MOD URETHANE PVT MKG- LINE5" (WHITE) (FOOT)	78009005 MOD URETHANE PVT MKG- LINE5" (YELLOW) (FOOT) NO PASS SB	78009005 MOD URETHANE PVT MKG- LINE5" (YELLOW) (FOOT) SKIP-DASH	78009005 MOD URETHANE PVT MKG- LINE5" (YELLOW) (FOOT) NO PASS NB	78009024 MOD URETHANE PVT MKG- LINE24" (FOOT)	78011000 GRV FOR RECSD PVT MKG, LET & SYMB (SQ FT)	78011030 GRV FOR RECSD PVT MKG, 6" (FOOT)	78011125 GRV FOR RECSD PVT MKG, 25" (FOOT)	78100100 RAISED REFL PVT MKR (EACH)	78300200 RAISED REFL PVT MKR REM (EACH)
	Sta.		Sta.	Length (Ft)												
US 51 NBEOP	63+20.00	to	64+50.00	130			130				28		130	28		
	64+50.00	to	119+70.00	5,520			5,520						5,520			
	120+30.00	to	145+41.00	2,511			2,511						2,511			
	145+70.00	to	199+28.00	5,358			5,358						5,358			
	200+00.00	to	200+27.00	27			27						27			
US 51 NBCL	63+20.00	to	71+32.00	812	244	81			203	812			1,015		10	10
	71+32.00	to	79+07.00	775	233	78		775	194				969		10	10
	79+07.00	to	81+65.00	258	77	26			65	258			323		3	3
	81+65.00	to	89+06.00	741	222	74		741	185				926		9	9
	89+06.00	to	96+63.00	757	227	76		757		757			1,514		9	9
	96+63.00	to	107+05.00	1,042	313	104			261	1,042			1,303		13	13
	107+05.00	to	113+11.00	606	182	61			152				152		8	8
	113+11.00	to	118+25.00	514	154	51			129	514			643		6	6
	118+25.00	to	128+86.00	1,061	318	106		1,061		1,061			2,122		13	13
	128+86.00	to	138+82.00	996	299	100		996	249				1,245		12	12
	138+82.00	to	145+45.00	663	199	66	61	663		663	33	61	1,326	33	8	8
	145+45.00	to	155+26.00	981	294	98	61	981	245		33	61	1,226	33	12	12
	155+26.00	to	200+27.00	4,501	1,350	450			1,125				1,125		56	56
US 51 SB EOP	63+20.00	to	64+50.00	130			130						130			
	64+50.00	to	79+80.00	1,530			1,530						1,530			
	80+70.00	to	119+60.00	3,890			3,890						3,890			
	120+35.00	to	145+25.00	2,490			2,490						2,490			
	145+54.00	to	172+70.00	2,716			2,716						2,716			
	173+40.00	to	200+27.00	2,687			2,687						2,687			
TOTALS				4,112	1,371	122	40,877				94	122	40,877	94	169	169



△ REVISED 1-2-2026

	USER NAME = brian.minder	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES				F.A.P. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -						322	43-10,SR	CHRISTIAN	23	10
		CHECKED -	REVISED -						CONTRACT NO. 72415				
	PLOT DATE = 10/17/2025	DATE -	REVISED -		SCALE: N/A		SHEET 2	OF 3	SHEETS	STA.	TO STA.		
					ILLINOIS FED. AID PROJECT								