

90% FED
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CLAY	EFFINGHAM
				ROADWAY	ROADWAY
				0005 RURAL	0005 RURAL
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	51583	2004	49579
40600372	LONGITUDINAL JOINT SEALANT, HALF-WIDTH	FOOT	87374	3340	84034
40600405	MATERIAL TRANSFER DEVICE	TON	15506	579	14927
40604164	POLYMERIZED HOT-MX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N90	TON	840	0	840
40604064	HOT-MX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N90	TON	840	0	840
40605034	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, 12.5, MIX "E", N80	TON	14001	579	13422
44000157	HOT-MX ASPHALT SURFACE REMOVAL, 2"	SQ YD	192267	7422	184845
44200565	CLASS A PATCHES, TYPE II, 11 INCH	SQ YD	48	24	24
44200571	CLASS A PATCHES, TYPE IV, 11 INCH	SQ YD	95	0	95
44200577	CLASS A PATCHES, TYPE II, 12 INCH	SQ YD	72	0	72
44200581	CLASS A PATCHES, TYPE III, 12 INCH	SQ YD	40	0	40
44200583	CLASS A PATCHES, TYPE IV, 12 INCH	SQ YD	74	0	74
44213000	PATCHING REINFORCEMENT	SQ YD	329	24	305
44213200	SAW CUTS	FOOT	1020	108	912
44213204	TIE BARS 3/4"	EACH	35	0	35

90% FED
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CLAY	EFFINGHAM
				ROADWAY	ROADWAY
				0005 RURAL	0005 RURAL
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1656	71	1585
48203100	HOT-MIX ASPHALT SHOULDERS	TON	8632	333	8299
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	79151	3340	75811
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	0.1	2.9
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	3	0.1	2.9
67100100	MOBILIZATION	L SUM	1	0.1	0.9
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2	0	2
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.1	0.9
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.1	0.9
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	0.1	0.9
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	0	1
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	14	14	0
70300100	SHORT TERM PAVEMENT MARKING	FOOT	7620	301	7319
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	2540	100	2440
70300211	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - PAINT	SQ FT	32	0	32
70300241	TEMPORARY PAVEMENT MARKING - LINE 6"- PAINT	FOOT	94527	3757	90770

MODEL: Summary of Quantities (Sheet)
FILE NAME: c:\paw\work\paw\illinois.gov\stacy.anderson@illinois.gov\stacy.anderson\105989D774C61-aitt-sq.dgn

△ REVISED 12-26-2025

REV - MS

F.A.I RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(25-6-1)RS-9 & (13-1)RS-3	*	32	3
ILLINOIS FED. AID PROJECT				

USER NAME = stacy.anderson	DESIGNED -	REVISED -
	DRAWN -	REVISED -
	CHECKED -	REVISED -
PLOT DATE = 11/7/2025	DATE -	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SUMMARY OF QUANTITIES	
SCALE:	SHEET 1 OF 2 SHEETS	STA.	TO STA.

*EFFINGHAM,CLAY

MODEL: Schedule [Sheet]
FILE NAME: c:\pwworking\lund\hd0910589\0774C61-sht-schedule.dgn

PAVING SCHEDULE											
STATION	TO	STATION	LENGTH	BITUMINOUS MATERIALS (TACK COAT)	LONGITUDINAL JOINT SEALANT, HALF WIDTH	HOT-MIX ASPHALT SHOULDERS	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, 1 L 9.5, MIX "D", N90	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX, IL 12.5, MIX "E" N80	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	AGGREGATE WEDGE SHOULDER, TYPE B	SHOULDER RYMBLE STRIPS, 16 INCH
NORTHBOUND			(FOOT)	(POUND)	(FOOT)	(TON)	(TON)	(TON)	(SQ YD)	(TON)	(EACH)
3310+13.00		3319+28.74	915.7	1098.9	1831.5	182.3		317.5	4070.0	39.1	1831.5
3319+28.74		4199+97.27	STATION EQUATION								
4199+97.27		4268+65.75	6868.5	8242.2	13737.0	1367.6		2381.1	30526.6	293.3	13737.0
4268+65.75		4270+90.08	STRUCTURE OMISSION								
4270+90.08		4305+99.41	3509.3	4211.2	7018.7	698.8		1216.6	15597.0	121.5	6355.6
RAMP D			1007.6	1358.9	2748.0	231.6	384.0		5499.8		
4305+99.41		4307+57.91	STRUCTURE OMISSION								
RAMP C			1494.1	1760.6	3852.0	358.8	455.5		7270.5		
4307+57.91		4554+42.81	24684.9	29621.9	49369.8	4915.0		8557.4	109710.7	1013.3	48409.8
4554+42.81		4554+62.41	STATION EQUATION								
4554+62.41		4582+79.08	2816.7	3380.0	5633.3	560.8		976.5	12518.5	120.3	5633.3
4582+79.08		4609+69.68	STATION EQUATION								
4609+69.68		4625+61.43	1591.8	1910.0	3183.5	316.9		551.8	7074.5	68.0	3183.5
TOTAL:			42889	51583	87374	8632	840	14001	192267	1656	79151



PAVEMENT MARKING SCHEDULE														
STATION	TO	STATION	LENGTH	SHORT TERM PAVEMENT MARKING	SHORT TERM PAVEMENT MARKING REMOVAL	THERMOPLASTIC PAVEMENT MARKING - LINE 6" (WHITE)	THERMOPLASTIC PAVEMENT MARKING - LINE 6" (YELLOW)	THERMOPLASTIC PAVEMENT MARKING - LINE 8" (WHITE)	THERMOPLASTIC PAVEMENT MARKING - LINE 12" (WHITE)	THERMOPLASTIC PAVEMENT MARKING - LINE 24" (WHITE)	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LINE 6" (WHITE)	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
NORTH BOUND			FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	EACH	EACH
3310+13.00		3319+28.74	915.7	171.1	57.0	915.7	915.7					229.0	23.0	23.0
3319+28.74		4199+97.27	STATION EQUATION											
4199+97.27		4268+65.75	6868.5	1283.6	427.9	6868.5	6868.5					1717.0	172.0	172.0
4268+65.75		4270+90.08	STRUCTURE OMISSION											
4270+90.08		4305+99.41	3509.3	581.6	193.9	2846.3	2846.3					1141.0	144.0	144.0
RAMP D			1007.6	110.2	36.7	1743.0	1028.0	839.0	64.0	38.0	32.0			
4305+99.41		4307+57.91	STRUCTURE OMISSION											
RAMP C			1494.1	167.8	55.9	2486.0	1382.0	1500.0						
4307+57.91		4554+42.81	24684.9	4481.7	1493.9	23725.0	23724.9					6172.0	618.0	618.0
4554+42.81		4554+62.41	STATION EQUATION											
4554+62.41		4582+79.08	2816.7	526.4	175.5	2816.7	2816.7					704.0	70.0	70.0
4582+79.08		4609+69.68	STATION EQUATION											
4609+69.68		4625+61.43	1591.8	297.5	99.2	1591.8	1591.8					398.0	40.0	40.0
TOTAL:			42889	7620	2540	42993	41174	2339	64	38	32	10361	1067	1067

⚠ REVISED 12-26-2025

	USER NAME = levi.lund	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					57	(25-6-1)RS-9 & (13-1)RS-3	*	32	8
		CHECKED -	REVISED -		CONTRACT NO. 74C61							
	PLOT DATE = 9/2/2025	DATE -	REVISED -		SCALE:	SHEET 1	OF 1 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		

*EFFINGHAM, CLAY