



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 8, 2026

SUBJECT FAP Routes 586/586A/592 (IL 162/IL 157)  
Project NHPP-STP-HSIP-6ATA(489)  
Section 51-1R  
Madison County  
Contract No. 76A46

Item No. 125, January 16, 2026 Letting  
Addendum B

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 14 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

## DETOUR SIGNING


Description: This work shall consist of furnishing, erecting, maintaining, covering, uncovering, and removing the required signs and changeable message signs as shown in the plans.

Materials: The materials used shall be in accordance with Section/Articles 1090-1091, 1093, 1006.29, and 1007.05 of the Standard Specifications. Signage for the proposed detour shall conform to Sections 701, 720-721, and 728- 730 of the Standard Specifications or as directed by the Engineer.

Construction Requirements: The Contractor shall furnish and erect detour signs at locations indicated in the plans. The signs shall be mounted with either metal or wood posts. At locations where the signs need to be placed within the pavement, a temporary mounting assembly will be allowed.

All signs, supports, hardware, materials, and labor shall be considered included in this work, and no additional compensation shall be allowed. The signs are to be in place and uncovered prior to any closure. When a detour is not in use, the detour signage shall be completely covered.

The signs and posts shall be removed when detours are no longer required. The Contractor shall return the area around the signs to its previous condition, which may include seeding, with no additional compensation.

Changeable message signs utilized for detour route notifications shall be paid for separately. 

Basis of Payment: This work will be paid for at the contract unit price per LUMP SUM for DETOUR SIGNING.

## PAINT PAVEMENT MARKING CURB

This work shall consist of painting a 6-inch stripe on the concrete curb as shown in the plans. Surface preparation and paint application shall be in accordance with Section 780 of the Standard Specifications.

Method Of Measurement: This work will be measured for payment in place in feet.

Basis Of Payment: This work will be paid for at the contract unit price per FOOT for PAINT PAVEMENT MARKING CURB.