

MODEL: S:\MODEL\NAMES
FILE NAME: c:\r\patrick-co-pw-bentley.com\patrick-co-pw-07\Documents\ILL_148_P\H2\CADD\data\CAD\sheet\ID978A09-Sht-SQ00.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED / 20% STATE	
				BOX CULVERT: SN 028-7138	
				0004	URBAN
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA	5	5	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28	28	
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	415	415	1
70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	FOOT	1245	1245	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	255	255	
70600241	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	2	2	
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	1	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	830	830	
78300201	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	277	277	1
X5012504	CONCRETE SLAB REMOVAL	SQ YD	75	75	
X5040150	PRECAST CONCRETE JUNCTION CHAMBER	EACH	2	2	
X5510011	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	1	1	
X5810103	MEMBRANE WATERPROOFING SYSTEM FOR BURIED STRUCTURES	SQ YD	227	227	

* SPECIALTY ITEM

1 REVISED 1-2-2026

REV - MS



PATRICK ENGINEERING INC.
65 EAST MONROE STREET
SUITE 3450
CHICAGO, IL 60603
www.rina-us.org
Design Firm License No. 154000409-0014

USER NAME = DT004	DESIGNED - DT	REVISED -
	DRAWN - DT	REVISED -
	CHECKED - KE	REVISED -
PLOT DATE = 10/16/2025	DATE - 10/16/2025	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
ILLINOIS ROUTE 148

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
726	127CR-1	FRANKLIN	42	8
CONTRACT NO. 78A09				
ILLINOIS FED. AID PROJECT				