

FUNDING SOURCE					LOCAL/STATE			LBFP
								80% FED 20 % LOCAL
CONSTRUCTION TYPE CODE					0004	0021	0042	0010
	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAINEES	STRUCTURAL
	550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	162	162			
	550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	81	81			
	550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	30	30			
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	514	514			
	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	156	156			
	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	205	205			
	550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	28	28			
	550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	211	211			
	550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	576	576			
	550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	175	175			
	550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	36	36			
	550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	13	13			
	55100100	STORM SEWER REMOVAL 4"	FOOT	43	43			
	55100400	STORM SEWER REMOVAL 10"	FOOT	6	6			
	55100500	STORM SEWER REMOVAL 12"	FOOT	404	404			
	55100700	STORM SEWER REMOVAL 15"	FOOT	355	355			
	55100900	STORM SEWER REMOVAL 18"	FOOT	50	50			
	55101200	STORM SEWER REMOVAL 24"	FOOT	576	576			
	55101600	STORM SEWER REMOVAL 36"	FOOT	545	545			
	55101800	STORM SEWER REMOVAL 42"	FOOT	155	155			

~ DENOTES SPECIALTY ITEM



USER NAME = aschaefer	DESIGNED - AJS/JRS	REVISED - 12/31/25 ADDENDUM #1
	DRAWN - JRS/PWN	REVISED -
PLOT SCALE = N.T.S.	CHECKED - AJS	REVISED -
PLOT DATE = 1/5/2026	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SEIL ROAD WIDENING
SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET 5 OF 12 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0403	21-00047-00-WR	WILL	149	8
		CONTRACT NO.	61M01	
ILLINOIS		FED. AID PROJECT		

FUNDING SOURCE					LOCAL/STATE			LBFP
								80% FED 20 % LOCAL
CONSTRUCTION TYPE CODE					0004	0021	0042	0010
	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAINEES	STRUCTURAL
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4			
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3			
	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4			
	60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2			
	60224456	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1			
	60224459	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3			
	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1			
	60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	1	1			
	60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	2	2			
	60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	2	2			
	60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6			
	60500040	REMOVING MANHOLES	EACH	5	5			
	60500050	REMOVING CATCH BASINS	EACH	13	13			
	60500060	REMOVING INLETS	EACH	3	3			
	60600605	CONCRETE CURB, TYPE B	FOOT	335	335			
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	470	470			
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3480	3480			
	60608552	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06	FOOT	845	845			
	60608562	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	245	245			
	60608582	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	185	185			

~ DENOTES SPECIALTY ITEM



USER NAME = aschaefer	DESIGNED - AJS/JRS	REVISED - 12/31/25 ADDENDUM #1
	DRAWN - JRS/PWN	REVISED -
PLOT SCALE = N.T.S.	CHECKED - AJS	REVISED -
PLOT DATE = 1/5/2026	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


SEIL ROAD WIDENING
SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET 7 OF 12 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0403	21-00047-00-WR	WILL	149	10
		CONTRACT NO.	61M01	
ILLINOIS		FED. AID PROJECT		

FUNDING SOURCE					LOCAL/STATE			LBFP
								80% FED 20 % LOCAL
CONSTRUCTION TYPE CODE					0004	0021	0042	0010
	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAINEES	STRUCTURAL
~	81301290	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 12" X 12" X 6"	EACH	2		2		
~	A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2			
~	81400200	HEAVY-DUTY HANDHOLE	EACH	2		2		
~	A2006520	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	4	4			
~	81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	9		9		
~	B2000772	TREE, AMELANCHIER X GRANDIFLORA AUTUMN BRILLIANCE (AUTUMN BRILLIANCE SERVICE BERRY), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	3	3			
~	81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	22900		22900		
~	B2001166	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	3	3			
~	81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	165		165		
~	B2001266	TREE, CORNUS ALTERNIFOLIA (PAGODA DOG WOOD), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	3	3			
~	82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP	EACH	1		1		
~	D2003760	EVERGREEN, THUJA OCCIDENTALIS (AMERICAN ARBORVITAE), 5' HEIGHT, BALLED AND BURLAPPED	EACH	28	28			
	X0321690	BRICK WALL REMOVAL	FOOT	65	65			
	X0326806	WASHOUT BASIN	L SUM	1	1			
	X0327036	BIKE PATH REMOVAL	SQ YD	125	125			
	X0327487	TRIAxIAL GEOGRID REINFORCEMENT, TYPE I	SQ YD	1615	1615			
	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	11	11			
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2	2			
	X4023000	TEMPORARY ACCESS (ROAD)	EACH	3	3			
	X4060280	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	300	300			
	X4200408	PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL)	SQ YD	434	434			
	X4400110	TEMPORARY PAVEMENT REMOVAL	SQ YD	225	225			
	X4420210	TEMPORARY PATCHING	SQ YD	500	500			
	X5021510	COFFERDAMS (SPECIAL)	EACH	2				2
~	X5091725	BICYCLE RAILING (SPECIAL)	FOOT	311				311

~ DENOTES SPECIALTY ITEM



USER NAME = aschaefer	DESIGNED - AJS/JRS	REVISED - 12/31/25 ADDENDUM #1
	DRAWN - JRS/PWN	REVISED -
PLOT SCALE = N.T.S.	CHECKED - AJS	REVISED -
PLOT DATE = 1/5/2026	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SEIL ROAD WIDENING
SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET 10 OF 12 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0403	21-00047-00-WR	WILL	149	13
		CONTRACT NO. 61M01		
ILLINOIS FED. AID PROJECT				

LEGEND

INLET FILTER OR
INLET & PIPE PROTECTION

SEEDING, CLASS 1A & WILDLIFE
FRIENDLY EROSION CONTROL BLANKET


SEEDING, CLASS 4A & WILDLIFE
FRIENDLY EROSION CONTROL BLANKET

SEEDING, CLASS 4B & WILDLIFE
FRIENDLY EROSION CONTROL BLANKET

TEMPORARY DITCH CHECK

PERIMETER EROSION
CONTROL BARRIER

NOTE: ALL SEEDING AREAS SHALL BE
PREPARED WITH A MINIMUM OF 6" OF TOPSOIL
UNLESS OTHERWISE NOTED IN THE TYPICAL SECTIONS



CL PROPOSED RAVEN ROAD

0002TE

PR. R.O.W. 0003

PROPOSED SEEDING SHOWN BETWEEN STA. 21+71
AND STA. 22+37 IS INTENDED TO BE PLACED
BELOW THE PROPOSED BRIDGE.

TREE (KENTUCKY COFFEETREE)
2 1/2" CALIPER, B&B - 2 EACH

TREE (AUTUMN BRILLIANCE SERVICE BERRY)
2 1/2" CALIPER, B&B - 3 EACH

240 SY STONE RIPRAP, CLASS A4, 1.5'

39 SY STONE RIPRAP, CLASS A3, 1.25'

TREE (PAGODA DOG WOOD)
6", B&B - 3 EACH

0003TE-A

CL PROPOSED SEIL ROAD

CL PROPOSED SEIL ROAD

SEIL RD

APPROX. R.O.W.

DUPAGE RIVER

MATCH LINE STA. 23+60

COFFERDAM (SPECIAL)
(SEE NOTE 1)

COFFERDAM (SPECIAL)
(SEE NOTE 1)

APPROX. R.O.W.

SEE SHEET 89
FOR PROPOSED BRIDGE PLAN

APPROX. EDGE OF
WATER (TYP.)

APPROX. LOCATION OF
CONCRETE WASHOUT BASIN
TO BE REMOVED
PRIOR TO STAGE 2
(SEE NOTE 2)

BEGIN IMPROVEMENT
STA 18+02.57

PR. R.O.W. 0001

- NOTES:
- THE LAYOUT/LIMITS OF THE PROPOSED COFFERDAMS ARE APPROXIMATE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE A DETAILED COFFERDAM PLAN PRIOR TO CONSTRUCTION. ALL WORK TO DESIGN, INSTALL, MAINTAIN AND REMOVE THE COFFERDAMS SHALL BE INCLUDED IN THE COST OF COFFERDAM (SPECIAL).
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROPERLY BARRICADING AND PROTECTING THE CONCRETE WASHOUT BASINS FROM PEDESTRIANS AND VEHICULAR TRAFFIC AT ALL TIMES. FINAL LOCATION OF THE BASINS SHALL BE APPROVED BY THE ENGINEER.
 - FINAL LAYOUT OF PROPOSED TREES SHALL BE APPROVED IN THE FIELD BY THE ENGINEER.

USER NAME = aschaefer	DESIGNED - AJS/JRS	REVISED - 12/31/25-ADDENDUM #1
	DRAWN - PWN/JRS	REVISED -
PLOT SCALE = 28'	CHECKED - AJS	REVISED -
PLOT DATE = 12/31/2025	DATE -	REVISED -

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0403	21-00047-00-WR	WILL	149	44
CONTRACT NO. 61M01				
ILLINOIS FED. AID PROJECT				