

MODEL: SQ01 [Sheet]
FILE NAME: c:\pw_work\wid01\illinois.gov_sergio.sema@illinois.gov\162D11026-sht-SQ0.dgn

SUMMARY OF QUANTITIES					TYPE CODE					
					URBAN	URBAN	URBAN	URBAN	URBAN	
					US 14 ROADWAY	US 14 TS	FRON. RD. ROADWAY	US 14 ROADWAY	IL 23 TS	
					80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% STATE	80% FED 20% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0005	0021	0005	0005	0021		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	8	8						
25200110	SODDING, SALT TOLERANT	SQ YD	8	8						
25200200	SUPPLEMENTAL WATERING	UNIT	1	1						
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	29755	27780		1975				
40600370	LONGITUDINAL JOINT SEALANT	FOOT	10892	9080		1812				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	69	62		7				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	191	191						
40603200	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50	TON	2264	2264						
40604060	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	TON	369			369				
40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	3458	3458						
42001300	PROTECTIVE COAT	SQ YD	35	35						
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	4388			4388				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	3496	3496						
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	37659	37659						
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	27			27				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	40			40				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	66			66				
44201875	CLASS D PATCHES, TYPE II, 19 INCH	SQ YD	247	247						
44201879	CLASS D PATCHES, TYPE III, 19 INCH	SQ YD	371	371						
44201781	CLASS D PATCHES, TYPE IV, 19 INCH	SQ YD	618	618						
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	313	241		72				

SUMMARY OF QUANTITIES					TYPE CODE					
					URBAN	URBAN	URBAN	URBAN	URBAN	
					US 14 ROADWAY	US 14 TS	FRON. RD. ROADWAY	US 14 ROADWAY	IL 23 TS	
					80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% STATE	80% FED 20% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0005	0021	0005	0005	0021		
60250200	CATCH BASINS TO BE ADJUSTED	EACH	5	5						
60618320	CONCRETE MEDIAN SURFACE, 6 INCH	SQ FT	70	70						
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	13135	13135						
67100100	MOBILIZATION	L SUM	1	0.8		0.2				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	8223	7496		727				
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	371	317		54				
70300211	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - PAINT	SQ FT	874	874						
70300221	TEMPORARY PAVEMENT MARKING - LINE 4"- PAINT	FOOT	44546	35916		8630				
70300241	TEMPORARY PAVEMENT MARKING - LINE 6"- PAINT	FOOT	6676	6676						
70300251	TEMPORARY PAVEMENT MARKING - LINE 8"- PAINT	FOOT	3946	3946						
70300261	TEMPORARY PAVEMENT MARKING - LINE 12"- PAINT	FOOT	3088	3088						
70300281	TEMPORARY PAVEMENT MARKING - LINE 24"- PAINT	FOOT	742	742						
70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	FOOT	112	959		163				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	437	437						
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	22273	17958		4315				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3338	3338						
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1973	1973						
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1544	1544						
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	371	371						
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	227	227						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	227	227						
78004630	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LINE 6"	FOOT	2157	2157						
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		2					

 REVISED SHEET 5/29/2026 * = SPECIALTY ITEM

	USER NAME = sergio.sema	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES US 14 AND US 14 - FRONTAGE RD.			F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					305	2025-2102-RS	MCHENRY	32	3
		CHECKED -	REVISED -					CONTRACT NO. 80C45				
	PLOT DATE = 3/19/2026	DATE -	REVISED -					ILLINOIS FED. AID PROJECT				
SCALE:		SHEET 1	OF 2	SHEETS	STA.	TO STA.						