

Pre-Demolition Asbestos Survey Report

Single-Family Residence – IDOT Work Order 51

203 East Fayette Avenue

Effingham, Effingham County, Illinois 62401


June 4, 2026 | Terracon Project Number: 11267090



Prepared for:

Illinois Department of Transportation (IDOT)

Springfield, Illinois



Prepared by:

Terracon Consultants, Inc.

Glendale Heights, Illinois



Nationwide
[Terracon.com](https://www.terracon.com)

- Facilities
- Environmental
- Geotechnical
- Materials



192 Exchange Boulevard
Glendale Heights, Illinois 60139-2089
P 630-717-4263
F 630-357-9489
Terracon.com

June 4, 2026

Illinois Department of Transportation
Bureau of Land Acquisition
2300 South Dirksen Parkway
Springfield, Illinois 62764

Attn: Mr. Travis Richardson
P: (217) 782-8687
E: Travis.Richardson@illinois.gov

RE: Pre-Demolition Asbestos Survey Report
Single-Family Residence – IDOT Work Order (WO) 51
203 East Fayette Avenue
Effingham, Effingham County, Illinois 62401
Terracon Project No. 11267090

IDOT Work Order No.: 51
IDOT Job No.: R-97-004-20
IDOT Contract No.: 74A02
Parcel: 7004125

Dear Mr. Richardson:

The purpose of this report is to present the results of the asbestos survey conducted by Terracon Consultants, Inc. (Terracon) on April 21, 2026, regarding the existing building (a vacant single-family residence) located at 203 East Fayette Avenue in Effingham, Illinois. This survey was conducted in accordance with Terracon's Work Plan, Terracon Project number 11267090, dated April 1, 2026, and IDOT Work Order 51/IDOT Job number R-97-004-20, authorized April 9, 2026. We understand the survey for asbestos-containing materials (ACM) is being conducted due to the planned demolition of the building.

Asbestos-containing materials (ACM) were identified as a result of this survey. Please refer to the attached report for further detail.

Terracon appreciates the opportunity to provide this service to IDOT. If you have any questions regarding this report, please contact us at 630-717-4263.

Sincerely,
Terracon Consultants, Inc.

A handwritten signature in black ink, reading "Christopher Heynen".

Christopher J. Heynen
Senior Staff Scientist

A handwritten signature in black ink, reading "Joseph A. Tussey".

Joseph A. Tussey, CHMM
Authorized Project Reviewer

Table of Contents

1.0	Introduction	1
1.1	Project Objective	1
1.2	Reliance.....	1
2.0	Building Description.....	2
3.0	Field Activities	2
3.1	Visual Assessment	2
3.2	Physical Assessment.....	2
3.3	Sample Collection	3
3.4	Sample Analysis.....	3
4.0	Regulatory Overview	3
5.0	Findings	4
6.0	General Comments.....	5

Appendices

APPENDIX A	Asbestos Survey Sample Summary
APPENDIX B	Confirmed Asbestos-Containing Materials
APPENDIX C	Asbestos Analytical Laboratory Data
APPENDIX D	Licenses and Certifications
APPENDIX E	Photographs
APPENDIX F	Sample/Asbestos Location Maps



PRE-DEMOLITION ASBESTOS SURVEY REPORT
Single-Family Residence – IDOT WO 51
203 East Fayette Avenue
Effingham, Effingham County, Illinois 602401
Terracon Project No. 11267090
June 4, 2026

1.0 Introduction

Terracon Consultants, Inc. (Terracon) conducted an asbestos survey of the existing building (a vacant single-family residence) located at 203 East Fayette Avenue in Effingham, Illinois that is planned for demolition. A detached two-car garage is also present on the property, but the garage is not currently planned for demolition and was therefore not included in this survey. The survey was conducted on April 21, 2026, by State of Illinois Department of Public Health (IDPH) licensed building inspectors in accordance with Terracon's Work Plan, Terracon Project number 11267090, dated April 1, 2026, and IDOT Work Order 51/IDOT Job number R-97-004-20, authorized April 9, 2026. Accessible building components were inspected, and homogeneous areas of suspect asbestos-containing materials (ACM) were visually identified and documented. Although reasonable effort was made to inspect accessible suspect materials, additional suspect but unsampled materials could be located in walls, in voids or in other concealed areas. Bulk samples from suspect ACM were collected in accordance with the sampling protocols outlined in United States Environmental Protection Agency (USEPA) 40 Code of Federal Regulations (CFR) Part 763-Asbestos, Subpart E-Asbestos-Containing Materials in Schools (40 CFR 763; known as the Asbestos Hazard Emergency Response Act [AHERA]). Collected bulk samples were delivered to a National Voluntary Laboratory Accreditation Program (NVLAP) accredited laboratory for analysis by polarized light microscopy (PLM).

1.1 Project Objective

We understand this survey was requested due to the planned demolition of the existing single-family residential building located at 203 East Fayette Avenue in Effingham, Illinois. USEPA regulation 40 CFR 61, Subpart M, National Emission Standards for Hazardous Air Pollutants (NESHAP); IDPH regulations; and Illinois Environmental Protection Agency (IEPA) prohibit the release of asbestos fibers to the atmosphere during renovation and demolition activities. The asbestos NESHAP and IDPH require that regulated and potentially regulated ACM be identified, classified, and quantified prior to planned renovation and demolition activities.

1.2 Reliance

This report is for the exclusive use of IDOT (Client) for the project being discussed. Reliance by any other party on this report is prohibited without written authorization of Terracon and the Client. Reliance on this report by the Client and all authorized parties will be subject to the terms, conditions, and limitations stated in the proposal, this report, and the agreement between

Terracon and the Client. The limitations of liability defined in the agreement is the aggregate limit of Terracon's liability to the Client.

2.0 Building Description

The existing building located at 203 East Fayette Avenue in Effingham, Illinois is a vacant single-family residence. The building is a one-story structure with finished attic and basement, totaling approximately 4,500 square feet of interior floor space and was constructed circa 1910. The exterior walls consist of brick and siding with a pitched shingled roof. Interior wall finishes consist of finished drywall and plaster. Flooring finishes consist of hardwood floors, vinyl floor tiles, and vinyl sheet flooring. Ceiling finishes consist of finished drywall, plaster, and ceiling tiles. Suspect asbestos-containing thermal system insulation (TSI) was not readily observed within the building (although unknown/concealed TSI may exist within inaccessible cavities). Heating is provided by a boiler in the basement. There is no air conditioning for the building. A detached two-car garage is present on the property, but the garage is not currently planned for demolition and was therefore not included in this survey.

3.0 Field Activities

The survey was conducted by Mr. Chris Heynen and Ms. Ashly Zwolinski, who are IDPH-licensed asbestos building inspectors (license # 100-19246 and 100-20242, respectively). Copies of their licenses are attached in Appendix D. The asbestos survey was conducted in accordance with the sampling protocols outlined in USEPA 40 CFR 763, Subpart E, Section 763.86 - AHERA. A summary of the survey activities follows.

3.1 Visual Assessment

Terracon's survey activities began with visual observation of accessible building materials to identify homogeneous areas and quantify materials suspected of containing asbestos (suspect ACM). A homogeneous area consists of materials that appear similar throughout in terms of color and texture. Homogeneous areas of suspect ACM were visually identified and documented. Although reasonable effort was made to inspect accessible suspect materials, additional suspect, but unsampled, materials could be located in walls, voids or in other concealed areas. Materials identified as glass, wood, or metal were not considered suspect ACM.

3.2 Physical Assessment

A physical assessment of each accessible homogeneous area of suspect ACM was conducted to assess the friability and condition of the materials. A friable material is defined by the USEPA as a material that can be crumbled, pulverized, or reduced to powder by hand pressure when dry. Friability was assessed by physically touching suspect materials.

3.3 Sample Collection

Based on results of the visual assessment, bulk samples from suspect ACM were collected in accordance with USEPA sampling protocols. Random samples of suspect materials were collected in each homogeneous area. The bulk samples were collected using wet methods, as applicable, to reduce the potential for fiber release. Samples were placed in sealable containers and labeled with unique sample numbers.

The selection of sample locations and frequency of sampling were based on Terracon's observations and the assumption that like materials in the same area are homogeneous in content.

Terracon collected a total of 55 bulk samples from 17 homogeneous areas of suspect ACM during this survey. The homogeneous areas of suspect ACM identified and sampled during the survey are listed in Appendix A. Photo examples of each homogeneous area of suspect ACM are included in Appendix E. Appendix F includes sample location maps (not to scale, for informational purposes only).

3.4 Sample Analysis

Bulk samples were submitted under chain of custody to Moody Labs, LLC (Moody) of Farmers Branch, Texas, a laboratory accredited for bulk asbestos analysis under NVLAP (laboratory number 102056-0) for analysis by PLM with dispersion staining techniques per USEPA's *Method for the Determination of Asbestos in Bulk Building Materials* (600/R-93-116). The percentage of asbestos, if present, was determined by microscopic visual estimation. Additionally, per Client request, if PLM results of flooring material samples were reported with asbestos not detected or detected at trace level, one sample from each homogeneous area of suspect asbestos-containing flooring material was re-analyzed using transmission electron microscopy (TEM) after gravimetric reduction in accordance with USEPA Method for the Determination of Asbestos in Bulk Building Materials (600/R-93/116 – Section 2.5.5.1). The laboratory analytical reports are included in Appendix C. A copy of Moody's NVLAP accreditation is provided in Appendix D.

4.0 Regulatory Overview

The asbestos NESHAP (40 CFR 61, Subpart M) regulates asbestos fiber emissions and asbestos waste disposal practices. It also requires the identification and classification of existing materials prior to demolition or renovation activity. Under NESHAP, ACMs are classified as friable, Category I nonfriable, or Category II nonfriable ACM. Friable materials are those that, when dry, may be crumbled, pulverized, or reduced to powder by hand pressure. Category I nonfriable ACM includes packings, gaskets, resilient floor coverings, and asphalt roofing products containing more than 1% asbestos. Category II nonfriable ACMs are any materials other than Category I materials that contain more than 1% asbestos. Friable ACMs and Category I and Category II nonfriable ACMs that are in poor condition and have become friable; will be subjected to drilling, sanding, grinding, cutting, or abrading; or could be crushed or pulverized during anticipated renovation or demolition activities are considered regulated ACM (RACM).

In Illinois, asbestos activities are regulated by the IEPA and IDPH. IEPA regulates asbestos fiber emissions under Illinois Administrative Code (IAC) 35 Part 228 Asbestos. For large projects (equal to and greater than 160 square feet and/or 260 linear feet) and demolition projects, the owner or operator must provide the IEPA with written notification and payment of applicable fees for removal activities at least 10 working days prior to the commencement of asbestos abatement activities.

IDPH regulates asbestos abatement activities in schools and other buildings under 77 IAC 855 Asbestos Abatement for Public and Private Schools and Commercial and Public Buildings in Illinois. Under 77 IAC 855.100 License Requirements, IDPH requires that any asbestos-related activity conducted in schools be performed by personnel licensed by the IDPH. This includes asbestos workers, supervisors, inspectors, management planners, project designers, project managers, air sampling professionals, and contractors. 77 IAC 855 specifies work practices and controls for all schools.

The Occupational Safety and Health Administration (OSHA) asbestos standard for the construction industry (29 CFR 1926.1101) regulates workplace exposure to asbestos during ACM removal. The OSHA standard requires that employee exposure to airborne asbestos fibers be maintained below the permissible exposure limits (PELs) of 0.1 asbestos fiber per cubic centimeter of air (0.1 f/cc) as an 8-hour time-weighted average (TWA) or 1.0 f/cc as a 30-minute excursion limit. The OSHA standard classifies the types of construction and maintenance activities that could disturb ACM and specifies work practices and precautions that employers must follow when engaging in each class of regulated work.

The above overview is not intended to be inclusive of all potentially pertinent regulatory information. The relevant city, state, USEPA, and OSHA standards should be consulted prior to undertaking activities involving demolition, renovation, or maintenance impacting ACMs.

5.0 Findings

Based on sampling and analysis performed for this survey, the presence of ACMs were identified regarding the existing vacant single-family residence located at 203 East Fayette Avenue, Effingham, Illinois. A table listing the identified ACMs is included in Appendix B.

Appendix A includes a sample summary with results. The laboratory analytical report is provided in Appendix C. The asbestos inspectors' licenses are included in Appendix D and photographs are provided in Appendix E. Sample location maps are included in Appendix F.

Based on the findings of the survey, Terracon offers the following:

- Identified ACMs should be removed and disposed of by an IDPH-licensed asbestos abatement contractor prior to the demolition activity that would disturb them in accordance with federal, state, and local asbestos regulations. Terracon recommends that an IDPH-licensed asbestos professional should represent the responsible party/Client on-site during abatement activities to

ensure that project activities are conducted in accordance with the scope of work and applicable rules and regulations.

- Following asbestos removal, final air clearance should be performed in accordance with applicable IDPH regulations.
- In addition, the possibility exists that additional suspect ACM is present that was not identified herein. Any suspect ACM not previously identified should be sampled to allow laboratory analysis to confirm the presence or absence of asbestos.

6.0 General Comments

The results, findings, and conclusions expressed in the report are based only on conditions that were noted during Terracon's April 21, 2026 survey of the existing single-family residential structure located at 203 East Fayette Avenue, Effingham, Illinois. The selection of sample locations and frequency of sampling were based on Terracon's observations and the assumption that like materials in the same area are homogeneous in content. Unidentified ACMs could be located in walls, in voids, or in other concealed areas or areas where investigation was not feasible.

This survey was conducted in a manner consistent with the level of care and skill ordinarily exercised by members of the profession currently practicing under similar conditions in the same locale. The results, findings, and conclusions expressed in this report are based on conditions observed during Terracon's survey of the building. The information contained in this report is relevant to the date on which this survey was performed and may not represent conditions at a later date. This report has been prepared on behalf of and exclusively for use by IDOT for specific application to their project as discussed. This report is not a bidding document. Contractors or consultants reviewing this report must draw their own conclusions regarding quantities of ACM and any further investigation or remediation deemed necessary. Terracon does not warrant the work of regulatory agencies, laboratories or other third parties supplying information that may have been used in the preparation of this report. No warranty, express or implied is made.

APPENDIX A

ASBESTOS SURVEY SAMPLE SUMMARY Single-Family Residence – IDOT WO 51 203 East Fayette Avenue Effingham, Effingham County, Illinois 62401 Terracon Project No. 11267090

Sample No.	Material Description	Material Location	Sample Location	Lab Result
51-1-1	Hard layered plaster walls and ceilings (tan bottom coat and tan top coat)	Throughout ground floor	North bedroom closet wall	None-Detected (ND)-bottom plaster ND-top plaster
51-1-2			North bedroom closet wall	ND-bottom plaster ND-top plaster
51-1-3			South bedroom closet wall	ND-bottom plaster ND-top plaster
51-1-4			South bedroom closet wall	ND-bottom plaster ND-top plaster
51-1-5			South bedroom wall	ND-bottom plaster ND-top plaster
51-1-6			Ground floor hallway closet ceiling	ND-bottom plaster ND-top plaster
51-1-7			Ground floor hallway closet ceiling	ND-bottom plaster ND-top plaster
51-2-8	Tan felt paper under wood flooring	Throughout ground floor	Living room register	ND-paper
51-2-9			Living room register	ND-paper
51-2-10			Living room register	ND-paper
51-3-11	Tan mastic on wood flooring	Dining room	Dining room	ND
51-3-12			Dining room	ND
51-3-13			Dining room	ND
51-4-14		Living room	Living room	ND

Sample No.	Material Description	Material Location	Sample Location	Lab Result
51-4-15	1' X 1' white smooth tongue and groove ceiling tile (no glue)		Living room	ND
51-4-16			Living room	ND
51-5-17	1' X 1' white pinhole tongue and groove ceiling tile (no glue)	Dining room, ground floor north bedroom	Dining room	ND
51-5-18			Dining room	ND
51-5-19			North bedroom	ND
51-6-20	Beige square pattern vinyl sheet flooring	Ground floor bathroom	Bathroom	ND-sheet flooring (by TEM)
51-6-21			Bathroom	ND-sheet flooring
51-6-22			Bathroom	ND-sheet flooring
51-7-23	Drywall, joint compound	Ground floor bathroom walls, walls and ceilings throughout 2 nd floor	Ground floor bathroom wall	ND-drywall material ND-joint Compound
51-7-24			2 nd floor ceiling-south	ND-drywall material 2 % Chrysotile-joint compound
51-7-25			2nd floor wall-north	ND-drywall material 2 % Chrysotile-joint compound
51-8-26	Beige rectangle pattern vinyl sheet flooring and clear mastic	Kitchen	Kitchen	ND-sheet flooring (by TEM) ND-clear mastic
51-8-27			Kitchen	ND-sheet flooring ND-clear mastic
51-8-28			Kitchen	ND-sheet flooring ND-clear mastic
51-9-29	Tan exterior window glazing	Kitchen windows, dining room windows, basement windows, 2 nd floor windows	Basement south window	ND-window glazing
51-9-30			Kitchen window	2 % Chrysotile-window glazing

Sample No.	Material Description	Material Location	Sample Location	Lab Result
51-9-31			2 nd floor west window	2 % Chrysotile-window glazing
51-10-32	Blue and beige octagon pattern vinyl sheet flooring with light gray fiber backing and clear mastic	Stairs to basement	Stairs to basement	ND-sheet flooring (by TEM) ND-fiber backing ND-clear mastic
51-10-33			Stairs to basement	ND-sheet flooring ND-fiber backing ND-clear mastic
51-10-34			Stairs to basement	ND-sheet flooring ND-fiber backing ND-clear mastic
51-11-35	Gray boiler flue cement	Basement chimney	Basement chimney	ND
51-11-36			Basement chimney	ND
51-11-37			Basement chimney	ND
51-12-38	9" X 9" brown with black streaks vinyl floor tile and black mastic over felt/tar paper	Stairs to 2 nd floor, center portion of 2 nd floor, 2 nd floor bathroom, 2 nd floor hallway	Center portion of 2 nd floor	5 % Chrysotile-floor tile ND-black mastic ND-felt/tar paper
51-12-39			Center portion of 2 nd floor	5 % Chrysotile-floor tile ND-black mastic ND-felt/tar paper
51-12-40			2 nd floor hallway	5 % Chrysotile-floor tile ND-black mastic ND-felt/tar paper
51-13-41	9" X 9" green with beige and black streaks vinyl floor tile	North portion of 2 nd floor	North portion of 2 nd floor	5 % Chrysotile-floor tile ND-black mastic ND-felt/tar paper

Sample No.	Material Description	Material Location	Sample Location	Lab Result
51-13-42	and black mastic over felt/tar paper		North portion of 2 nd floor	5 % Chrysotile-floor tile ND-black mastic ND-felt/tar paper
51-13-43			North portion of 2 nd floor	5 % Chrysotile-floor tile ND-black mastic ND-felt/tar paper
51-14-44	Beige boiler flue cement with gray insulation (additional insulation may be hidden behind cement)	Basement chimney	Basement chimney	ND-cement 20 % Chrysotile-insulation
51-14-45			Basement chimney	ND-cement 20 % Chrysotile-insulation
51-14-46			Basement chimney	ND-cement 20 % Chrysotile-insulation
51-15-47	Red brick and gray mortar	Exterior façade	Exterior façade	ND-brick ND-mortar
51-15-48			Exterior façade	ND-brick ND-mortar
51-15-49			Exterior façade	ND-brick ND-mortar
51-16-50	Black tar paper with tan paper layer	Under wood siding, under vinyl siding	South	ND-tar paper ND-paper
51-16-51			South	ND-tar paper ND-paper
51-16-52			South	ND-tar paper ND-paper
51-17-53	White/black asphalt roof shingles and underly black tar paper	Roof field	Southwest	ND-roofing shingles ND-roofing tars ND-tar paper
51-17-54			Southwest	ND-roofing shingles ND-roofing tars ND-tar paper



Sample No.	Material Description	Material Location	Sample Location	Lab Result
51-17-55			Southwest	ND-roofing shingles ND-roofing tars ND-tar paper

APPENDIX B

CONFIRMED ASBESTOS-CONTAINING MATERIALS Single-Family Residence – IDOT WO 51 203 East Fayette Avenue Effingham, Effingham County, Illinois 62401 Terracon Project No. 11267090

HA No.	Description	Material Location	Percent / Type Asbestos	NESHAP Classification	Condition	Estimated Quantity*
7	Joint compound within the drywall system walls and ceilings	Ground floor bathroom walls, walls and ceilings throughout 2nd floor	2% Chrysotile-joint compound	RACM	Good	5,000 square feet (SF)
9	Tan exterior window glazing	Kitchen windows, dining room windows, basement windows, 2nd floor windows	2% Chrysotile-window glazing	Category II Non-friable	Good	25 SF
12	9" X 9" brown with black streaks vinyl floor tile over non-ACM black mastic and non-ACM felt/tar paper	Stairs to 2nd floor, center portion of 2nd floor, 2nd floor bathroom, 2nd floor hallway	5% Chrysotile-floor tile	Category I Non-friable	Good	400 SF
13	9" X 9" green with beige and black streaks vinyl floor tile over non-ACM black mastic and non-ACM felt/tar paper	North portion of 2nd floor	5% Chrysotile-floor tile	Category I Non-friable	Good	200 SF
14	Gray insulation with non-ACM beige boiler flue cement (additional insulation may be hidden behind cement)	Basement chimney	20% Chrysotile-insulation	RACM	Good	1 SF

*Estimated quantities are based on a cursory field evaluation, and actual quantities may vary especially if ACMs are present in hidden and/or inaccessible areas not evaluated as part of this survey. This is not a bidding document; contractors would be responsible for drawing their own conclusions regarding quantities present.



RACM: Includes friable ACM, Category I non-friable ACM that has become friable, Category I nonfriable ACM that will be or has been subjected to sanding, grinding, cutting, or abrading, or Category II non-friable ACM that has a high probability of becoming or has become crumbled, pulverized, or reduced to powder by the forces expected to act on the material in the course of demolition or renovation operations.

Category I Non-friable: Includes asbestos-containing packings, gaskets, asphaltic roofing products, resilient flooring, and associated mastic containing more than 1% asbestos.

Category II Non-friable: Includes any material, excluding Category I non-friable ACM, containing more than 1% asbestos that, when dry, cannot be crumbled, pulverized, or reduced to powder by hand pressure.

APPENDIX C

ASBESTOS ANALYTICAL LABORATORY DATA



PLM Summary Report

NVLAP Lab Code 102056-0

TDSHS License No. 300084

2051 Valley View Lane

Farmers Branch, TX 75234 Phone: (972) 241-8460

Client : Terracon - Glendale Heights
Project : IDOT W051, 203 E. Fayette Ave., Effingham, IL
Project # : 11267090
Identification : Asbestos, Bulk Sample Analysis
Test Method : Polarized Light Microscopy / Dispersion Staining (PLM/DS)
EPA Method 600 / R-93 / 116

Lab Job No. : 26B-04956
Report Date : 05/07/2026
Sample Date : 04/21/2026

Page 1 of 5

On 4/27/2026, fifty five (55) bulk material samples were submitted by a representative of Terracon - Glendale Heights for asbestos analysis by PLM/DS. The PLM Detail Report is attached; additional information may be found therein. The results are summarized below:

Sample Number	Client Sample Description / Location	Asbestos Content
51-1-1	Plaster Walls and Ceilings, North Bedroom Closet Wall	None Detected - Bottom Plaster None Detected - Top Plaster
51-1-2	Plaster Walls and Ceilings, North Bedroom Closet Wall	None Detected - Bottom Plaster None Detected - Top Plaster
51-1-3	Plaster Walls and Ceilings, South Bedroom Closet Wall	None Detected - Bottom Plaster None Detected - Top Plaster
51-1-4	Plaster Walls and Ceilings, South Bedroom Closet Wall	None Detected - Bottom Plaster None Detected - Top Plaster
51-1-5	Plaster Walls and Ceilings, South Bedroom Wall	None Detected - Bottom Plaster None Detected - Top Plaster
51-1-6	Plaster Walls and Ceilings, Ground Floor Hallway Closet Ceiling	None Detected - Bottom Plaster None Detected - Top Plaster
51-1-7	Plaster Walls and Ceilings, Ground Floor Hallway Closet Ceiling	None Detected - Bottom Plaster None Detected - Top Plaster
51-2-8	Paper under Wood Flooring, Living Room Register	None Detected - Paper
51-2-9	Paper under Wood Flooring, Living Room Register	None Detected - Paper
51-2-10	Paper under Wood Flooring, Living Room Register	None Detected - Paper
51-3-11	Mastic (Tan) on Wood Flooring, Dining Room	None Detected - Tan Mastic None Detected - Wood Flooring
51-3-12	Mastic (Tan) on Wood Flooring, Dining Room	None Detected - Tan Mastic None Detected - Wood Flooring
51-3-13	Mastic (Tan) on Wood Flooring, Dining Room	None Detected - Tan Mastic None Detected - Wood Flooring
51-4-14	1' x 1' Ceiling Tile (White, Smooth, Tongue and Groove), No Glue, Living Room	None Detected - Acoustic Tile
51-4-15	1' x 1' Ceiling Tile (White, Smooth, Tongue and Groove), No Glue, Living Room	None Detected - Acoustic Tile



PLM Summary Report

NVLAP Lab Code 102056-0

TDSHS License No. 300084

2051 Valley View Lane

Farmers Branch, TX 75234 Phone: (972) 241-8460

Client : Terracon - Glendale Heights
Project : IDOT W051, 203 E. Fayette Ave., Effingham, IL
Project # : 11267090
Identification : Asbestos, Bulk Sample Analysis
Test Method : Polarized Light Microscopy / Dispersion Staining (PLM/DS)
EPA Method 600 / R-93 / 116

Lab Job No. : 26B-04956
Report Date : 05/07/2026
Sample Date : 04/21/2026

Page 2 of 5

On 4/27/2026, fifty five (55) bulk material samples were submitted by a representative of Terracon - Glendale Heights for asbestos analysis by PLM/DS. The PLM Detail Report is attached; additional information may be found therein. The results are summarized below:

Sample Number	Client Sample Description / Location	Asbestos Content
51-4-16	1' x 1' Ceiling Tile (White, Smooth, Tongue and Groove), No Glue, Living Room	None Detected - Acoustic Tile
51-5-17	1' x 1' Ceiling Tile (White, Pinhole, Tongue and Groove), No Glue, Dining Room	None Detected - Acoustic Tile
51-5-18	1' x 1' Ceiling Tile (White, Pinhole, Tongue and Groove), No Glue, Dining Room	None Detected - Acoustic Tile
51-5-19	1' x 1' Ceiling Tile (White, Pinhole, Tongue and Groove), No Glue, North Bedroom	None Detected - Acoustic Tile
51-6-20	Vinyl Sheet Flooring (Beige Square Pattern), Bathroom	None Detected - Sheet Flooring
51-6-21	Vinyl Sheet Flooring (Beige Square Pattern), Bathroom	None Detected - Sheet Flooring
51-6-22	Vinyl Sheet Flooring (Beige Square Pattern), Bathroom	None Detected - Sheet Flooring
51-7-23	Drywall, Joint Compound, Ground Floor Bathroom Wall	None Detected - Drywall Material None Detected - Joint Compound
51-7-24	Drywall, Joint Compound, 2nd Floor Ceiling, South	None Detected - Drywall Material 2% Chrysotile - Joint Compound
51-7-25	Drywall, Joint Compound, 2nd Floor Wall, North	None Detected - Drywall Material 2% Chrysotile - Joint Compound
51-8-26	Vinyl Sheet Flooring (Beige Rectangle Pattern), Adhesive (Clear), Kitchen	None Detected - Sheet Flooring None Detected - Clear Adhesive
51-8-27	Vinyl Sheet Flooring (Beige Rectangle Pattern), Adhesive (Clear), Kitchen	None Detected - Sheet Flooring None Detected - Clear Adhesive
51-8-28	Vinyl Sheet Flooring (Beige Rectangle Pattern), Adhesive (Clear), Kitchen	None Detected - Sheet Flooring None Detected - Clear Adhesive
51-9-29	Exterior Window Glazing (Tan), Basement South Window	None Detected - Window Glazing
51-9-30	Exterior Window Glazing (Tan), Kitchen Window	2% Chrysotile - Window Glazing
51-9-31	Exterior Window Glazing (Tan), 2nd Floor West Window	2% Chrysotile - Window Glazing



PLM Summary Report

NVLAP Lab Code 102056-0

TDSHS License No. 300084

2051 Valley View Lane

Farmers Branch, TX 75234 Phone: (972) 241-8460

Client : Terracon - Glendale Heights
Project : IDOT W051, 203 E. Fayette Ave., Effingham, IL
Project # : 11267090
Identification : Asbestos, Bulk Sample Analysis
Test Method : Polarized Light Microscopy / Dispersion Staining (PLM/DS)
EPA Method 600 / R-93 / 116

Lab Job No. : 26B-04956
Report Date : 05/07/2026
Sample Date : 04/21/2026

Page 3 of 5

On 4/27/2026, fifty five (55) bulk material samples were submitted by a representative of Terracon - Glendale Heights for asbestos analysis by PLM/DS. The PLM Detail Report is attached; additional information may be found therein. The results are summarized below:

Sample Number	Client Sample Description / Location	Asbestos Content
51-10-32	Vinyl Sheet Flooring (Blue and Beige Octagon Pattern) and Adhesive (Clear), Stairs to Basement	None Detected - Sheet Flooring None Detected - Fiber Backing None Detected - Clear Adhesive
51-10-33	Vinyl Sheet Flooring (Blue and Beige Octagon Pattern) and Adhesive (Clear), Stairs to Basement	None Detected - Sheet Flooring None Detected - Fiber Backing None Detected - Clear Adhesive
51-10-34	Vinyl Sheet Flooring (Blue and Beige Octagon Pattern) and Adhesive (Clear), Stairs to Basement	None Detected - Sheet Flooring None Detected - Fiber Backing None Detected - Clear Adhesive
51-11-35	Boiler Flue Cement (Gray), Basement Chimney	None Detected - Cement
51-11-36	Boiler Flue Cement (Gray), Basement Chimney	None Detected - Cement
51-11-37	Boiler Flue Cement (Gray), Basement Chimney	None Detected - Cement
51-12-38	9" x 9" Vinyl Floor Tile (Brown with Black Streaks) and Mastic, Center Portion of 2nd Floor	5% Chrysotile - Floor Tile None Detected - Black Mastic None Detected - Felt / Tar Paper
51-12-39	9" x 9" Vinyl Floor Tile (Brown with Black Streaks) and Mastic, Center Portion of 2nd Floor	5% Chrysotile - Floor Tile None Detected - Black Mastic None Detected - Felt / Tar Paper
51-12-40	9" x 9" Vinyl Floor Tile (Brown with Black Streaks) and Mastic, 2nd Floor Hallway	5% Chrysotile - Floor Tile None Detected - Black Mastic None Detected - Felt / Tar Paper
51-13-41	9" x 9" Vinyl Floor Tile (Green with Beige and Black Streaks) and Mastic, North Portion of 2nd Floor	5% Chrysotile - Floor Tile None Detected - Black Mastic None Detected - Felt / Tar Paper
51-13-42	9" x 9" Vinyl Floor Tile (Green with Beige and Black Streaks) and Mastic, North Portion of 2nd Floor	5% Chrysotile - Floor Tile None Detected - Black Mastic None Detected - Felt / Tar Paper
51-13-43	9" x 9" Vinyl Floor Tile (Green with Beige and Black Streaks) and Mastic, North Portion of 2nd Floor	5% Chrysotile - Floor Tile None Detected - Black Mastic None Detected - Felt / Tar Paper



PLM Summary Report

NVLAP Lab Code 102056-0

TDSHS License No. 300084

2051 Valley View Lane
Farmers Branch, TX 75234 Phone: (972) 241-8460

Client :	Terracon - Glendale Heights	Lab Job No. : 26B-04956
Project :	IDOT W051, 203 E. Fayette Ave., Effingham, IL	Report Date : 05/07/2026
Project # :	11267090	Sample Date : 04/21/2026
Identification :	Asbestos, Bulk Sample Analysis	
Test Method :	Polarized Light Microscopy / Dispersion Staining (PLM/DS) EPA Method 600 / R-93 / 116	

Page 4 of 5

On 4/27/2026, fifty five (55) bulk material samples were submitted by a representative of Terracon - Glendale Heights for asbestos analysis by PLM/DS. The PLM Detail Report is attached; additional information may be found therein. The results are summarized below:

Sample Number	Client Sample Description / Location	Asbestos Content
51-14-44	Boiler Flue Cement (Beige), Basement Chimney	None Detected - Cement 20% Chrysotile - Insulation
51-14-45	Boiler Flue Cement (Beige), Basement Chimney	None Detected - Cement 20% Chrysotile - Insulation
51-14-46	Boiler Flue Cement (Beige), Basement Chimney	None Detected - Cement 20% Chrysotile - Insulation
51-15-47	Brick (Red) and Mortar (Gray), Exterior Façade	None Detected - Brick None Detected - Mortar
51-15-48	Brick (Red) and Mortar (Gray), Exterior Façade	None Detected - Brick None Detected - Mortar
51-15-49	Brick (Red) and Mortar (Gray), Exterior Façade	None Detected - Brick None Detected - Mortar
51-16-50	Tar Paper, South	None Detected - Tar Paper None Detected - Paper
51-16-51	Tar Paper, South	None Detected - Tar Paper None Detected - Paper
51-16-52	Tar Paper, South	None Detected - Tar Paper None Detected - Paper
51-17-53	Shingled Roof, Southwest	None Detected - Roofing Shingles None Detected - Roofing Tars None Detected - Tar Paper
51-17-54	Shingled Roof, Southwest	None Detected - Roofing Shingles None Detected - Roofing Tars None Detected - Tar Paper
51-17-55	Shingled Roof, Southwest	None Detected - Roofing Shingles None Detected - Roofing Tars None Detected - Tar Paper



PLM Summary Report

NVLAP Lab Code 102056-0

TDSHS License No. 300084

2051 Valley View Lane

Farmers Branch, TX 75234 Phone: (972) 241-8460

Client : Terracon - Glendale Heights

Lab Job No. : 26B-04956

Project : IDOT W051, 203 E. Fayette Ave., Effingham, IL

Report Date : 05/07/2026

Project # : 11267090

Sample Date : 04/21/2026

Identification : Asbestos, Bulk Sample Analysis

Test Method : Polarized Light Microscopy / Dispersion Staining (PLM/DS)

EPA Method 600 / R-93 / 116

Page 5 of 5

On 4/27/2026, fifty five (55) bulk material samples were submitted by a representative of Terracon - Glendale Heights for asbestos analysis by PLM/DS. The PLM Detail Report is attached; additional information may be found therein. The results are summarized below:

Sample Number	Client Sample Description / Location	Asbestos Content

These samples were analyzed by layers. Quantification, unless otherwise noted, is performed by calibrated visual estimate. The test report shall not be reproduced except in full without written approval of the laboratory. The results relate only to the items tested. These test results do not imply endorsement by NVLAP or any agency of the U.S. Government. Accredited by the National Voluntary Laboratory Accreditation Program for Bulk Asbestos Fiber Analysis under Lab Code 102056-0.



Analyst(s): Heather Lopez

Lab Manager : Heather Lopez

Lab Director : Bruce Crabb

Approved Signatory : _____

Approved Signatory : _____

Thank you for choosing Moody Labs

This Page Left Intentionally Blank

Moody Labs

2051 Valley View Lane

Farmers Branch, TX 75234 Phone: (972) 241-8460

PLM Detail Report
Supplement to PLM Summary Report

NVLAP Lab Code 102056-0

TDSHS License No. 300084

Client : Terracon - Glendale Heights

Project : IDOT W051, 203 E. Fayette Ave., Effingham, IL

Project # : 11267090

Lab Job No. : 26B-04956

Report Date : 05/07/2026

Page 1 of 7

Sample Number	Layer	% Of Sample	Components	% of Layer	Analysis Date	Analyst
51-1-1	Bottom Plaster (Tan)	90%	Hair Fibers	<1%	05/06	HL
			Aggregate	65%		
			Calcite / Binders	35%		
	Top Plaster (Tan)	10%	Calcite / Binders	100%		
51-1-2	Bottom Plaster (Tan)	90%	Hair Fibers	<1%	05/06	HL
			Aggregate	65%		
			Calcite / Binders	35%		
	Top Plaster (Tan)	10%	Calcite / Binders	100%		
51-1-3	Bottom Plaster (Tan)	90%	Hair Fibers	<1%	05/06	HL
			Aggregate	65%		
			Calcite / Binders	35%		
	Top Plaster (Tan)	10%	Calcite / Binders	100%		
51-1-4	Bottom Plaster (Tan)	90%	Hair Fibers	<1%	05/06	HL
			Aggregate	65%		
			Calcite / Binders	35%		
	Top Plaster (Tan)	10%	Calcite / Binders	100%		
51-1-5	Bottom Plaster (Tan)	90%	Hair Fibers	<1%	05/06	HL
			Aggregate	65%		
			Calcite / Binders	35%		
	Top Plaster (Tan)	10%	Calcite / Binders	100%		
51-1-6	Bottom Plaster (Tan)	90%	Hair Fibers	<1%	05/06	HL
			Aggregate	65%		
			Calcite / Binders	35%		
	Top Plaster (Tan)	10%	Calcite / Binders	100%		
51-1-7	Bottom Plaster (Tan)	90%	Hair Fibers	<1%	05/06	HL
			Aggregate	65%		
			Calcite / Binders	35%		
	Top Plaster (Tan)	10%	Calcite / Binders	100%		
51-2-8	Paper (Tan)	100%	Cellulose Fibers	100%	05/06	HL

Moody Labs

2051 Valley View Lane

Farmers Branch, TX 75234 Phone: (972) 241-8460

PLM Detail Report
Supplement to PLM Summary Report

NVLAP Lab Code 102056-0

TDSHS License No. 300084

Client : Terracon - Glendale Heights

Project : IDOT W051, 203 E. Fayette Ave., Effingham, IL

Project # : 11267090

Lab Job No. : 26B-04956

Report Date : 05/07/2026

Page 2 of 7

Sample Number	Layer	% Of Sample	Components	% of Layer	Analysis Date	Analyst
51-2-9	Paper (Tan)	100%	Cellulose Fibers	100%	05/06	HL
51-2-10	Paper (Tan)	100%	Cellulose Fibers	100%	05/06	HL
51-3-11	Tan Mastic (Tan)	2%	Glue Binders	100%	05/06	HL
	Wood Flooring (Brown)	98%	Wood	100%		
51-3-12	Tan Mastic (Tan)	2%	Glue Binders	100%	05/06	HL
	Wood Flooring (Brown)	98%	Wood	100%		
51-3-13	Tan Mastic (Tan)	2%	Glue Binders	100%	05/06	HL
	Wood Flooring (Brown)	98%	Wood	100%		
51-4-14	Acoustic Tile (Tan)	100%	Cellulose Fibers	100%	05/06	HL
51-4-15	Acoustic Tile (Tan)	100%	Cellulose Fibers	100%	05/06	HL
51-4-16	Acoustic Tile (Tan)	100%	Cellulose Fibers	100%	05/06	HL
51-5-17	Acoustic Tile (Tan)	100%	Cellulose Fibers	100%	05/06	HL
51-5-18	Acoustic Tile (Tan)	100%	Cellulose Fibers	100%	05/06	HL
51-5-19	Acoustic Tile (Tan)	100%	Cellulose Fibers	100%	05/06	HL
51-6-20	Sheet Flooring (Beige)	100%	Glass Wool Fibers	5%	05/06	HL
			Synthetic Foam	65%		
			Vinyl Binders	30%		
51-6-21	Sheet Flooring (Beige)	100%	Glass Wool Fibers	5%	05/06	HL
			Synthetic Foam	65%		
			Vinyl Binders	30%		
51-6-22	Sheet Flooring (Beige)	100%	Glass Wool Fibers	5%	05/06	HL
			Synthetic Foam	65%		
			Vinyl Binders	30%		
51-7-23	Drywall Material (White)	85%	Glass Wool Fibers	2%	05/06	HL
			Gypsum / Binders	98%		
	DW Paper / Tape (Tan / White)	5%	Cellulose Fibers	100%		
	Joint Compound (White)	10%	Calcite / Talc / Binders	100%		

Moody Labs

2051 Valley View Lane

Farmers Branch, TX 75234 Phone: (972) 241-8460

PLM Detail Report
Supplement to PLM Summary Report

NVLAP Lab Code 102056-0

TDSHS License No. 300084

Client : Terracon - Glendale Heights

Project : IDOT W051, 203 E. Fayette Ave., Effingham, IL

Project # : 11267090

Lab Job No. : 26B-04956

Report Date : 05/07/2026

Page 3 of 7

Sample Number	Layer	% Of Sample	Components	% of Layer	Analysis Date	Analyst
51-7-24	Drywall Material (White)	30%	Cellulose Fibers	5%	05/06	HL
			Gypsum / Binders	95%		
	DW Paper / Tape (Tan / White)	30%	Cellulose Fibers	100%		
	Joint Compound (White)	40%	Chrysotile	2%		
			Calcite / Talc / Binders	98%		
51-7-25	Drywall Material (White)	65%	Cellulose Fibers	5%	05/06	HL
			Gypsum / Binders	95%		
	DW Paper / Tape (Tan / White)	15%	Cellulose Fibers	100%		
	Joint Compound (White)	20%	Chrysotile	2%		
			Calcite / Talc / Binders	98%		
51-8-26	Sheet Flooring (Beige)	99%	Glass Wool Fibers	5%	05/06	HL
			Synthetic Foam	65%		
			Vinyl Binders	30%		
	Clear Adhesive (Clear)	1%	Glue Binders	100%		
51-8-27	Sheet Flooring (Beige)	99%	Glass Wool Fibers	5%	05/06	HL
			Synthetic Foam	65%		
			Vinyl Binders	30%		
	Clear Adhesive (Clear)	1%	Glue Binders	100%		
51-8-28	Sheet Flooring (Beige)	99%	Glass Wool Fibers	5%	05/06	HL
			Synthetic Foam	65%		
			Vinyl Binders	30%		
	Clear Adhesive (Clear)	1%	Glue Binders	100%		
51-9-29	Window Glazing (Light Tan)	100%	Calcite	60%	05/06	HL
			Binders / Fillers	40%		
51-9-30	Window Glazing (White)	100%	Chrysotile	2%	05/06	HL
			Calcite / Binders	98%		
51-9-31	Window Glazing (White)	100%	Chrysotile	2%	05/06	HL
			Calcite / Binders	98%		

Moody Labs

2051 Valley View Lane

Farmers Branch, TX 75234 Phone: (972) 241-8460

PLM Detail Report
Supplement to PLM Summary Report

NVLAP Lab Code 102056-0

TDSHS License No. 300084

Client : Terracon - Glendale Heights

Project : IDOT W051, 203 E. Fayette Ave., Effingham, IL

Project # : 11267090

Lab Job No. : 26B-04956

Report Date : 05/07/2026

Page 4 of 7

Sample Number	Layer	% Of Sample	Components	% of Layer	Analysis Date	Analyst
51-10-32	Sheet Flooring (Blue and Beige)	50%	Synthetic Foam	70%	05/06	HL
			Vinyl Binders	30%		
	Fiber Backing (Light Gray)	49%	Cellulose Fibers	55%		
			Synthetic Fibers	5%		
			Glass Wool Fibers	5%		
			Binders / Fillers	35%		
	Clear Adhesive (Clear)	1%	Glue Binders	100%		
51-10-33	Sheet Flooring (Blue and Beige)	50%	Synthetic Foam	70%	05/06	HL
			Vinyl Binders	30%		
	Fiber Backing (Light Gray)	49%	Cellulose Fibers	55%		
			Synthetic Fibers	5%		
			Glass Wool Fibers	5%		
			Binders / Fillers	35%		
	Clear Adhesive (Clear)	1%	Glue Binders	100%		
51-10-34	Sheet Flooring (Blue and Beige)	50%	Synthetic Foam	70%	05/06	HL
			Vinyl Binders	30%		
	Fiber Backing (Light Gray)	49%	Cellulose Fibers	55%		
			Synthetic Fibers	5%		
			Glass Wool Fibers	5%		
			Binders / Fillers	35%		
	Clear Adhesive (Clear)	1%	Glue Binders	100%		
51-11-35	Cement (Gray)	100%	Aggregate	65%	05/06	HL
			Cement Binders	35%		
51-11-36	Cement (Gray)	100%	Aggregate	65%	05/06	HL
			Cement Binders	35%		
51-11-37	Cement (Gray)	100%	Aggregate	65%	05/06	HL
			Cement Binders	35%		

Moody Labs

2051 Valley View Lane

Farmers Branch, TX 75234 Phone: (972) 241-8460

PLM Detail Report
Supplement to PLM Summary Report

NVLAP Lab Code 102056-0

TDSHS License No. 300084

Client : Terracon - Glendale Heights

Project : IDOT W051, 203 E. Fayette Ave., Effingham, IL

Project # : 11267090

Lab Job No. : 26B-04956

Report Date : 05/07/2026

Page 5 of 7

Sample Number	Layer	% Of Sample	Components	% of Layer	Analysis Date	Analyst
51-12-38	Floor Tile (Brown)	87%	Chrysotile	5%	05/06	HL
			Calcite / Vinyl Binders	95%		
	Black Mastic (Black)	3%	Tar Binders	100%		
	Felt / Tar Paper (Black)	10%	Cellulose Fibers	85%		
			Tar Binders	15%		
51-12-39	Floor Tile (Brown)	87%	Chrysotile	5%	05/06	HL
			Calcite / Vinyl Binders	95%		
	Black Mastic (Black)	3%	Tar Binders	100%		
	Felt / Tar Paper (Black)	10%	Cellulose Fibers	85%		
			Tar Binders	15%		
51-12-40	Floor Tile (Brown)	87%	Chrysotile	5%	05/06	HL
			Calcite / Vinyl Binders	95%		
	Black Mastic (Black)	3%	Tar Binders	100%		
	Felt / Tar Paper (Black)	10%	Cellulose Fibers	85%		
			Tar Binders	15%		
51-13-41	Floor Tile (Green)	87%	Chrysotile	5%	05/06	HL
			Calcite / Vinyl Binders	95%		
	Black Mastic (Black)	3%	Tar Binders	100%		
	Felt / Tar Paper (Black)	10%	Cellulose Fibers	85%		
			Tar Binders	15%		
51-13-42	Floor Tile (Green)	87%	Chrysotile	5%	05/06	HL
			Calcite / Vinyl Binders	95%		
	Black Mastic (Black)	3%	Tar Binders	100%		
	Felt / Tar Paper (Black)	10%	Cellulose Fibers	85%		
			Tar Binders	15%		
51-13-43	Floor Tile (Green)	87%	Chrysotile	5%	05/06	HL
			Calcite / Vinyl Binders	95%		
	Black Mastic (Black)	3%	Tar Binders	100%		
	Felt / Tar Paper (Black)	10%	Cellulose Fibers	85%		
			Tar Binders	15%		

Moody Labs

2051 Valley View Lane

Farmers Branch, TX 75234 Phone: (972) 241-8460

PLM Detail Report
Supplement to PLM Summary Report

NVLAP Lab Code 102056-0

TDSHS License No. 300084

Client : Terracon - Glendale Heights

Project : IDOT W051, 203 E. Fayette Ave., Effingham, IL

Project # : 11267090

Lab Job No. : 26B-04956

Report Date : 05/07/2026

Page 6 of 7

Sample Number	Layer	% Of Sample	Components	% of Layer	Analysis Date	Analyst
51-14-44	Cement (Beige)	95%	Aggregate	65%	05/06	HL
			Cement Binders	35%		
	Insulation (Gray)	5%	Chrysotile	20%		
			Binders / Fillers	80%		
51-14-45	Cement (Beige)	98%	Aggregate	65%	05/06	HL
			Cement Binders	35%		
	Insulation (Gray)	2%	Chrysotile	20%		
			Binders / Fillers	80%		
51-14-46	Cement (Beige)	99%	Aggregate	65%	05/06	HL
			Cement Binders	35%		
	Insulation (Gray)	1%	Chrysotile	20%		
			Binders / Fillers	80%		
51-15-47	Brick (Red)	95%	Sintered Clays	100%	05/06	HL
	Mortar (Gray)	5%	Aggregate	65%		
			Cement Binders	35%		
51-15-48	Brick (Red)	95%	Sintered Clays	100%	05/06	HL
	Mortar (Gray)	5%	Aggregate	65%		
			Cement Binders	35%		
51-15-49	Brick (Red)	90%	Sintered Clays	100%	05/06	HL
	Mortar (Gray)	10%	Aggregate	65%		
			Cement Binders	35%		
51-16-50	Tar Paper (Black)	50%	Cellulose Fibers	90%	05/06	HL
	Paper (Tan)	50%	Tar Binders	10%		
			Cellulose Fibers	100%		
51-16-51	Tar Paper (Black)	50%	Cellulose Fibers	90%	05/06	HL
	Paper (Tan)	50%	Tar Binders	10%		
			Cellulose Fibers	100%		

Moody Labs

2051 Valley View Lane

Farmers Branch, TX 75234 Phone: (972) 241-8460

PLM Detail Report
Supplement to PLM Summary Report

NVLAP Lab Code 102056-0

TDSHS License No. 300084

Client : Terracon - Glendale Heights

Project : IDOT W051, 203 E. Fayette Ave., Effingham, IL

Project # : 11267090

Lab Job No. : 26B-04956

Report Date : 05/07/2026

Page 7 of 7

Sample Number	Layer	% Of Sample	Components	% of Layer	Analysis Date	Analyst
51-16-52	Tar Paper (Black)	50%	Cellulose Fibers	90%	05/06	HL
			Tar Binders	10%		
	Paper (Tan)	50%	Cellulose Fibers	100%		
51-17-53	Sand Layer (White / Black)	15%	Aggregate	100%	05/06	HL
	Roofing Shingles (Black)	75%	Glass Wool Fibers	20%		
			Calcite	35%		
			Tar Binders	45%		
	Roofing Tars (Black)	5%	Tar Binders	100%		
	Tar Paper (Black)	5%	Cellulose Fibers	85%		
			Tar Binders	15%		
51-17-54	Sand Layer (White / Black)	15%	Aggregate	100%	05/06	HL
	Roofing Shingles (Black)	75%	Glass Wool Fibers	20%		
			Calcite	35%		
			Tar Binders	45%		
	Roofing Tars (Black)	5%	Tar Binders	100%		
	Tar Paper (Black)	5%	Cellulose Fibers	85%		
			Tar Binders	15%		
51-17-55	Sand Layer (White / Black)	15%	Aggregate	100%	05/06	HL
	Roofing Shingles (Black)	75%	Glass Wool Fibers	20%		
			Calcite	35%		
			Tar Binders	45%		
	Roofing Tars (Black)	5%	Tar Binders	100%		
	Tar Paper (Black)	5%	Cellulose Fibers	85%		
			Tar Binders	15%		

TEM Bulk Summary Report

Moody Labs

2051 Valley View Lane

Farmers Branch, TX 75234 Phone: (972) 241-8460

NVLAP Lab Code 102056-0

TDSHS License No. 300084

Client : Terracon - Glendale Heights Lab Job No. : 26T-04956A
Project : IDOT W051, 203 E. Fayette Ave., Effingham, IL Report Date : 05/28/2026
Project # : 11267090 Sample Date : 04/21/2026
Identification : Asbestos, Bulk Sample Analysis
Test Method : Transmission Electron Microscopy / X-Ray Analysis (TEM/EDX) / Gravimetric Analysis. EPA 600/R93/116

Page 1 of 1

On 5/21/2026, three (3) bulk material samples were submitted by a representative of Terracon - Glendale Heights for asbestos analysis by TEM/EDX/Gravimetric. The TEM Chatfield Detail Report is attached; additional information may be found therein. The results are summarized below:

Sample Number	Client Sample Description / Location	Asbestos Content
51-6-20	Vinyl Sheet Flooring (Beige Square Pattern), Bathroom	None Detected - Sheet Flooring
51-8-26	Vinyl Sheet Flooring (Beige Rectangle Pattern), Adhesive (Clear), Kitchen	None Detected - Sheet Flooring
51-10-32	Vinyl Sheet Flooring (Blue and Beige Octagon Pattern) and Adhesive (Clear), Stairs to Basement	None Detected - Sheet Flooring

These samples were analyzed by layers. Quantification, unless otherwise noted, is performed by calibrated visual estimate. Results may not be reproduced except in full. This test report relates only to the samples tested. These test results do not imply endorsement by NVLAP or any agency of the U.S. Government. Accredited by the National Voluntary Laboratory Accreditation Program for Bulk Asbestos Fiber Analysis under Lab Code 102056.

Analyst(s): Yokebed Alvarado

Lab Manager : Heather Lopez

Lab Director : Bruce Crabb

Approved Signatory :

Approved Signatory :

Thank you for choosing Steve Moody Micro Services

Moody Labs

2051 Valley View Lane

Farmers Branch, TX 75234 Phone: (972) 241-8460

TEM Chatfield Detail Report

Supplement to TEM Bulk Summary Report

NVLAP Lab Code 102056-0

TDSHS License No. 300084

Client : Terracon - Glendale Heights

Project : IDOT W051, 203 E. Fayette Ave., Effingham, IL

Project # : 11267090

Lab Job No. : 26T-04956A

Report Date : 05/28/2026

Page 1 of 1

Sample Number	Layer	Mass		Percent of Sample	
51-6-20	Sheet Flooring	Original Sample	0.1336 grams		
		Ashed Sample	0.0457 grams	Ashed	65.79%
		Acid Washed Sample	0.0018 grams	Acid	98.65%
		Sediment	N/A grams	Sediment	N/A
		Percent Remaining	1.35%		
		Estimated Asbestos Percentage	None Detected		
		TEM - Gravimetric Result	None Detected		
		Analyst: Yokebed Alvarado	Analyzed On: 05/28/2026		
51-8-26	Sheet Flooring	Original Sample	0.1986 grams		
		Ashed Sample	0.0499 grams	Ashed	74.87%
		Acid Washed Sample	0.0119 grams	Acid	94.01%
		Sediment	N/A grams	Sediment	N/A
		Percent Remaining	5.99%		
		Estimated Asbestos Percentage	None Detected		
		TEM - Gravimetric Result	None Detected		
		Analyst: Yokebed Alvarado	Analyzed On: 05/28/2026		
51-10-32	Sheet Flooring	Original Sample	0.2097 grams		
		Ashed Sample	0.0646 grams	Ashed	69.19%
		Acid Washed Sample	0.0352 grams	Acid	83.21%
		Sediment	N/A grams	Sediment	N/A
		Percent Remaining	16.79%		
		Estimated Asbestos Percentage	None Detected		
		TEM - Gravimetric Result	None Detected		
		Analyst: Yokebed Alvarado	Analyzed On: 05/28/2026		



Asbestos Bulk Sample Log & Chain of Custody Form

Lab Use Only:

268 . 04956 PLK

Lab Location:

Page 1 of 4

Glendale Heights: 192 Exchange Blvd., Glendale Heights, IL 60139 (630) 717-4263

Project Name:	IDOT W051
Project Address:	203 E. Fayette Ave

Project Number:	11267690
City/State / Zip:	Effingham, IL

Project Manager:	Heather Eckard
Email Results To:	Heather.Eckard@terracon.com & Chris.Heynen@terracon.com

Sample Identification WO - HA - Sample # - # - #	Sample Location Description	Material Description (Color/Texture/Etc.)	HA General Location	Quantity (SF, LF, CF, Units)	NESHAP Category ¹	Condition ² / Notes
51-1-1	N bedroom closet wall	Plaster walls + ceilings	Throughout ground floor		F C1 C2	G D SD
1-1-2	↓					
1-1-3	S bedroom closet wall					
1-1-4	↓					
1-1-5	S bedroom wall					
1-1-6	GF Hallway closet ceiling					
↓-↓-7	↓				F C1 C2	G D SD
- - -						
- - -						
51-2-8	Living room register	Paper under wood flooring	Throughout 'ground floor'		F C1 C2	G D SD
1-1-9	↓					
↓-↓-10	↓					
51-3-11	dining room	Tan mastic on wood flooring	Dining room	16' x 11'	F C1 C2	G D SD
1-1-12	↓					
↓-↓-13	↓					

Sampling Date: 4/21/26	Collected by (print): Chris Heynen	Inspector's Signature: Christopher Heynen
Relinquished by: Chris Heynen	Date/Time: 4/24/26	Received by: [Signature] Date/Time: 4/27/26 1:00p
Analysis: PLM EPA 600/R-93/116 ☒ PLM 400 Point Count ☐ TEM ☐ Other	Instructions: Terracon ARMS: ☒ Stop Positive: ☐ Number of samples: _____	
Turnaround Time: 6 Hrs ☐ 24 Hrs ☐ 2 Days ☐ 3 Days ☐ 5 Days ☐ Other: 5-7 days		

¹ F = Friable; C1 = Category I Nonfriable: packings, gaskets, resilient floor covering, and asphalt roofing products; C2 = Category II Nonfriable: any nonfriable material other than Category I Nonfriable² G = Good (no damage); D = Damaged (<10% distributed or <25% localized); or SD = Significantly Damaged (>10% distributed or >25% localized)



Asbestos Bulk Sample Log & Chain of Custody Form

Lab Use Only:

26B - 04956

Glendale Heights: 192 Exchange Blvd., Glendale Heights, IL 60139 (630) 717-4263

Lab Location:

Page 2 of 4

Sample Identification			Sample Location Description	Material Description (Color/Texture/Etc.)	HA General Location	Quantity (SF, LF, CF, Units)	NESHAP Category ¹	Condition ² / Notes
WO #	HA #	Sample #						
51-4-14			Living room	1'x1' white smooth tongue & groove ceiling tile (no glue)	Living room	14'x23'	F C1 C2	G D SD
↓-↓-15			↓					
↓-↓-16			↓					
51-5-17			dining room	1'x1' white pinhole tongue & groove ceiling tile (no glue)	Dining room, ground floor N bedroom	16'x11'	F C1 C2	G D SD
↓-↓-18			↓					
↓-↓-19			North Bedroom					
51-6-20			Bathroom	Beige square pattern vinyl sheet flooring	GF bathroom	9'x3'	F C1 C2	G D SD
↓-↓-21			↓					
↓-↓-22			↓					
51-7-23			GF bathroom wall	Drywall, joint compound	GF bathroom walls, walls & ceilings throughout 2nd flr		F C1 C2	G D SD
↓-↓-24			2nd flr ceiling - S					
↓-↓-25			2nd flr wall - N					
51-8-26			Kitchen	Beige rectangle pattern vinyl sheet flooring clear adhesive	Kitchen	18'x12'	F C1 C2	G D SD
↓-↓-27			↓					
↓-↓-28			↓					
51-9-29			Basement S window	Tan exterior window glazing	Kitchen windows, dining room windows, basement windows, 2nd flr windows		F C1 C2	G D SD
↓-↓-30			Kitchen window					
↓-↓-31			2nd flr W window					



Asbestos Bulk Sample Log & Chain of Custody Form

Lab Use Only:

26B. 04956

Lab Location:

Page 3 of 4

Glendale Heights: 192 Exchange Blvd., Glendale Heights, IL 60139 (630) 717-4263

Sample Identification			Sample Location Description	Material Description (Color/Texture/Etc.)	HA General Location	Quantity (SF, LF, CF, Units)	NESHAP Category ¹	Condition ² / Notes
WO #	HA #	Sample #						
51	10	32	Stairs to basement	Blue & beige octagon pattern vinyl sheet flooring + clear adhesive	stairs to basement	8'x3.5'	F C1 C2	G D SD
1	1	33	↓					
	1	34	↓					
	11	35	Basement chimney	Gray Boiler flue cement	Basement chimney		F C1 C2	G D SD
	1	36	↓					
	1	37	↓					
	12	38	Center portion of 2 nd flr	9"x9" brown w/ black streaks vinyl floor tile + mastic	Stairs to 2 nd flr Center portion of 2 nd flr, 2 nd flr restroom, 2 nd flr hallway	22'x15' + 4'x8'	F C1 C2	G D SD
	1	39	↓					
	1	40	2 nd flr hallway					
	13	41	W portion of 2 nd flr	9"x9" green w/ beige & black streaks vinyl floor tile + mastic	W portion of 2 nd flr	17'x12'	F C1 C2	G D SD
	1	42	↓					
	1	43	↓					
	14	44	Basement chimney	Beige boiler flue cement	Basement chimney		F C1 C2	G D SD
	1	45	↓					
	1	46	↓					
	15	47	exterior facade	Red Brick and Gray mortar	Exterior facade		F C1 C2	G D SD
	1	48	↓					
	1	49	↓					



Asbestos Bulk Sample Log & Chain of Custody Form

Lab Use Only:

26B. 04956

Lab Location:

Page 4 of 4

Glendale Heights: 192 Exchange Blvd., Glendale Heights, IL 60139 (630) 717-4263

Sample Identification			Sample Location Description	Material Description (Color/Texture/Etc.)	HA General Location	Quantity (SF, LF, CF, Units)	NESHAP Category ¹	Condition ² / Notes
WO #	HA #	Sample #						
51-16	-	50	South	Tar paper	Under wood siding Under vinyl siding		F C1 C2	G D SD
1-1	-	51	↓					
↓-↓	-	52	↓					
51-17	-	53	SW	Shingled roof	Roof field		F C1 C2	G D SD
1-1	-	54	↓					
↓-↓	-	55	↓					
-	-						F C1 C2	G D SD
-	-							
-	-							
-	-						F C1 C2	G D SD
-	-							
-	-							
-	-						F C1 C2	G D SD
-	-							
-	-							
-	-						F C1 C2	G D SD
-	-							
-	-							

APPENDIX D

LICENSES AND CERTIFICATIONS



525-535 West Jefferson Street • Springfield, Illinois 62761-0001 • www.dph.illinois.gov

CHRISTOPHER J HEYNEN

3/28/2025

ASBESTOS PROFESSIONAL LICENSE ID NUMBER: 19246

Enclosed is your Asbestos Professional License. Please note the expiration date on the card and in the image depicted below.

COPY OF THE ASBESTOS PROFESSIONAL LICENSE

Front of License

Back of License

		ASBESTOS PROFESSIONAL LICENSE		ENDORSEMENTS	TC EXPIRES
ID NUMBER 100 - 19246		ISSUED 3/28/2025		INSPECTOR	1/30/2026
EXPIRES 05/15/2026					
CHRISTOPHER J HEYNEN					
					
Environmental Health					
Alteration of this license shall result in legal action This license issued under authority of the State of Illinois Department of Public Health This license is valid only when accompanied by a valid training course certificate.					

If you have any questions or need further assistance, contact the Asbestos Program at (217)782-3517 or fax (217)785-5897.

Our WEB address is: dph.illinois.gov/topics-services/environmental-health-protection/asbestos

EMAIL Address: dph.asbestos@illinois.gov

PROTECTING HEALTH, IMPROVING LIVES

Nationally Accredited by PHAB



2026

OCCUPATIONAL TRAINING & SUPPLY, INC. | 7233 ADAMS STREET | WILLOWBROOK, IL 60527 (630)655-3900 | WWW.OTSSAFETY.COM

Asbestos Building Inspector Refresher

Occupational Training & Supply, Inc. certifies that

Christopher Heynen

has successfully completed the Asbestos Building Inspector Refresher course and has passed the competency exam with a minimum score of 70%. The course is accredited by the Illinois Department of Public Health and Indiana Department of Environmental Management for purposes of accreditation in accordance with EPA 40 CFR 763, Asbestos Hazard Emergency Response Act (AHERA) and TSCA Title II.

Course Date: 1/29/2026

Exam Date: 1/29/2026

Expiration Date: 1/29/2027

Certificate Number: BIR2601290375

Course Credit Hours: BIR 4 Hours

Kristina Miczek, Training Manager



**ASBESTOS
PROFESSIONAL
LICENSE**

ID NUMBER
100 - 20242

ISSUED
5/23/2025

EXPIRES
05/15/2026

ASHLY M ZWOLINSKI
6260 S LAKE DR #518
CUDAHY, WI 53110

Environmental Health





2026

OCCUPATIONAL TRAINING & SUPPLY, INC. | 7233 ADAMS STREET | WILLOWBROOK, IL 60527 (630)655-3900 | WWW.OTSSAFETY.COM

Asbestos Building Inspector Refresher

Occupational Training & Supply, Inc. certifies that

Ashly Zwolinski

has successfully completed the Asbestos Building Inspector Refresher course and has passed the competency exam with a minimum score of 70%. This course is accredited by the State of Wisconsin, Department of Health Services under ch. DHS 159, Wis. Admin. Code, The Illinois Department of Public Health and The Indiana Department of Environmental Management, under 326 IAC 18. Training was in accordance with requirements listed under EPA 40 CFR 763, Asbestos Hazard Emergency Response Act (AHERA) and TSCA Title II.

Location: 12304 75th Street
Kenosha, WI 53142


Certificate Number: BIRWI2602060458

Course Date: 2/6/2026

Exam Date: 2/6/2026

Expiration Date: 2/6/2027

Tyler Nicholson, Authorized Signer



Issue Date: 2/6/2026

Course Credit Hours: BIR WI 4 Hours

United States Department of Commerce
National Institute of Standards and Technology



Certificate of Accreditation to ISO/IEC 17025:2017

NVLAP LAB CODE: 102056-0

Moody Labs, LLC
Farmers Branch, TX

*is accredited by the National Voluntary Laboratory Accreditation Program for specific services,
listed on the Scope of Accreditation, for:*

Asbestos Fiber Analysis

*This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2017.
This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality
management system (refer to joint ISO-ILAC-IAF Communiqué on ISO/IEC 17025).*

2025-07-01 through 2026-06-30

Effective Dates



A handwritten signature in blue ink, appearing to read "R. K. Kueh".

For the National Voluntary Laboratory Accreditation Program

SCOPE OF ACCREDITATION TO ISO/IEC 17025:2017

Moody Labs, LLC
2051 Valley View Lane
Farmers Branch, TX 75234-8956
Mr. Bruce Crabb
Phone: 972-241-8460 Fax: 972-241-8461
Email: bruce.crabb@moodylabs.com
<http://www.moodylabs.com>

ASBESTOS FIBER ANALYSIS


NVLAP LAB CODE 102056-0

Bulk Asbestos Analysis

<u>Code</u>	<u>Description</u>
18/A01	EPA -- 40 CFR Appendix E to Subpart E of Part 763, Interim Method of the Determination of Asbestos in Bulk Insulation Samples
18/A03	EPA 600/R-93/116: Method for the Determination of Asbestos in Bulk Building Materials

Airborne Asbestos Analysis

<u>Code</u>	<u>Description</u>
18/A02	U.S. EPA's "Interim Transmission Electron Microscopy Analytical Methods-Mandatory and Nonmandatory-and Mandatory Section to Determine Completion of Response Actions" as found in 40 CFR, Part 763, Subpart E, Appendix A.



For the National Voluntary Laboratory Accreditation Program



APPENDIX E

PHOTOGRAPHS



		
Photo #1 HA 1: Hard layered plaster walls and ceilings (non-ACM)		Photo #2 HA 2: Tan felt paper under wood flooring (non-ACM)
		
Photo #3 HA 3: Tan mastic on wood flooring (non-ACM)		Photo #4 HA 4: 1' X 1' white smooth tongue and groove ceiling tile (no glue) (non-ACM)
		
Photo #5 HA 5: 1' X 1' white pinhole tongue and groove ceiling tile (no glue) (non-ACM)		Photo #6 HA 6: Beige square pattern vinyl sheet flooring and clear mastic (non-ACM)


		
Photo #7 HA 7: Drywall (non-ACM), joint compound (ACM)		Photo #8 HA 8: Beige rectangle pattern vinyl sheet flooring and clear mastic (non-ACM)
		
Photo #9 HA 9: Tan exterior window glazing (ACM)		Photo #10 HA 10: Blue and beige octagon pattern vinyl sheet flooring with light gray fiber backing (non-ACM) and clear mastic (non-ACM)
		
Photo #11 HA 11: Gray boiler flue cement (non-ACM)		Photo #12 HA 12: 9" X 9" brown with black streaks vinyl floor tile (ACM) and black mastic over felt/tar paper (non-ACM)

		
Photo #13 HA 13: 9" X 9" green with beige and black streaks vinyl floor tile (ACM) and black mastic over felt/tar paper (non-ACM)		Photo #14 HA 14: Beige boiler flue cement (non-ACM) with gray insulation (ACM)
		
Photo #15 HA 15: Red brick (non-ACM) and gray mortar (non-ACM)		Photo #16 HA 16: Tar paper under exterior siding (non-ACM)
		
Photo #17 HA 17: White/black asphalt shingles (non-ACM) and underlying black tar paper (non-ACM)		



APPENDIX F

SAMPLE / ASBESTOS LOCATION MAPS



LEGEND

X SAMPLE COLLECTION

DIAGRAM IS INTENDED FOR GENERAL USE ONLY, AND IS NOT FOR CONSTRUCTION PURPOSES. LOCATIONS ARE APPROXIMATE.

Project Mng:	CJH
Approved By:	CJH
Checked By:	CJH
Drawn By:	DBM
Project No.	11267090
Scale:	NTS
Date:	05/14/2026
File No.	11267090.DWG




SAMPLE LOCATION PLAN - GROUND FLOOR

SINGLE FAMILY RESIDENCE - IDOT WORK ORDER 51

203 EAST FAYETTE AVENUE
EFFINGHAM, EFFINGHAM COUNTY, ILLINOIS

EXHIBIT

1



LEGEND

X SAMPLE COLLECTION

DIAGRAM IS INTENDED FOR GENERAL USE ONLY, AND IS NOT FOR CONSTRUCTION PURPOSES. LOCATIONS ARE APPROXIMATE.


Project Mngr:	CJH	Project No.	11267090
Approved By:	CJH	Scale:	NTS
Checked By:	CJH	Date:	05/14/2026
Drawn By:	DBM	File No.	11267090.DWG



SAMPLE LOCATION PLAN - 2ND FLOOR
SINGLE FAMILY RESIDENCE - IDOT WORK ORDER 51
203 EAST FAYETTE AVENUE
EFFINGHAM, EFFINGHAM COUNTY, ILLINOIS

EXHIBIT

2




LEGEND

X SAMPLE COLLECTION

DIAGRAM IS INTENDED FOR GENERAL USE ONLY, AND IS NOT FOR CONSTRUCTION PURPOSES. LOCATIONS ARE APPROXIMATE.

Project Mngr: CJH	Project No. 11267090	 192 EXCHANGE BLVD GLENDALE HEIGHTS, ILLINOIS 60139 PH. (630) 717-4263 TERRACON.COM	SAMPLE LOCATION PLAN - BASEMENT SINGLE FAMILY RESIDENCE - IDOT WORK ORDER 51 203 EAST FAYETTE AVENUE EFFINGHAM, EFFINGHAM COUNTY, ILLINOIS	EXHIBIT 3
Approved By: CJH	Scale: NTS			
Checked By: CJH	Date: 05/14/2026			
Drawn By: DBM	File No. 11267090.DWG			



LEGEND: LOCATION OF ASBESTOS - CONTAINING MATERIAL

-  JOINT COMPOUND WITHIN THE DRYWALL SYSTEM - WALLS AND CEILINGS
* WHOLE DRYWALL SYSTEM NEEDS TO BE REMOVED, DRYWALL SYSTEM
MAYBE HIDDEN IN PLACES.
-  TAN EXTERIOR WINDOW GLAZING

DIAGRAM IS INTENDED FOR GENERAL USE ONLY, AND IS NOT
FOR CONSTRUCTION PURPOSES. LOCATIONS ARE APPROXIMATE.

Project Mngr:	CJH
Approved By:	CJH
Checked By:	CJH
Drawn By:	DBM

Project No.	11267090
Scale:	NTS
Date:	05/14/2026
File No.	11267090.DWG

**Terracon**

192 EXCHANGE BLVD GLENDALE HEIGHTS, ILLINOIS 60139
PH. (630) 717-4263
TERRACON.COM


ASBESTOS LOCATION PLAN - GROUND FLOOR

SINGLE FAMILY RESIDENCE - IDOT WORK ORDER 51

203 EAST FAYETTE AVENUE
EFFINGHAM, EFFINGHAM COUNTY, ILLINOIS

EXHIBIT

4




LEGEND: LOCATION OF ASBESTOS - CONTAINING MATERIAL

-  JOINT COMPOUND WITHIN THE DRYWALL SYSTEM - WALLS AND CEILINGS
* WHOLE DRYWALL SYSTEM NEEDS TO BE REMOVED, DRYWALL SYSTEM MAYBE HIDDEN IN PLACES.
-  TAN EXTERIOR WINDOW GLAZING
-  9" X 9" BROWN WITH BLACK STREAKS VINYL FLOOR TILE OVER NON-ACM BLACK MASTIC AND NON-ACM FLET/TAR PAPER
-  9" X 9" GREEN AND BEIGE AND BLACK STREAKS VINYL FLOOR TILE OVER NON-ACM BLACK MASTIC AND NON-ACM FELT/TAR PAPER

DIAGRAM IS INTENDED FOR GENERAL USE ONLY, AND IS NOT FOR CONSTRUCTION PURPOSES. LOCATIONS ARE APPROXIMATE.

Project Mngr:	CJH
Approved By:	CJH
Checked By:	CJH
Drawn By:	DBM


Project No.	11267090
Scale:	NTS
Date:	05/14/2026
File No.	11267090.DWG



ASBESTOS LOCATION PLAN - 2ND FLOOR
SINGLE FAMILY RESIDENCE - IDOT WORK ORDER 51
203 EAST FAYETTE AVENUE
EFFINGHAM, EFFINGHAM COUNTY, ILLINOIS

EXHIBIT

5



LEGEND: LOCATION OF ASBESTOS - CONTAINING MATERIAL

 GRAY INSULATION WITH NON-ACM BEIGE BOILER FLUE CEMENT
* ADDITIONAL INSULATION MAY BE HIDDEN BEHIND CEMENT

 TAN EXTERIOR WINDOW GLAZING

DIAGRAM IS INTENDED FOR GENERAL USE ONLY, AND IS NOT
FOR CONSTRUCTION PURPOSES. LOCATIONS ARE APPROXIMATE.

Project Mngr:	CJH
Approved By:	CJH
Checked By:	CJH
Drawn By:	DBM

Project No.	11267090
Scale:	NTS
Date:	05/14/2026
File No.	11267090.DWG

**Terracon**

192 EXCHANGE BLVD GLENDALE HEIGHTS, ILLINOIS 60139
PH. (630) 717-4263
TERRACON.COM

ASBESTOS LOCATION PLAN - BASEMENT

SINGLE FAMILY RESIDENCE - IDOT WORK ORDER 51
203 EAST FAYETTE AVENUE
EFFINGHAM, EFFINGHAM COUNTY, ILLINOIS

EXHIBIT

6