



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 3, 2026

SUBJECT: Various Routes
Section 21-00070-00-SW (Vandalia)
Fayette County
Contract No. 95997
Item 147
June 12, 2026 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised Plan Sheet 3**
- 2. Revised page 4 of the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

plan and sign the Contractor Certification Statement. The Contractor must work with the City of Vandalia to create a login if they haven't already, assist in completing, and submit the IEPA Notice of Intent (NOI) and submit the Storm Water Pollution Prevention Plan electronically to the Illinois EPA at <https://cdx.epa.gov/cdx/Login?ReturnUrl=%2fCDX%2fMuCDX> . Upon completion of the project, the Contractor shall create and submit the Notice of Termination (NOT) to the IEPA. Estimated quantities for various erosion control items are shown on the erosion control plan sheets. Upon completion of the project, the Contractor shall remove all materials used for temporary erosion control. These items shall become property of the Contractor. It is the responsibility of the Contractor to conduct inspections and complete maintenance report form for the SWPPP in compliance with EPA guidelines. The SWPPP is attached after the Special Provisions.

This work shall include all permit fees, labor, equipment, and material to comply with the erosion control plan sheet and the IEPA permits. The price of everything above shall be included in the Contract and shall include all permit fees stated above.

PIPE HANDRAIL

This work shall include installing a hand railing at the locations as shown in the plans and specifications, and in accordance with Section 509 of the specifications. The pipe handrail shall be powder coated black. The railing shall be constructed in accordance with ADA compliance and the Illinois Accessibility Code. Base plates shall be placed in the concrete to allow for installation of handrail. Base plates will not be paid for separately but will be included in the price of pipe handrail. The contractor and/or handrail manufacturer will be responsible for taking all necessary measurements for length and elevation needed to compile the shop drawings for the proposed handrail. **Drilling and placing anchor bolts shall be included in this pay item.** This work will be paid for at the contractor unit price FOOT for PIPE HANDRAIL, which will shall include all equipment, materials, fabrication and labor.

DOMESTIC METER VAULTS TO BE ADJUSTED

The Contractor shall adjust the existing water meter pits and meter lids to the elevations shown in the plans or match the ground elevations around the meter vault. This work shall be in accordance to the applicable portions of Section 602 of the Standard Specifications for Road & Bridge Construction. The Contractor shall coordinate this work with the City of Vandalia Water Department. The contractor shall provide an ADA compliant lid approved by the City of Vandalia or City Engineer. The Contractor shall be paid at the contract unit price per EACH for DOMESTIC METER VAULTS TO BE ADJUSTED.

INLETS TO BE ADJUSTED

This work shall consist of adjusting the existing inlet with a new grate. This work shall be done in accordance with Section 602 of the Standard Specifications with a Type 15 Frame and Lid as shown in IDOT Standard 604066-02 or equivalent. This work shall include all labor, material and equipment and shall be paid for the Contract Unit Price per EACH for INLETS TO BE ADJUSTED.