CODE NO.	ITEM	UNIT	TOTAL QUANTITY	FED 80% STATE 20% ROADWAY 0005 RURAL	FED 80% CITY 20% ROADWAY 0005 RURAL	FED 80% STATE 10% CITY 10% TRAFFIC SIGNALS 0021 RURAL
20200100	EARTH EXCAVATION	CU YD	87	15	72	
20800150	TRENCH BACKFILL	CU YD	163		163	
21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SQ YD	133	79.6	53.4	⚠
25200100	SODDING	SQ YD	133	79.6	53.4	
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	184		184	
35800200	AGGREGATE BASE REPAIR	TON	16	2.4	13.6	
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	20472	20472		
40600370	LONGITUDINAL JOINT SEALANT	FOOT	14527	14527		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	150	150		
40600990	TEMPORARY RAMP	SQ YD	129	129		
40603219	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-9.5FG, N90	TON	2243	2243		
40604164	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N90	TON	2669	2669		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	117		117	
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	125		125	
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	979		979	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	36	36		
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	7594	7594		
42400800	DETECTABLE WARNINGS	SQ FT	657	657		
44000100	PAVEMENT REMOVAL	SQ YD	969	126.7	842.3	

⚠ REVISED 7-21-2026

MODEL: SOQ 1 [Sheet]
FILE NAME: c:\pw_work\pwdothille\d1004209\D774829-sht-SOQ.dgn

USER NAME = jessica.hille	DESIGNED -	REVISED -
	DRAWN -	REVISED -
	CHECKED -	REVISED -
PLOT DATE = 3/12/2026	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET 3 OF 8 SHEETS | STA. | TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
762	(2,2Z) RS-3	MOULTRIE	143	3
		CONTRACT NO. 74829		
	ILLINOIS FED. AID PROJECT			