



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 9, 2026

SUBJECT Various Routes
Section 2024-1059-BDS
Lake County
Contract No. 62Y03
Item No. 10 September 18, 2026, Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page the Table of Contents to the Special Provisions
3. Revised pages 2, 12, 13, & 29 of the Special Provisions
4. Revised sheets 2 3, & 4 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
PUBLIC CONVENIENCE AND SAFETY (D1)	2
TOLLWAY PERMIT AND BOND (D1)	2
TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	3
TEMPORARY INFORMATION SIGNING	7
KEEPING THE TOLLWAY OPEN TO TRAFFIC	8
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY)	9
BRIDGE DECK CONCRETE SEALER	10
TRAFFIC CONTROL PLAN (D1)	12
COMPENSABLE DELAY COSTS (BDE)	14
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	17
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	19
ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE)	22
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	23
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	24
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	25
SUBMISSION OF BIDDERS LIST INFORMATION (BDE)	25
SUBMISSION OF PAYROLL RECORDS – STATE CONTRACT (BDE)	26
SURVEYING SERVICES (BDE)	26
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)	26
WEEKLY DBE TRUCKING REPORTS (BDE)	27
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	27
WORK ZONE WIDTH RESTRICTION (BDE)	29
WORKING DAYS (BDE)	29

Revised 9/9/2026

PUBLIC CONVENIENCE AND SAFETY (D1)

Effective: May 1, 2012

Revised: July 15, 2012

Add the following to the end of the fourth paragraph of Article 107.09:

“If the holiday is on a Saturday or Sunday, and is legally observed on a Friday or Monday, the length of Holiday Period for Monday or Friday shall apply.”

Add the following sentence after the Holiday Period table in the fourth paragraph of Article 107.09:

“The Length of Holiday Period for Thanksgiving shall be from 5:00 AM the Wednesday prior to 11:59 PM the Sunday After”

Delete the fifth paragraph of Article 107.09 of the Standard Specifications:

“On weekends, excluding holidays, roadways with Average Daily Traffic of 25,000 or greater, all lanes shall be open to traffic from 3:00 P.M. Friday to midnight Sunday except where structure construction or major rehabilitation makes it impractical.”

TOLLWAY PERMIT AND BOND (D1)

Effective: January 13, 1989

The Contractor will be required to obtain a permit from the Illinois State Toll Highway Authority (ISTHA) according to Article 107.04 of the Standard Specifications prior to initiating any lane closures on the Tollway or doing any work on the ISTHA right of way. As part of the permit, the Contractor will be required to post a surety bond with the ISTHA.

The Contractor will furnish a copy of the authorized permit to the Engineer.

Revised 9/9/2026

TRAFFIC CONTROL PLAN (D1)

Effective: September 30, 1985

Revised: January 1, 2007

Traffic Control shall be according to the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans, and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contact the District One Bureau of Traffic at least 72 hours in advance of beginning work.

STANDARDS: 701006, 701101, 701411, 701421, 701501, 701502, 701601, 701606, 701701, 701801, 701901

DETAILS:

TC-08: Entrance and Exit Ramp Closure Details.

TC-10: Traffic Control and Protection for Side Roads, Intersections & Driveways

TC-17: Traffic Control Details For freeway Shoulder Closures and Partial Ramp Closures.

SPECIAL PROVISIONS:

Public Convenience and Safety (D1)

Keeping the Tollway Open to Traffic

Temporary Information Signing

Traffic Control and Protection (Expressways)

Keeping Arterial Roadways open to Traffic (Lane Closures only)

Tollway Permit and Bond (D1)

Vehicle and Equipment Warning Lights (BDE)

Work Zone Traffic Control Devices (BDE)

Work Zone Width Restrictions (BDE)

Revised 9/9/2026

This page intentionally left blank

Revised 9/9/2026

Revise Articles 1106.02(g), 1106.02(k), 1106.02(l), and 1106.02(m) of the Standard Specifications to read:

“(g) Truck Mounted/Trailer Mounted Attenuators. The attenuator shall be approved for use at Test Level 3. Test Level 2 may be used for normal posted speeds less than or equal to 45 mph.

(k) Temporary Water Filled Barrier. The water filled barrier shall be a lightweight plastic shell designed to accept water ballast and be on the Department’s qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings.

(l) Movable Traffic Barrier. The movable traffic barrier shall be on the Department’s qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings. The barrier shall be capable of being moved on and off the roadway on a daily basis.

(m) Detectable Pedestrian Channelizing Barricades. The top panel or handrail shall be continuous and there should be at least a 2 in. (50 mm) gap between the hand trailing edge and its support. When visible to vehicular traffic, the top rail shall have alternating white and orange retroreflective stripes sloping at 45 degrees. The bottom panel shall be continuous and have alternating white and orange retroreflective stripes sloping at 45 degrees. Barricade stripes shall be 6 in. (150 mm) in width. The predominant color for other barricade components shall be white, orange, or silver.”

WORK ZONE WIDTH RESTRICTION (BDE)

Effective: July 1, 2026

Revise the second paragraph of Article 701.06 of the Standard Specifications to read:

“Where the clear width through a work zone will be 17.5 ft (5.34 m) or less, the Contractor shall notify the Engineer at least 21 days in advance of implementing the traffic control for that restriction.”

WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within 40 working days.

Revised 9/9/2026