

MODEL: GenNotesSh01 [Sheet]
FILE NAME: c:\paw_work\paw\illinois.gov_merlin.jose@illinois.gov\1066639\109825-sh1t-gennote.dgn

INDEX OF SHEETS

STATE STANDARDS

GENERAL NOTES

SHEET NO.	DESCRIPTION
1	TITLE SHEETS
2	INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	SCHEDULE OF QUANTITIES
5-11	LOCATION MAPS
12	EXISTING BRIDGE PLANS (LOCATION NO. 1 SN 049-0065)
13	EXISTING BRIDGE PLANS (LOCATION NO. 2 SN 049-0064)
14	EXISTING BRIDGE PLANS (LOCATION NO. 3 SN 049-0096)
15	EXISTING BRIDGE PLANS (LOCATION NO. 4 SN 049-0199)
16	EXISTING BRIDGE PLANS (LOCATION NO. 5 SN 049-0063)
17	EXISTING BRIDGE PLANS (LOCATION NO. 6 SN 049-0017)
18	EXISTING BRIDGE PLANS (LOCATION NO. 7 SN 049-0167)
19	EXISTING BRIDGE PLANS (LOCATION NO. 8 SN 049-0019)
20	EXISTING BRIDGE PLANS (LOCATION NO. 9 SN 049-0601)
21	EXISTING BRIDGE PLANS (LOCATION NO. 10 SN 049-0175)
22	EXISTING BRIDGE PLANS (LOCATION NO. 11 SN 049-0198)
23	EXISTING BRIDGE PLANS (LOCATION NO. 12 SN 049-0178)
24	EXISTING BRIDGE PLANS (LOCATION NO. 13 SN 049-0055)
25	EXISTING BRIDGE PLANS (LOCATION NO. 14 SN 049-0195)
26	EXISTING BRIDGE PLANS (LOCATION NO. 15 SN 049-0533)
27	EXISTING BRIDGE PLANS (LOCATION NO. 16 SN 049-0534)
28	EXISTING BRIDGE PLANS (LOCATION NO. 17 SN 049-0028)
29	EXISTING BRIDGE PLANS (LOCATION NO. 18 SN 049-0163)
30	EXISTING BRIDGE PLANS (LOCATION NO. 19 SN 049-0201)
31	EXISTING BRIDGE PLANS (LOCATION NO. 20 SN 049-0118)
32	EXISTING BRIDGE PLANS (LOCATION NO. 21 SN 049-0164)
33	EXISTING BRIDGE PLANS (LOCATION NO. 22 SN 049-0159)
34	EXISTING BRIDGE PLANS (LOCATION NO. 23 SN 049-0220)
35	EXISTING BRIDGE PLANS (LOCATION NO. 24 SN 049-9901)
36	EXISTING BRIDGE PLANS (LOCATION NO. 25 SN 049-0221)
37	EXISTING BRIDGE PLANS (LOCATION NO. 26 SN 049-0222)
37	EXISTING BRIDGE PLANS (LOCATION NO. 27 SN 049-0179)
38	EXISTING BRIDGE PLANS (LOCATION NO. 28 SN 049-0126)
38	EXISTING BRIDGE PLANS (LOCATION NO. 29 SN 049-0125)
39	EXISTING BRIDGE PLANS (LOCATION NO. 30 SN 049-0048)
40	EXISTING BRIDGE PLANS (LOCATION NO. 31 SN 049-0049)
40	EXISTING BRIDGE PLANS (LOCATION NO. 32 SN 049-0129)
41	EXISTING BRIDGE PLANS (LOCATION NO. 33 SN 049-0130)
41	EXISTING BRIDGE PLANS (LOCATION NO. 34 SN 049-0209)
42	EXISTING BRIDGE PLANS (LOCATION NO. 35 SN 049-0016)
43	EXISTING BRIDGE PLANS (LOCATION NO. 36 SN 049-0087)
44	EXISTING BRIDGE PLANS (LOCATION NO. 37 SN 049-0051)
45	EXISTING BRIDGE PLANS (LOCATION NO. 38 SN 049-0050)
46	ENTRANCE AND EXIT RAMP CLOSURE DETAILS (TC-08)
47	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS INTERSECTION AND DRIVEWAYS (TC-10)
48	TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES (TC-17)
49	ARTERIAL ROAD INFORMATION SIGNING (TC-22)

STANDARD NO.	DESCRIPTION
000001-09	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
701411-09	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS > 45 MPH
701428-01	TRAFFIC CONTROL SETUP AND REMOVAL, FREEWAY/EXPRESSWAY
701501-06	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701502-09	URBAN LANE CLOSURE, 2L, 2W, WITH BIDIRECTIONAL LEFT TURN LANE
701601-09	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NON TRAVERSABLE MEDIAN
701606-10	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701-10	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-06	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901-10	TRAFFIC CONTROL DEVICES
701006-05	OFF-ROAD OPERATIONS, 2L, 2W, 15' (4.5M) TO 24" (600MM) FROM PAVEMENT EDGE
701101-05	OFF-ROAD OPERATIONS, MULTILANE 15' (4.5M) TO 24" (600MM) FROM PAVEMENT EDGE
701421-08	LANE CLOSURE , MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS > 45 MPH TO 55 MPH

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, THE CITIES OF WAUKEGAN AND NORTH CHICAGO, AND THE VILLAGES OF WADSWORTH, GURNEE, GREEN OAKS, FOX LAKE, LIBERTYVILLE, LONG LAKE, ANTIOCH, CHANNEL LAKE AND LAKE VILLA.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM THE BUREAU OF MAINTENANCE BRIDGE INSPECTORS

IT SHALL BE CONTRACTORS RESPONSIBILITY TO PROTECT AND MAINTAIN THE EXISTING BRIDGE LIGHTING AT ANY LOCATIONS THAT LIGHTING IS ENCOUNTERED .

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION.

WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHTTIME OPERATIONS,THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJACENT RESIDENTIAL AREAS.

THE CONTRACTOR SHALL TAKE NECESSARY PRECAUTIONS WHEN WORKING NEAR THE ABUTMENTS IF ELECTRICAL JUNCTION BOXES AND ATTACHED CONDUITS ARE PRESENT

THE "ARTERIAL ROAD INFORMATION SIGN (TC-22) IS APPLICABLE ONLY TO ARTERIAL ROADS AND SHALL NOT BE APPLIED TO EXPRESSWAYS/TOLLWAYS

THE CONTRACTOR SHALL CONTACT THE DISTRICT TRAFFIC CONTROL SUPERVISOR AT KALPANA.KANNAN-HOSADURGA@ILLINOIS.GOV A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE RESIDENT ENGINEER SHALL CONTACT BRANDY KENNEDEY AREA TRAFFIC CONTROL SUPERVISOR AT BRANDY-KENNEDY@ILLINOIS.GOV A MINIMUM OF TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMENANT PAVEMENT MARKERS

EXISTING PAVEMENT MARKINGS SHALL BE TEMPORARILY COVERED PRIOR TO APPLICATION OF THE DECK SURFACE TREATMENT TO PREVENT THE MATERIAL FROM BEING APPLIED TO THE MARKINGS. THE TEMPORARY COVERING MATERIAL USED SHALL BE SUCH THAT IT WILL NOT AFFECT THE MARKING'S REFLECTIVITY WHEN REMOVED AFTER APPLICATION OF THE DECK SURFACE TREATMENT AND PRIOR TO OPENING TO TRAFFIC COST INCLUDED WITH CONCRETE SEALER.

THE CONTRACTOR SHALL TAKE NECESSARY PRECAUTIONS TO INSURE THAT NO DEBRIS WILL ENDANGER OR INTERFERE WITH TRAFFIC ON THE ROADWAY OR BENEATH THE BRIDGE ACCORDING TO ARTICLE 107.09 OF THE STANDARD SPECIFICATION. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR THE APPROPRIATE PAY ITEM INVOLVED AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

1 REVISED SHEET 9/4/2026

	USER NAME = Merlin.Jose	DESIGNED -	REVISED - 1 9/3/26 MJ	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					VAR	2024-1059-BDS	Lake	50	2
	PLOT SCALE = 0.16666633 ' / In.	CHECKED -	REVISED -					CONTRACT NO. 62Y03				
	PLOT DATE = 8/19/2026	DATE -	REVISED -		SCALE:	SHEET	OF 11 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		

1

	SN 049-0065	SN 049-0064	SN 049-0096	SN 049-0199	SN 049-0063	SN 049-0017	SN 049-0167	SN 049-0019	SN 049-0601	SN 049-0175	SN 049-0198	SN 049-0178	SN 049-0055	SN 049-0195	SN 049-0533	SN 049-0534	SN 049-0028	SN 049-0163	SN 049-0201
LOCATION	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
BRIDGE DECK CONCRETE SEALER (SQ FT)	18451	29235	15643	6000	11592	1946	60195	9157	6318	3264	7559	11893	1628	2896	10818	12023	5112	10413	27747
TRAFFIC CONTROL AND PROTECTION, STANDARD 701501						X			X	X	X	X	X	X					
TRAFFIC CONTROL AND PROTECTION, STANDARD 701502																			X
TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	X	X	X	X													X	X	
TRAFFIC CONTROL AND PROTECTION, STANDARD 701606					X		X	X											
TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	X	X		X											X	X			
TRAFFIC CONTROL AND PROTECTION, STANDARD 701801				X			X	X							X	X			X
TRAFFIC CONTROL AND PROTECTION, STANDARD 701421									X								X	X	
TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS) [TC-08,TC17,STANDARD 701411]	X	X																	
KEEPING THE TOLLWAY OPEN TO TRAFFIC	X	X																	
TOLLWAY PERMIT AND BOND	X	X																	
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY)					X		X	X	X								X		
NIGHTTIME WORKZONE LIGHTING	X	X																	

	SN 049-0118	SN 049-0164	SN 049-0159	SN 049-0220	SN 049-9901	SN 049-0221	SN 049-0222	SN 049-0179	SN 049-0126	SN 049-0125	SN 049-0048	SN 049-0049	SN 049-0129	SN 049-0130	SN 049-0209	SN 049-0016	SN 049-0087	SN 049-0051	SN 049-0050
LOCATION	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38
BRIDGE DECK CONCRETE SEALER (SQ FT)	14011	7157	6787	31537	22163	11277	14007	43218	13513	13238	6771	6771	6646	6646	71861	19253	9783	24643	22957
TEMPORARY INFORMATION SIGNING (SQFT) (TC-08)																			51.8
TRAFFIC CONTROL AND PROTECTION, STANDARD 701501																			
TRAFFIC CONTROL AND PROTECTION, STANDARD 701502		X																	
TRAFFIC CONTROL AND PROTECTION, STANDARD 701601					X			X								X		X	
TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	X																		
TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	X	X						X								X			
TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	X	X			X			X											
TRAFFIC CONTROL AND PROTECTION, STANDARD 701421			X	X		X	X		X	X	X	X	X	X	X			X	X
TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS) [TC-08,TC17,STANDARD 701411]				X		X	X	X	X	X	X	X	X	X			X	X	X
KEEPING THE TOLLWAY OPEN TO TRAFFIC				X		X	X												
TOLLWAY PERMIT AND BOND				X		X	X												
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY)				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
NIGHTTIME WORKZONE LIGHTING				X		X	X		X	X	X	X	X	X					

1 REVISED ENTIRE SHEET 9/4/2026

MODEL: Schedule01 [Sheet]
FILE NAME: c:\paw_work\work\illinois.gov_merlin.jose@illinois.gov\1066639\109825-shit-schedule.dgn

	USER NAME = Merlin.Jose		DESIGNED -	REVISED -  9/3/26 MJ	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES		F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN -		REVISOR -	REVISION -				VAR	2024-1059-BDS	Lake	49	4
	PLOT SCALE = 0.16666633" / In.		CHECKED -	REVISOR -		SCALE:		CONTRACT NO. 62Y03				
	PLOT DATE = 8/19/2026		DATE -	REVISION -		SHEET	OF 11 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		