



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 14, 2026

SUBJECT: FAU 3561 (Willow Road)
Section 08-00103-00-FP (Winnetka)
Cook County
Contract No. 61M29
Item 024
September 18, 2026 Letting
Addendum (B)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Page 10 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

EARTH EXCAVATION

202.03 Removal and Disposal of Surplus, Unsuitable, and Organic Materials: Add the following;

The Contractor may seek approval from the Village of Winnetka to dispose of surplus materials related to this contract at the Village's closed landfill located at Willow Road. Surplus materials that will be accepted at the landfill include clean, inorganic clay meeting the recommendations of the Engineer. The clean inorganic clay must have a pH value between 6.25 and 9.0, inclusive. The Contractor shall perform the pH testing and provide the results to the Village at no additional cost. The following materials will not be accepted by the Village at the closed landfill;

- Concrete
- Restricted-use miscellaneous materials according to Article 1009.04.
- Organic material and topsoil.
- Sand.
- Materials with pH values below 6.25 and above 9.0.
- Regulated substances according to Section 669.

All materials, equipment, testing, dust control, and labor needed to dump and spread surplus materials at the closed landfill will not be paid for separately and shall be included in the cost of EARTH EXCAVATION, REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS, and STRUCTURE EXCAVATION.

202.04 Classification: Add the following;

Stripping and disposal of existing topsoil will be paid for as EARTH EXCAVATION.

All posts, railroad ties, and decorative timber in conflict with the proposed improvements shall be removed and relocated as determined by the Engineer at the time of construction. Every effort shall be made by the Contractor when removing these items to preserve them from harm. Items not relocated shall be properly disposed of by the Contractor. This work shall be included in the cost of EARTH EXCAVATION.

AGGREGATE SURFACE COURSE FOR TEMPORARY ACCESS (D1)

Effective: April 1, 2001

Revised: January 2, 2007

Revise Article 402.10 of the Standard Specifications to read:

"402.10 For Temporary Access. The contractor shall construct and maintain aggregate surface course for temporary access to private CURBs, commercial entrances and roads according to Article 402.07 and as directed by the Engineer.

The aggregate surface course shall be constructed to the dimensions and grades specified below, except as modified by the plans or as directed by the Engineer.