



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 8, 2026

SUBJECT: FAI Route 80 (I-80)
Project NHPP-RBDM(511)
Section (37-(3-1,4,5,6))BRR
Henry County
Contract No. 64T43
Item No. 34, September 18, 2026 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page iii of the Table of Contents to the Special Provisions.
3. Revised page 125 to the Special Provisions.
4. Revised sheets 4-8, 10, 11-13, 20, 25-49, 94, 96, 100-104, 120, 128, and 129 of the plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

WEEKLY DBE TRUCKING REPORTS (BDE).....	122
WORK ZONE TRAFFIC CONTROL DEVICES (BDE).....	123
WORK ZONE WIDTH RESTRICTION (BDE).....	125
WORKING DAYS (BDE)	125
COARSE AGGREGATE FOR PIPE UNDERDRAINS FOR STRUCTURES	125

Revised September 8, 2026

WORK ZONE WIDTH RESTRICTION (BDE)

Effective: July 1, 2026

Revise the second paragraph of Article 701.06 of the Standard Specifications to read:

“Where the clear width through a work zone will be 17.5 ft (5.34 m) or less, the Contractor shall notify the Engineer at least 21 days in advance of implementing the traffic control for that restriction.”

WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within **110** working days.

COARSE AGGREGATE FOR PIPE UNDERDRAINS FOR STRUCTURES

Revise the application “Bedding and Backfill for Pipe Underdrains, Type 2” in the table of Article 1004.05(c) of the Specifications to read: “Bedding and Backfill for Pipe Underdrains, Type 2 and Bedding and Backfill for Pipe Underdrains for Structures”.

Aggregate for Bedding and Backfill for Pipe Underdrains for Structures shall be included in the contract unit price for PIPE UNDERDRAINS FOR STRUCTURES.

Revised September 8, 2026