

MODEL: SOQ (Sheet)
FILE NAME: C:\SP\WHKS & CO\Jobs-Spring - Projects\DOT D-3\9712.00 D-3 On-Call\9712.15 050-0047 and 0251 PSE\ICADD Data\Sheets\ID6692-shr-SOQ.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE
				NHPP	NHPP
				80% FED / 20% STATE	80% FED / 20% STATE
				BRIDGE	BRIDGE
				0013 S.N. 050-0047	0010 S.N. 050-0251
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	956	956	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	132	132	
20101000	TEMPORARY FENCE	FOOT	110		110
20200100	EARTH EXCAVATION	CU YD	235	130	105
20300100	CHANNEL EXCAVATION	CU YD	142		142
20400800	FURNISHED EXCAVATION	CU YD	1050	545	505
25000210	SEEDING, CLASS 2A	ACRE	0.5		0.5
25000300	SEEDING, CLASS 3	ACRE	0.75	0.75	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	93	68	25
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	93	68	25
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	93	68	25
25100115	MULCH, METHOD 2	ACRE	0.25		0.25
25100630	EROSION CONTROL BLANKET	SQ YD	3910	3191	719
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	131	75	56

Design firm
No. 184001036

whks

engineers + planners + land surveyors

USER NAME = kfair	DESIGNED - KNF	REVISED -
	DRAWN - KNF	REVISED -
PLOT SCALE = 99.99980000' / in.	CHECKED - LNJ	REVISED -
PLOT DATE = 5/21/2026	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
FAP 68 (IL 23)

SCALE: SHEET 1 OF 10 SHEETS STA. TO STA.

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	(1BR)D,(1BR-1)BR-1	LASALLE	144	5
CONTRACT NO. 66926				
ILLINOIS FED. AID PROJECT				

MODEL: SOQ-1 (Sheet)
FILE NAME: C:\SP\WHKS & CO\Jobs-Spring - Projects\IDOT D-3\9712.00 D-3 On-Call\9712.15 050-0047 and 0251 PSE\CADD Data\Sheets\036692.sht-SOQ.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE
				NHPP	NHPP
				80% FED / 20% STATE	80% FED / 20% STATE
				BRIDGE	BRIDGE
				0013	0010
				S.N. 050-0047	S.N. 050-0251
28000400	PERIMETER EROSION BARRIER	FOOT	2978	2101	877
28000500	INLET AND PIPE PROTECTION	EACH	1		1
28100107	STONE RIPRAP, CLASS A4	SQ YD	1331	111	1220
28200200	FILTER FABRIC	SQ YD	1339	119	1220
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	246	227	19
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	74	49	25
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	4185	2567	1618
40600370	LONGITUDINAL JOINT SEALANT	FOOT	1384	893	491
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	106	106	
40600990	TEMPORARY RAMP	SQ YD	188	112	76
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	21	21	
40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	364	234	130
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	18	18	
42000060	WELDED WIRE REINFORCEMENT	SQ YD	277	142	135

design firm
No. 184001036


engineers + planners + land surveyors

USER NAME = kfair	DESIGNED - KNF	REVISED -
	DRAWN - KNF	REVISED -
PLOT SCALE = 99.99980000' / in.	CHECKED - LNJ	REVISED -
PLOT DATE = 5/21/2026	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
FAP 68 (IL 23)

SCALE: SHEET 2 OF 10 SHEETS TO STA.

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	(1BR)D,(1BR-1)BR-1	LASALLE	144	6
CONTRACT NO. 66926				
ILLINOIS FED. AID PROJECT				

MODEL: SQ02 [Sheet]
FILE NAME: C:\SP\WHKS & CO\Jobs-Spring - Projects\DOT D-3\9712.00 D-3 On-Call\9712.15 050-0047 and 0251 PSEICADD\10.12\CADD Data\Sheet\036692-shh-SQ0.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE
				NHPP	NHPP
				80% FED / 20% STATE	80% FED / 20% STATE
				BRIDGE	BRIDGE
				0013	0010
				S.N. 050-0047	S.N. 050-0251
42000080	PAVEMENT CONNECTOR (PCC) FOR BRIDGE APPROACH SLAB	SQ YD	325	212	113
44000100	PAVEMENT REMOVAL	SQ YD	260	135	125
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 13/4"	SQ YD	1267		1267
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	34		34
44004000	PAVED DITCH REMOVAL	FOOT	227	227	
44004250	PAVED SHOULDER REMOVAL	SQ YD	1577	1198	379
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	5		5
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1740	1241	499
48203100	HOT-MIX ASPHALT SHOULDERS	TON	82		82
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD	18.9	18.9	
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1	1	
50105220	PIPE CULVERT REMOVAL	FOOT	26	26	
50200100	STRUCTURE EXCAVATION	CU YD	95	31	64

SUMMARY OF QUANTITIES			
FAP 68 (IL 23)			
SCALE:	SHEET 3	OF 10 SHEETS	STA. TO STA.

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	(1BR)D,(1BR-1)BR-1	LASALLE	144	7
CONTRACT NO. 66926				
ILLINOIS FED. AID PROJECT				

MODEL: SQQ-3 [Sheet]
FILE NAME: C:\SP\WHKS & CO\Jobs-Spring - Projects\IDOT D-3\9712.00 D-3 On-Call\9712.15 050-0047 and 0251 PSEICADD\10.12\CADD Data\Sheet\036692.sht-SQQ.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE
				NHPP 80% FED / 20% STATE	NHPP 80% FED / 20% STATE
				BRIDGE	BRIDGE
				0013 S.N. 050-0047	0010 S.N. 050-0251
50300225	CONCRETE STRUCTURES	CU YD	113.5	27.2	86.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	435.7	255.7	180
50300260	BRIDGE DECK GROOVING	SQ YD	1476	869	607
50300300	PROTECTIVE COAT	SQ YD	1857	1107	750
50301350	CONCRETE SUPERSTRUCTURE (APPROACH SLAB)	CU YD	225.4	106.0	119.4
50401315	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BEAMS, IL36N	FOOT	498		498
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3370	3370	
50500505	STUD SHEAR CONNECTORS	EACH	1704	1704	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	197390	107730	89660
50800515	BAR SPLICERS	EACH	1353	768	585
50800530	MECHANICAL SPLICERS	EACH	18	18	
51200963	FURNISHING METAL SHELL PILES 16" X 0.375"	FOOT	325		325
51202305	DRIVING PILES	FOOT	325		325
51203200	TEST PILE METAL SHELLS	EACH	2		2

SUMMARY OF QUANTITIES FAP 68 (IL 23)			
SCALE:	SHEET 4	OF 10 SHEETS	STA. TO STA.

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	(1BR)D,(1BR-1)BR-1	LASALLE	144	8
CONTRACT NO. 66926				
ILLINOIS FED. AID PROJECT				

design firm no. 184001036  engineers + planners + land surveyors	USER NAME = kfair	DESIGNED - KNF	REVISED -
		DRAWN - KNF	REVISED -
	PLOT SCALE = 99.99980000' / in.	CHECKED - LNJ	REVISED -
	PLOT DATE = 5/21/2026	DATE -	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		

MODEL: SQ0-4 [Sheet]
FILE NAME: C:\SP\WHKS & CO\Jobs-Spring - Projects\IDOT D-3\9712.00 D-3 On-Call\9712.15 050-0047 and 0251 PSEICADD\10.12\CADD Data\SheetID38682.sht-SQ.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE
				NHPP 80% FED / 20% STATE	NHPP 80% FED / 20% STATE
				BRIDGE	BRIDGE
				0013 S.N. 050-0047	0010 S.N. 050-0251
51204650	PILE SHOES	EACH	10		10
51500100	NAME PLATES	EACH	2	1	1
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12	12	
52100510	ANCHOR BOLTS, 3/4"	EACH	48	48	
52200010	TEMPORARY SHEET PILING	SQ FT	195	195	
52200020	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	78		78
* 53212754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	14	14	
58600101	GRANULAR BACKFILL FOR STRUCTURES	CU YD	227	80	147
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	156	70	86
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	5	5	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	4		4
60146304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	252	110	142
60500060	REMOVING INLETS	EACH	1	1	
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	3	3	

1

design firm
no. 184001036

whks

engineers + planners + land surveyors

USER NAME = kfair	DESIGNED - KNF	REVISED -
	DRAWN - KNF	REVISED -
PLOT SCALE = 99.99980000' / in.	CHECKED - LNJ	REVISED -
PLOT DATE = 5/21/2026	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES FAP 68 (IL 23)			
SCALE:	SHEET 5	OF 10 SHEETS	STA. TO STA.

FAP RTE. 68	SECTION (1BR)D,(1BR-1)BR-1	COUNTY LASALLE	TOTAL SHEETS 144	SHEET NO. 9
CONTRACT NO. 66926				
ILLINOIS FED. AID PROJECT				

MODEL: SQ0-5 [Sheet]
FILE NAME: C:\SP\WHKS & CO\Jobs-Spring - Projects\IDOT D-319712.00 D-3 On-Call\9712.15 050-0047 and 0251 PSEICADD\10.12\CADD Data\SheetID38682.sht-SQ0.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE
				NHPP	NHPP
				80% FED / 20% STATE	80% FED / 20% STATE
				BRIDGE	BRIDGE
				0013	0010
				S.N. 050-0047	S.N. 050-0251
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	34		34
60920018	PIPE CULVERTS TO BE CLEANED 18"	FOOT	64		64
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1413	1063	350
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	7	4	3
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	6	3	3
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) FLARED	EACH	1	1	
63200310	GUARDRAIL REMOVAL	FOOT	1368	1368	
64300260	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1		1
64301090	ATTENUATOR BASE	SQ YD	34		34
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	4	4
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	70	35	35

*= SPECIALTY ITEM

design firm
no. 184001036

whks

engineers + planners + land surveyors

USER NAME = kfair	DESIGNED - KNF	REVISED -
	DRAWN - KNF	REVISED -
PLOT SCALE = 99.99980000' / in.	CHECKED - LNJ	REVISED -
PLOT DATE = 5/21/2026	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
FAP 68 (IL 23)			
SCALE:	SHEET 6	OF 10 SHEETS	STA. TO STA.

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	(1BR)D,(1BR-1)BR-1	LASALLE	144	10
CONTRACT NO. 66926				
ILLINOIS FED. AID PROJECT				

MODEL: SQQ-6 (Sheet)
FILE NAME: C:\SP\WHKS & CO\Jobs-Spring - Projects\IDOT D-319712.00 D-3 On-Call\9712.15 050-0047 and 0251 PSEICADD\10.12\CADD Data\SheetID38692.sht-SQQ.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE
				NHPP	NHPP
				80% FED / 20% STATE	80% FED / 20% STATE
				BRIDGE	BRIDGE
				0013	0010
				S.N. 050-0047	S.N. 050-0251
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1	1
70106700	TEMPORARY RUMBLE STRIPS	EACH	12	6	6
70300100	SHORT TERM PAVEMENT MARKING	FOOT	773	288	485
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	262	96	166
70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	FOOT	2708		2708
70307130	TEMPORARY PAVEMENT MARKING - LINE 6" - TYPE IV TAPE	FOOT	340		340
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1350	550	800
70400125	PINNING TEMPORARY CONCRETE BARRIER	EACH	96	78	18
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1275	525	750
70500100	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	200	200	
70500665	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
70600251	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	2	2
70600352	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE,NARROW), TEST LEVEL 3	EACH	4	2	2
* 72000100	SIGN PANEL - TYPE 1	SQ FT	6	6	

*= SPECIALTY ITEM

design firm
no. 184001036

whks

engineers + planners + land surveyors

USER NAME = kfair	DESIGNED - KNF	REVISED -
	DRAWN - KNF	REVISED -
PLOT SCALE = 99.99980000 ' / in.	CHECKED - LNJ	REVISED -
PLOT DATE = 5/21/2026	DATE -	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SUMMARY OF QUANTITIES FAP 68 (IL 23)			CONTRACT NO. 66926	
SCALE:	SHEET 7	OF 10	SHEETS	STA.	TO STA.	
						ILLINOIS FED. AID PROJECT

MODEL: SQ0-7 [Sheet]
FILE NAME: C:\SP\WHKS & CO\Jobs-Spring - Projects\IDOT D-319712.00 D-3 On-Call\9712.15 050-0047 and 0251 PSEICADD\10.12\CADD Data\SheetID36692.sht-SQ0.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE
				NHPP	NHPP
				80% FED / 20% STATE	80% FED / 20% STATE
				BRIDGE	BRIDGE
				0013	0010
				S.N. 050-0047	S.N. 050-0251
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	1		1
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	18	6	12
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1		1
* 72501000	TERMINAL MARKER - DIRECT APPLIED	EACH	7	4	3
73000100	WOOD SIGN SUPPORT	FOOT	30	16	14
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	11978	6564	5414
* 78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	1297	620	677
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	28	12	16
* 78200005	GUARDRAIL REFLECTORS, TYPE A	EACH	20	10	10
* 78200011	BARRIER WALL REFLECTORS, TYPE C	EACH	8	4	4
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	28	12	16
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	2538	388	2150
X4062952	HOT-MIX ASPHALT STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL	SQ YD	757	552	205
X4201410	BRIDGE APPROACH PAVEMENT CONNECTOR (SPECIAL)	SQ YD	90		90

*= SPECIALTY ITEM

design firm
no. 184001036

whks

engineers + planners + land surveyors

USER NAME = kfair	DESIGNED - KNF	REVISED -
	DRAWN - KNF	REVISED -
PLOT SCALE = 99.99980000" / in.	CHECKED - LNJ	REVISED -
PLOT DATE = 5/21/2026	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES FAP 68 (IL 23)			
SCALE:	SHEET 8	OF 10 SHEETS	STA. TO STA.

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	(1BR)D,(1BR-1)BR-1	LASALLE	144	12
CONTRACT NO. 66926				
ILLINOIS FED. AID PROJECT				

MODEL: SQ0-8 (Sheet)
FILE NAME: C:\SP\WHKS & CO\Jobs-Spring - Projects\IDOT D-3\9712.00 D-3 On-Call\9712.15 050-0047 and 0251 PSEICADD\10.12\CADD Data\SheetID36692.sht-SQ.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE
				NHPP	NHPP
				80% FED / 20% STATE	80% FED / 20% STATE
				BRIDGE	BRIDGE
				0013	0010
				S.N. 050-0047	S.N. 050-0251
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	3139	2264	875
X5010523	REMOVE CONCRETE END SECTION	EACH	1	1	
X5080530	BAR TERMINATORS	EACH	656	136	520
X5110308	SLOPE WALL CRACK SEALING	FOOT	50	50	
X5110310	SLOPE WALL REPAIR	SQ YD	5	5	
X5230174	DRAINAGE SCUPPERS, DS-11	EACH	2	2	
X6061460	PAVED DITCH (SPECIAL)	FOOT	211	211	
X6320100	GUARDRAIL REMOVAL (SPECIAL)	FOOT	670		670
X6350120	DELINEATOR REMOVAL	EACH	2	2	
X6350204	LINEAR DELINEATOR PANELS, 4 INCH	EACH	26	16	10
X6350206	LINEAR DELINEATOR PANELS, 6 INCH	EACH	8	6	2
X6640108	FENCE REMOVAL AND REINSTALLATION	FOOT	82	82	
* X6670106	FURNISH PERMANENT SURVEY MARKERS	EACH	1	1	
X7200061	TEMPORARY INFORMATION SIGNING	SQ FT	84	42	42

*= SPECIALTY ITEM

MODEL: SQQ-9 [Sheet]
FILE NAME: C:\SP\WHKS & CO\Jobs-Spring - Projects\DOT D-3\9712.00 D-3 On-Call\9712.15 050-0047 and 0251 PSEICADD\10.12\CADD Data\Sheets\D36682-eh-SQQ.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE
				NHPP	NHPP
				80% FED / 20% STATE	80% FED / 20% STATE
				BRIDGE	BRIDGE
				0013	0010
				S.N. 050-0047	S.N. 050-0251
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	12	12	
Z0007101	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1	
Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	1	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1		1
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	63	63	
* 66901001	REGULATED SUBSTANCES PRECONSTRUCTION PLAN	L SUM	1	1	
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA	6	6	
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1	
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1	
Ø Z0076600	TRAINEES	hour	1,000	1,000	
Ø Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	hour	1,000	1,000	

*= SPECIALTY ITEM Ø 0042