

MODEL: 72406 SOQ-2 (Sheet)
FILE NAME: c:\pwworking\andrew.cisler@illinois.gov\d115961772406-shl-SOQ.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	6-01119-0200	6-01119-0200
				80% FEDERAL 20% STATE	100% MISSOURI
				BRIDGE	BRIDGE
				0047	0047
				001-0068	001-0068
* 81300420	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 10" X 8" X 6"	EACH	19.0	9.5	9.5
* 81702100	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 12	FOOT	1,938	969	969
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	958	479	479
* 82110007	LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION G	EACH	19.0	9.5	9.5
* 82200608	WATERWAY OBSTRUCTION WARNING LUMINAIRE, LED, 180 DEGREE RED	EACH	8	4	4
* 82200609	WATERWAY OBSTRUCTION WARNING LUMINAIRE, LED, 360 DEGREE GREEN	EACH	4	2	2
* 82200705	AVATION OBSTRUCTION WARNING LUMINAIRE, LED	EACH	4	2	2
84301101	REMOVAL OF OBSTRUCTION WARNING LIGHTING UNIT *	EACH	4	2	2
84301201	REMOVAL OF OBSTRUCTION WARNING LIGHTING SYSTEM *	L SUM	1	.5	.5
* X0323631	REMOVE AND REPLACE INTERIOR TOWER INSPECTION LIGHTS	EACH	12	6	6
X1400398	REMOVE LUMINAIRE, COMPLETE	EACH	19.0	9.5	9.5
* X0323633	REMOVE AND REPLACE EXHAUST FAN	EACH	4	2	2
X5030250	BRIDGE DECK GROOVING (LONGITUDINAL)	SQ YD	12,004	6,002	6,002
X5230172	DRAINAGE SCUPPERS TO BE ADJUSTED	EACH	50	25	25
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	.5	.5
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	.5	.5



REVISED 8-31-2026

REV - MS

* SPECIALTY ITEM

USER NAME = andrew.cisler	DESIGNED -	REVISED -
	DRAWN -	REVISED -
	CHECKED -	REVISED -
PLOT DATE = 6/24/2026	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 3 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
63	(12B1)BDR-1	ADAMS	56	5
CONTRACT NO. 72406				
ILLINOIS FED. AID PROJECT				