

MODEL: SC01 [Sheet]
FILE NAME: c:\pw_work\pwidolund\hd099830\ID74D06-shi-sq.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	FAP 776 80 FED/20 STATE	FAI 64 90 FED/10 STATE
				ROADWAY	BRIDGE
				0005 RURAL	0047 S.N. 096-0032
20200100	EARTH EXCAVATION	CU YD	101	101	
21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SQ YD	189	189	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	176	176	
35300510	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/2"	SQ YD	1391	1391	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	158	158	
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	15801	15801	
40600370	LONGITUDINAL JOINT SEALANT	FOOT	6495	6495	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2184	2184	
40600990	TEMPORARY RAMP	SQ YD	102	102	
40602970	HOT-MIX ASPHALT BINDER COURSE, IL-9.5FG, N70	TON	2111	2111	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	34	34	
					⚠
40603219	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL 9.5FG, N90	TON	149	149	
40604052	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N70	TON	2451	2451	
40604164	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N90	TON	171	171	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	22	22	
42000060	WELDED WIRE REINFORCEMENT	SQ YD	58	58	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	57	57	
44000100	PAVEMENT REMOVAL	SQ YD	474	474	

⚠ REVISED 9-4-2026

REV - MS

	USER NAME = levi.lund	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					776	*	WAYNE	81	3
		CHECKED -	REVISED -					CONTRACT NO. 74D06				
	PLOT DATE = 6/24/2026	DATE -	REVISED -		SCALE:	SHEET 1	OF 6	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	

MODEL: SCQ2 [Sheet]
FILE NAME: c:\pw_work\pwidolund\hd099830\ID74D06-shi-sq.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	FAP 776 80 FED/20 STATE	FAI 64 90 FED/10 STATE
				ROADWAY	BRIDGE
				0005 RURAL	0047 S.N. 096-0032
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	12845	12845	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	14613	14613	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	57	57	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3943	3943	
44003100	MEDIAN REMOVAL	SQ FT	1690	1690	
44201299	DOWEL BARS 1 1/2"	EACH	44	44	
44201371	CLASS C PATCHES, TYPE IV, 11 INCH	SQ YD	58	58	
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	360.4	360.4	
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	103.5	103.5	
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	35	35	
44213200	SAW CUTS	FOOT	158	158	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	555	555	
48203012	HOT-MIX ASPHALT SHOULDERS, 3 3/4"	SQ YD	6736	6736	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	453	453	
50102400	CONCRETE REMOVAL	CU YD	38.7		38.7
50157300	PROTECTIVE SHIELD	SQ YD	761		761
50300100	FLOOR DRAINS	EACH	8		8
50300225	CONCRETE STRUCTURES	CU YD	8		8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	38.6		38.6

△ REVISED 9-4-2026

REV - MS

	USER NAME = levi.lund	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					776	*	WAYNE	81	4
		CHECKED -	REVISED -					CONTRACT NO. 74D06				
	PLOT DATE = 6/24/2026	DATE -	REVISED -		SCALE:	SHEET 2	OF 6	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	

MODEL: Schedule1 [Sheet]
FILE NAME: c:\pw_work\pwtdotlund\ld099830\D774D06-sh-schedule.dgn

PAVEMENT SCHEDULE																	
SCHEDULE			HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL, BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL, 1.5 INCH	HOT-MIX ASPHALT SURFACE REMOVAL, 2.5 INCH	BITUMINOUS MATERIALS (TACK COAT) BINDER	BITUMINOUS MATERIALS (TACK COAT) SURFACE	LONGITUDINAL JOINT SEALANT	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	HOT-MIX ASPHALT BINDER COURSE, IL-9.5FG, N70	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX C, N70	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE; IL-9.5, MIX "D" N90	HOT - MIX ASPHALT SHOULDERS, 3 3/4"	HOT - MIX ASPHALT SHOULDERS, 8"	AGGREGATE WEDGE SHOULDERS TYPE B	
STA		TO	STA	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(POUND)	(POUND)	(FOOT)	(TON)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(TON)
67+00.00			62+11.00		122.2		2551.6	714.2	357.1	489.0		155.5	177.8		1086.7		41.8
62+11.00			56+50.00				2956.6	909.5	454.7			198.0	226.4		935.6		47.9
56+50.00			51+53.00		163.9		3100.0	965.6	482.8	632.0		210.3	240.3		1104.4		42.5
51+53.00			48+47.00														
48+47.00			43+28.00		163.9		3254.4	1012.7	506.4	654.0		220.6	252.1		1153.3		44.3
43+28.00			37+86.00				2750.7	875.8	437.9			190.7	218.0		1204.4		46.3
37+86.00			30+25.00	108.4		3607.5		1057.8	528.9	1522.0		230.4	263.3		1251.1	132.0	62.3
30+25.00			363+23.22	STATION EQUATION													
363+23.22			372+24.47			2603.6		1171.6	585.8	901.3		255.2	291.6			300.4	74.1
372+24.47			372+87.50	STATION EQUATION													
372+87.50			395+84.00		130.0	6634.3		2985.5	1492.7	2296.5		650.2	743.1			20.8	5.3
CR 050			338.6	80.0			155.7	77.9		34.0		38.8					190.8
I-64 WB OFF RAMP				431.6			194.2	97.1					48.3				
I-64 WB ON RAMP				337.2			151.7	75.9					37.8				
I-64 EB ON RAMP				359.2			161.6	80.8					40.2				
I-64 EB OFF RAMP				396.1			178.3	89.1					44.4				
		TOTAL:	447	2184	12845	14613	10534	5267	6495	34	2111	2451	171	6736	453		555

PCC SCHEDULE													
SCHEDULE			PORTLAND CEMENT CONCRETE BASE COURSE 10 1/2"	CORRUGATED MEDIAN	COMBINATION CURB AND GUTTER, TYPE M 6.06	COMBINATION CURB AND GUTTER, TYPE M 6.06 (DOWELLED)	CONCRETE MEDIAN SURFACE, 7 INCH	ISLAND PAVEMENT (6")	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	MEDIAN REMOVAL	PAVEMENT REMOVAL	ISLAND REMOVAL	
STA		TO	STA	(SQ YD)	(SQ FT)	(FOOT)	(FOOT)	(SQ FT)	(SQ YD)	(SQ YD)	(SQ FT)	(SQ YD)	(SQFT)
67+00.00			62+11.00									30.8	
62+11.00			56+50.00		740.0	1091.0		170.6	11.7		170.6	82.2	105.8
56+50.00			51+53.00	671.4	280.0	1067.0	386.0	671.4		671.4	119.0		
51+53.00			48+47.00										
48+47.00			43+28.00	719.7			407.0	719.7			719.7	129.0	
43+28.00			37+86.00		297.0	992.0		127.8	12.6		127.8	33.0	125.6
37+86.00			30+25.00		720.0					57.0		80.0	
			TOTAL:	1391	2037	3150	793	1690	24	57	1690	474	231

	USER NAME = levi.lund	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -						776	*	WAYNE	81	13
		CHECKED -	REVISED -						CONTRACT NO. 74D06				
	PLOT DATE = 9/4/2026	DATE -	REVISED -		SCALE:	SHEET 1	OF 3	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT (101, 102) RS-2, (96-2)BDR, BJR		