

MODEL: SQQ (Sheet)
FILE NAME: c:\pw\work\tda\teen\td1223333\0876V26-sh-SQQ.dgn

				CONSTR. CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE ROADWAY 0005
				RURAL
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	25779	25779
40600370	LONGITUDINAL JOINT SEALANT	FOOT	22715	22715
40600990	TEMPORARY RAMP	SQ YD	396	396
40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	4813	4813
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	57287	57287
44200050	WELDED WIRE REINFORCEMENT	SQ YD	3221	3221
44201031	CLASS B PATCHES, TYPE II, 15 INCH	SQ YD	815	815
44201035	CLASS B PATCHES, TYPE III, 15 INCH	SQ YD	436	436
44201037	CLASS B PATCHES, TYPE IV, 15 INCH	SQ YD	3221	3221
44201299	DOWEL BARS 1 1/2"	EACH	4457	4457
44213200	SAW CUTS	FOOT	12776	12776
44213204	TIE BARS 3/4"	EACH	656	656
* 63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	3438	3438
* 63000030	STRONG POST GUARDRAIL ATTACHED TO CULVERT	FOOT	25	25

* SPECIALTY ITEM

				CONSTR. CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE ROADWAY 0005
				RURAL
* 63000350	LONG-SPAN GUARDRAIL OVER CULVERT, 12 FT 6 IN SPAN	FOOT	150	150
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	22	22
63200310	GUARDRAIL REMOVAL	FOOT	5003	5003
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	296	296
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2170	2170
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	369	369
70300221	TEMPORARY PAVEMENT MARKING - LINE 4"- PAINT	FOOT	56365	56365

△ REVISED 9-2-2026

REV - MS

	USER NAME = Joseph.Arteen	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					327	21RS-6,(22,23)RS-3	CLINTON	11	3
		CHECKED -	REVISED -				CONTRACT NO. 76V26					
	PLOT DATE = 6/16/2026	DATE -	REVISED -		SCALE:	SHEET 1	OF 2	SHEETS	STA.	TO STA.		
					ILLINOIS FED. AID PROJECT							

MODEL: Schedule [Sheet]
FILE NAME: c:\paw_work\wkdtdh\humpreys\bd1223338\03876\26-shit-schedule.dgn

PAVEMENT MARKING SCHEDULE												
LOCATION				THERMOPLASTIC AND TEMPORARY PAVEMENT MARKING				TEMPORARY PAVEMENT MARKING REMOVAL - WATER BLASTING	SHORT TERM PAVEMENT MARKING	SHORT TERM PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS	
MILE STA	TO	MILE STA	LENGTH	LINE - 6" THERMOPLASTIC / LINE - 4" TEMPORARY			24" WHITE CROSSWALKS	SQ. FT	FOOT	SQ. FT	AMBER EACH	REMOVAL EACH
			FOOT	WHITE EDGE LINE	YELLOW CENTER LINE	YELLOW 10' - 30' SKIP-DASH						
57.925	TO	57.938	69		275		36	92	10	2		3
57.938	TO	58.006	359		359	90	72	150	40	7		5
58.006	TO	58.636	3326			832	252	278	310	52		42
58.636	TO	58.660	127	254		32		96	20	4		2
STRUCTURE OMISSION												
58.715	TO	59.310	3142	6284		786		2357	290	49		40
59.310	TO	59.720	2165	4330	4330			2887	200	34		28
59.720	TO	59.811	480	961	480	121		521	50	9	7	7
59.811	TO	59.988	935	1870		234		702	90	15	12	12
59.988	TO	60.187	1051	2102		263		1139	100	17	14	14
60.187	TO	60.356	892	1785	1785			1190	90	15	12	12
60.356	TO	60.562	1088	2176	1088	272		1179	100	17	14	14
60.562	TO	60.751	998	1996		250		749	100	17	13	13
60.751	TO	60.934	966	1933	966	242		1048	90	15	13	13
60.934	TO	60.970	190	381		48		143	20	4	3	3
60.970	TO	61.147	935	1870	935	234		1013	90	15	12	12
61.147	TO	61.174	143	286		36		108	20	4	2	2
61.174	TO	61.379	1082	2165	1082	271		1173	100	17	14	14
61.379	TO	61.596	1146	2292	1146	287		1242	110	19	15	15
61.596	TO	62.285	3638	7276		910		2729	340	57	46	46
TOTAL				37961	13496	4908	360	18796	2170	369	177	297

GUARDRAIL SCHEDULE											
LOCATION			LT/RT	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A 9 FOOT POSTS	LONG-SPAN GUARDRAIL OVER CULVERT 12'-6" SPAN	STRONG POST GUARDRAIL ATTACHED TO CULVERT	TRAFFIC BARRIER TERMINAL, TYPE 1, (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 6	GUARDRAIL REFLECTORS, TYPE A	TERMINAL MARKERS DIRECT APPLIED
MILE STA	TO	MILE STA		FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH
58.635	TO	58.660	RT	100	12.5			1	1	4	1
58.635	TO	58.660	LT	100	12.5			1	1	4	1
58.718	TO	58.754	LT	175	87.5			1	1	4	1
58.718	TO	58.754	RT	113	25.0			1	1	4	1
58.846	TO	58.967	RT	663	562.5			2		8	2
58.894	TO	59.209	LT	1650	1550.0			2		21	2
58.973	TO	59.096	RT	650	550.0			2		9	2
59.943	TO	60.012	RT	313	175.0	37.5		2		5	2
59.984	TO	60.024	LT	175	75.0			2		4	2
60.234	TO	60.302	RT	238	100.0	37.5		2		5	2
60.248	TO	60.316	LT	238	100.0	37.5		2		5	2
60.469	TO	60.544	LT	375	100.0	37.5		2		5	2
60.475	TO	60.519	RT	213	87.5		25.0	2		4	2
TOTAL				5003	3438	150	25	22	4	82	22

RESURFACING SCHEDULE							
MILE STATION		DIMENSION		HMA SURFACE REMOVAL 1 1/2"	LONGITUDINAL JOINT SEALANT	BITUMINOUS MATERIALS (TACK COAT)	HMA SURFACE COURSE IL-9.5" MIX D" N70
		LENGTH	WIDTH				
FROM	TO	FEET	FEET	SQ. YD	FEET	POUND	TON
57.925	58.660	3881	26	11211	3881	5045	942
58.660	58.718	STRUCTURE OMISSION					
58.718	58.750	169	24	451	169	203	38
58.750	62.285	18665	22	45625	18665	20531	3833
TOTAL				57287	22715	25779	4813

CLASS B PATCHING SCHEDULE (TABLE 1 OF 3)											
LOCATION		WIDTH	LENGTH	15 INCH			SAW CUTS	DOWEL	TIE	WELDED WIRE	
				TY-II	TY-III	TY-IV				REINFORCEMENT	
MILE STA	EB/WB	FOOT	FOOT	SQ YD	SQ YD	SQ YD	FOOT	EACH	EACH	SQ YD	
57.925	EB	13	10	14.4			59	22			
57.925	EB	13	8	11.6			55	22			
58.025	EB	13	70			101.1	179	62	23	101.1	
58.025	EB	13	6	8.7			51	22			
58.025	EB	13	16		23.1		71	22			
58.125	EB	13	16		23.1		71	22			
58.125	EB	13	10	14.4			59	22			
58.175	EB	13	10	14.4			59	22			
58.225	EB	13	15		21.7		69	22			
58.225	EB	13	6	8.7			51	22			
58.275	EB	13	6	8.7			51	22			
58.325	EB	13	10	14.4			59	22			
58.375	EB	13	85			122.8	209	73	28	122.8	
58.625	EB	13	35			50.6	109	37	12	50.6	
58.725	EB	12.5	45			62.5	128	42	15	62.5	
58.725	EB	12.5	55			76.4	148	49	18	76.4	
58.925	EB	12.5	30			41.7	98	32	10	41.7	
59.125	EB	12.5	15		20.8		68	21			
59.175	EB	12.5	25			34.7	88	28	8	34.7	
59.225	EB	12.5	15		20.8		68	21			
59.325	EB	12.5	15		20.8		68	21			
59.375	EB	12.5	8	11.1			54	21			
59.425	EB	12.5	25			34.7	88	28	8	34.7	
59.525	EB	12.5	10	13.9			58	21			
59.625	EB	12.5	10	13.9			58	21			
59.725	EB	12.5	70			97.2	178	60	23	97.2	
59.825	EB	12.5	6	8.3			50	21			
59.875	EB	12.5	6	8.3			50	21			
59.925	EB	12.5	6	8.3			50	21			
59.975	EB	12.5	6	8.3			50	21			
60.025	EB	12.5	15		20.8		68	21			
60.125	EB	12.5	6	8.3			50	21			
60.175	EB	12.5	6	8.3			50	21			
60.225	EB	12.5	30			41.7	98	32	10	41.7	
60.225	EB	12.5	6	8.3			50	21			
60.275	EB	12.5	60			83.3	158	53	20	83.3	
60.325	EB	12.5	10	13.9			58	21			
60.325	EB	12.5	75			104.2	188	63	25	104.2	
60.325	EB	12.5	6	8.3			50	21			
60.375	EB	12.5	10	13.9			58	21			
60.375	EB	12.5	6	8.3			50	21			
60.425	EB	12.5	25			34.7	88	28	8	34.7	
60.475	EB	12.5	6	8.3			50	21			
60.525	EB	12.5	6	8.3			50	21			
60.575	EB	12.5	20			27.8	78	21		27.8	
60.625	EB	12.5	6	8.3			50	21			
60.725	EB	12.5	18			25.0	74	21		25.0	
60.775	EB	12.5	6	8.3			50	21			
60.825	EB	12.5	15		20.8		68	21			
60.925	EB	12.5	15		20.8		68	21			
60.975	EB	12.5	40			55.6	118	39	13	55.6	
61.025	EB	12.5	18			25.0	74	21		25.0	
61.125	EB	12.5	6	8.3			50	21			
SUB-TOTAL				279	193	1019	4131	1454	223	1019	

REVISD 9-2-2026

MODEL: Schedule [Sheet] FILE NAME: c:\paw_work\wkdtdh\humpreys\bd1223338\03876\26-shit-schedule.dgn	USER NAME = Brandon.Humphreys		DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			DRAWN -	REVISED -						327	21RS-6.(22,23)RS-3	CLINTON	11	9
			CHECKED -	REVISED -						CONTRACT NO. 76V26				
	PLOT DATE = 9/2/2026		DATE -	REVISED -		SCALE:	SHEET 1	OF 4	SHEETS	STA.	TO STA.	ILLINOIS	FED. AID PROJECT	