



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 9, 2026

SUBJECT: Various Routes
Section 25-00001-00-ES
Franklin County
Contract No. 99778
Item 097
September 18, 2026 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices**
- 2. Revised the Table of Contents and page 2 of the Special Provisions**
- 3. Revised Plan Sheets 2 and 3**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

LOCATION OF PROJECT 1

DESCRIPTION OF IMPROVEMENT..... 1

MANDATORY PRE-BID MEETING 1

WORKING DAYS..... 1

TRAFFIC CONTROL PLAN 2

BARRICADES, TYPE III..... 2

PREPARATION OF BASE 2

~~FIBER MODIFIED ASPHALT~~ CRACK SEALING..... 2

SAWING PAVEMENT (FULL DEPTH) 3

DRAINAGE STRUCTURE REPAIR..... 3-4

LR107-4 5

LR1030-2 6-7

TRAFFIC CONTROL PLAN

Traffic control shall be in accordance with the applicable sections of the Standard Specifications, the applicable guidelines contained in the latest edition of the Manual on Uniform Traffic Control Devices; these special provisions, and any details and highway standards contained herein and in the plans.

Special attention is called to Articles 107.09 and 107.14, Sections 701 through 705 of the Standard Specifications, the traffic control related Highway Standards; the Supplemental Specifications and Recurring Special Provisions; and other Special Provisions relating to Traffic Control.

Basis of Payment. Traffic control and protection will be paid for at the contract unit price per LUMP SUM for TRAFFIC CONTROL AND PROTECTION (SPECIAL).

BARRICADES, TYPE III

Description. This work shall consist of the furnishing, installation, and maintenance of Type III barricades. ROAD CLOSED signs (R11-2) shall be mounted on the Type III barricades.

Basis of Payment. This work will be paid for at the contract unit price per EACH for BARRICADES, TYPE III. The ROAD CLOSED signs will be paid for at the contract unit price per SQ FT for SIGN PANEL – TYPE 2.

PREPARATION OF BASE

Description. Rend Lake Conservancy District will do limited preparation of base. Preliminary brooming of surface and weed spray will be performed. Contractor will be responsible to ensure surface is suitable per Section 358 of the SSRBC.

Basis of Payment. This work will be paid for per Article 109.04 of the SSRBC.

~~FIBER-MODIFIED ASPHALT~~ CRACK SEALING

Description. This work shall consist of cleaning and sealing cracks/joints in both hot-mix asphalt (HMA) and portland cement concrete pavements –according to Section 404 of the SSRBC, the plans, and this special provision. Existing vegetation shall be burned off with a torch, joints cleaned, then sealed. Prior to cleaning and sealing cracks/joints, the Engineer shall determine which cracks/joints to clean and seal.

Basis of Payment. This work will be paid for at the contract unit price per ~~FOOT of FIBER-MODIFIED ASPHALT~~ POUND of CRACK SEALING and per POUND of JOINT OR CRACK SEALING according to sections 451 and 452 of the Standard Specifications. This price shall include burning the vegetation, cleaning of the cracks/joints, and sealing the cracks/joints.