

GENERAL NOTES

1. ALL PATCHING AREAS, CURB AND GUTTER REMOVAL AND REPLACEMENT AND ANY ADDITIONAL AREAS TO BE OVERLAID WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.

COMMITMENTS

NONE

APPLICATION RATES

BITUMINOUS MATERIALS (FOG SEAL) = 0.72 LB/SQ YD
HOT-MIX ASPHALT BINDER COURSE = 112 LBS/SQ YD-IN
BITUMINOUS MATERIALS PRIME COAT = 0.25 LBS/SQ FT
AGGREGATE SURFACE COURSE = 2.05 TONS/CU YD

UTILITY CONTACT INFORMATION

UTILITIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA.

GAS/ELECTRIC - AMEREN ILLINOIS
Ms.HAYLEIGH STARKEY
HSTARKEY@AMEREN.COM
PHONE: (618) 253-9888

WATER - REND LAKE INTER-CITY WATER
1123' MARCUM BRANCH ROAD
BENTON, IL 62812
PHONE: (618) 439-4394

HMA MIXTURE REQUIREMENTS TABLES

THE FOLLOWING HMA MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT.	
LOCATION(S):	VARIOUS
MIXTURE USE(S):	3" BINDER COURSE
PG:	SB PG 64-22
DESIGN AIR VOIDS:	4.0% @ 50
MIXTURE COMPOSITION: (GRADATION MIXTURE)	IL-19.0
FRICTION AGGREGATE:	N/A
QUALITY MANAGEMENT PROGRAM:	QC/QA
MATERIAL TRANSFER DEVICE (REQUIRED?)	NO

HIGHWAY STANDARDS

0000001-09	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001006	DECIMAL OF AN INCH AND A FOOT
442001-04	CLASS C PATCHES
606001-09	CONCRETE CURB TYPE B-6.24 AND COMBINATION CONCRETE CURB AND GUTTER
701901-11	TRAFFIC CONTROL DEVICES

MODEL: General Notes [Sheet]
FILE NAME: I:\25jobs\2510103_03\CAD\Road\Sheet\2510103-Gen_Notes.dgn



USER NAME = Pop00275	DESIGNED - JTE - 3/2/2026	REVISED -  REV 9/2/2026 DJP
	DRAWN - DJP - 3/6/2026	REVISED -
	CHECKED - JTE - 6/3/2026	REVISED -
PLOT DATE = 9/2/2026	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

REND LAKE CONSERVANCY DISTRICT - ROADWAY IMPROVEMENTS
GENERAL NOTES AND HIGHWAY STANDARDS

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	25-00001-00-ES	FRANKLIN	10	2
CONTRACT NO. 99778				
25L0103	ILLINOIS	FED. AID PROJECT		

[illegible]