



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 12, 2026

SUBJECT: Key Route (Marked Route/Name)

Section MS 309 (West Pleasant Hill Road)
City of Carbondale
Contract No. 99718
Item 216
January 16, 2026 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. **Revised Plan Sheets 1 & 2**
2. **Added Plan Sheets 24A, 24B, 24C, & 24D**
3. **Revised Recurring Special Provision Index**
4. **Revised Special Provision Index**
5. **Revised pages 7 & 8 of the Special Provisions**
6. **Added page 12A to the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment



Check Sheet for Recurring Special Provisions

Local Public Agency

City of Carbondale

County

Jackson

Section Number

22-00149-00-PV

☐ Check this box for lettings prior to 01/01/2026

The Following Recurring Special Provisions Indicated By An "X" Are Applicable To This Contract And Are Included By Reference:

Recurring Special Provisions

Check Sheet #		Page No.
1	<input checked="" type="checkbox"/> Additional State Requirements for Federal-Aid Construction Contracts	87
2	<input checked="" type="checkbox"/> Subletting of Contracts (Federal-Aid Contracts)	90
3	<input checked="" type="checkbox"/> EEO	91
4	<input type="checkbox"/> Specific EEO Responsibilities Non Federal-Aid Contracts	101
5	<input type="checkbox"/> Required Provisions - State Contracts	106
6	<input type="checkbox"/> Asbestos Bearing Pad Removal	112
7	<input type="checkbox"/> Asbestos Waterproofing Membrane and Asbestos HMA Surface Removal	113
8	<input type="checkbox"/> Temporary Stream Crossings and In-Stream Work Pads	114
9	<input checked="" type="checkbox"/> Construction Layout Stakes	115
10	<input type="checkbox"/> Use of Geotextile Fabric for Railroad Crossing	118
11	<input type="checkbox"/> Subsealing of Concrete Pavements	120
12	<input type="checkbox"/> Hot-Mix Asphalt Surface Correction	124
13	<input type="checkbox"/> Pavement and Shoulder Resurfacing	126
14	<input type="checkbox"/> Patching with Hot-Mix Asphalt Overlay Removal	127
15	<input type="checkbox"/> Polymer Concrete	129
16	<input type="checkbox"/> Reserved	131
17	<input type="checkbox"/> Bicycle Racks	132
18	<input checked="" type="checkbox"/> Temporary Portable Bridge Traffic Signals	134
19	<input type="checkbox"/> Nighttime Inspection of Roadway Lighting	136
20	<input type="checkbox"/> English Substitution of Metric Bolts	137
21	<input type="checkbox"/> Calcium Chloride Accelerator for Portland Cement Concrete	138
22	<input type="checkbox"/> Quality Control of Concrete Mixtures at the Plant	139
23	<input checked="" type="checkbox"/> Quality Control/Quality Assurance of Concrete Mixtures	147
24	<input type="checkbox"/> Reserved	163
25	<input type="checkbox"/> Reserved	164
26	<input type="checkbox"/> Temporary Raised Pavement Markers	165
27	<input type="checkbox"/> Restoring Bridge Approach Pavements Using High-Density Foam	166
28	<input type="checkbox"/> Portland Cement Concrete Inlay or Overlay	169
29	<input type="checkbox"/> Portland Cement Concrete Partial Depth Hot-Mix Asphalt Patching	173
30	<input type="checkbox"/> Longitudinal Joint and Crack Patching	176
31	<input type="checkbox"/> Concrete Mix Design - Department Provided	178
32	<input type="checkbox"/> Station Numbers in Pavements or Overlays	179

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
WORKING DAYS.....	1
RESIDENT NOTIFICATION	1
QUALITY CONTROL TESTING.....	2
SITE INSPECTION	2
SHOP DRAWINGS	2
TRAFFIC CONTROL PLAN.....	2
TRAFFIC CONTROL AND PROTECTION (SPECIAL)	4
ACCESS TO ENTRANCES	5
AGGREGATE FOR TEMPORARY ACCESS.....	5
DISPOSAL OF SURPLUS MATERIALS.....	5
SAFETY AND PROTECTION	6
UTILITIES	7
JOINT UTILITY INFORMATION FOR EXCAVATIONS (J.U.L.I.E.).....	8
POTHOLING.....	9
AVAILABILITY OF ELECTRONIC FILES	9
PROPERTY OWNER NOTIFICATION	10
TRENCH BACKFILL	10
TIE BARS AND DOWELL BARS.....	10
PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	10
PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	10
PIPE CULVERT REMOVAL	11
WATER VALVES TO BE ADJUSTED	11
WOVEN WIRE FENCE TO BE REMOVED AND RE-ERECTED.....	11
RELOCATE SIGN, SPECIAL.....	11
ILLUMINATED SIGN (SPECIAL).....	12
PAVEMENT PATCHING (SPECIAL)	12
HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH.....	12
TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)	12A
INSURANCE (LR 107-4).....	13
LOCAL QUALITY ASSURANCE / QUALITY MANAGEMENT QC/QA (LR 1030-2).....	14
STORM WATER POLLUTION PREVENTION PLAN	16

In EMERGENCIES affecting the safety or protection of persons or the Work or property at the site or adjacent thereto, Contractor, without special instructions or authorization from Engineer or Owner, is obligated to act to prevent threatened damage injury or loss. Contractor shall give Engineer prompt, written notice if Contractor believes that any significant changes in the Work or variations from the Contract Documents is required because of action taken in response to an emergency, a Work Directive Change or Change Order will be issued to document the consequences of the changes or variations.

Compliance with this special provision shall be considered included in the cost of the contract and no additional compensation will be allowed for any costs incurred.

UTILITIES

Underground utilities have been plotted from available surveys and record drawings; therefore their locations must be considered approximate. There may also be utilities for with the presence and location are unknown. Verification of locations of underground utilities, shown or not shown, will be the responsibility of the Contractor.

The following utility companies have facilities within the project limits which may require adjustments:

Name and Address of Utility	Type	Status
Ameren Illinois 1800 W. Main St. Marion, IL 62959	Gas	Gas Valve to be adjusted to grade (During Construction): STA. 105+70.90, 36.8' LT Gas Valve/Service to be relocated (Not completed): STA. 112+79.03, 28.4' RT STA. 115+68.54, 30.9' RT
Egyptian Electric Cooperative Association 1732 Finney Rd. Murphysboro, IL 62966 Southern Illinois Power Cooperative 11543 Lake of Egypt Road Marion, IL 62959	Electric	Service Pole to be relocated(Poles relocated except 1 pole that is owned by Southern Illinois Power Cooperative needing to be relocated. SIPA has been contacted and scheduling relocated): STA. 112+52.19, 25.5' RT STA. 115+79.37, 27.1' RT Guy Wire to be adjusted to grade (Completed except those associated with 1 pole that is owned by Southern Illinois Power Cooperative needing to be relocated. SIPA has been contacted and scheduling relocated): STA. 115+88.23, 28.1' LT STA. 125+99.42, 23.8' LT STA. 125+99.84, 24.7' LT STA. 126+04.83, 23.8' LT STA. 126+05.12, 24.9' LT STA. 126+13.05, 24.2' LT STA. 126+13.20, 25.1' LT

MUN 0309 PLEASANT HILL ROAD
SECTION 22-00149-00-PV
CARBONDALE, IL
JACKSON COUNTY

		STA. 128+16.69, 31.3' RT
City of Carbondale 200 S. Illinois Avenue Carbondale, IL 62901	Sanitary Sewer	No adjustments anticipated.
Frontier Communications 208 W Union St. Marion, IL 62959	Communications	(Relocates originally scheduled for 12/15. Still waiting on fiber optic cable. Once available, relocation will start) Splice Box to be adjusted to grade: STA. 101+24.64, 20.7' LT STA. 101+29.38, 19.8' LT STA. 111+53.69, 21.4' RT STA. 128+06.41, 30.6' RT STA. 128+12.45, 35.0' RT Splice Box to be relocated: STA. 111+15.41, 20.5' LT STA. 115+08.09, 22.9' RT STA. 118+97.53, 21.3' LT Pullbox to be adjusted to grade: STA. 118+84.55, 24.4' LT Fiber Marker to be relocated: STA. 104+62.32, 26.1' LT
Clearwave Communications 2 N Vine St. Harrisburg, IL 62946	Communications	No adjustments anticipated.
South Highway Water District	Water	Water Meter to be adjusted to grade (During Construction): STA. 111+79.95, 24.8' RT Water Meter to be relocated (Not Completed): STA. 114+20.72, 19.4' RT STA. 114+20.52, 26.8' RT
Zito Media	Communications	No adjustments anticipated.
MediaCom 1603 E Deyoung St. Marion, IL 62959	Communications	No adjustments anticipated.
SIU – Campus Facilities foc.facilities@siu.edu	Various	No adjustments anticipated.

JOINT UTILITY INFORMATION FOR EXCAVATIONS (J.U.L.I.E.)

This work shall be done in accordance with Article 107.39 of the Standards Specifications except as modified herein:

TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)

This item shall include furnishing, operating and maintaining all temporary traffic signals as shown on the staging details for the construction of the project.

Temporary Bridge Traffic Signals (Special) will be measured for payment as each, where each is defined as the entire traffic signal system regardless of the number of signal heads.

This work will not be measured or paid for separately and shall be included in the LUMP SUM contract unit price for TRAFFIC CONTROL AND PROTECTION, (SPECIAL) and no additional compensation will be allowed.