



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 13, 2026

SUBJECT: FAU 6780 (South Lake Storey Road)
Section 19-01502-40-BT (Galesburg)
Knox County
Contract No. 89834
Item 220
January 16, 2026 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised Special Provision Index**
- 2. Revised page 9 of the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
STATUS OF UTILITIES/UTILITIES TO BE ADJUSTED	1
UTILITIES – LOCATIONS/INFORMATION ON PLANS	2
LOCATION OF UNDERGROUND STATE MAINTAINED FACILITIES	2
CONSTRUCTION LAYOUT RESPONSIBILITY	3
TRAFFIC CONTROL PLAN	3
AGGREGATE BASE COURSE, TYPE B 2", 4", AND 6"	4
SEEDING (SPECIAL)	4
REMOVAL OF EXISTING WOOD BOLLARDS	4
BIKE PATH REMOVAL	5
REMOVE AND REINSTALL BRICK PAVERS	5
FOLD DOWN BALLARDS	5
CHAIN LINK FENCE REMOVAL	5
CHAIN LINK FENCE, 5' (SPECIAL)	6
BOLLARDS	6
ROCK FILL	7
PRECAST CONCRETE BOX CULVERT (SPECIAL)	7
PCC QMP ELECTRONIC REPORT SUBMITTALS	8
PCC AUTOMATIC BATCHING EQUIPMENT	8
REMOVAL OF ABANDONED UNDERGROUND UTILITIES	8
PROOF ROLLING	9
INTERIM COMPLETION DATE	9
SUBGRADE TREATMENT	10
CONSTRUCTION LAYOUT UTILIZING GPS EQUIPMENT	10
PNEUMATIC-TIRED ROLLER FOR HOT-MIX ASPHALT	10
MEMBRANE CURING METHOD	11

FENCE REMOVAL	11
RELOCATE SIGN, SPECIAL	11
RELOCATE MEMORIAL STONE	12
STUMP REMOVAL	12
ADJUST SANITARY SEWER CLEANOUT	12
LR 107-4 – INSURANCE	13
LR 1030-2 LOCAL QUALITY ASSURANCE / QUALITY MANAGEMENT	14
STORMWATER POLLUTION PREVENTION PLAN (SWPPP)	16
CONTRACTOR CERTIFICATION STATEMENT	27
GEOTECH REPORT	28
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING	61

PROOF ROLLING

Effective April 23, 2004 Revised October 30, 2023

This work shall consist of proof rolling the path subgrade with a fully loaded tandem axle dump truck and driver at the direction of the Engineer.

This work will not be paid for separately, but considered included in the various earthwork pay items.

INTERIM COMPLETION DATE

The Contractor shall complete all embankment work that needs to be constructed in Lake Storey to a minimum elevation of 757.00, from approximate Sta. 14+50 to Sta. 20+50, Sta. 35+50 to Sta. 36+75, Sta. 52+50 to Sta. 57+00, culvert extensions, and any other location in the lake, by June 1, 2026. The City of Galesburg agrees to maintain low lake levels until June 1st. After that date, the City of Galesburg will let the lake refill naturally. If embankment and culvert extension work described herein is not completed by June 1, 2026, liquidated damages will be assessed in accordance with the Standard Specifications.