


STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION




SECTION A-A



SECTION B-B



PLAN (North abutment shown, south abutment mirrored about Bridge Chord)



SECTION C-C

(Dimensions at Rt. L's)

- 1. Cross hatched area indicates concrete romoval.
- Cross hatched area indicates concrete romoval.
 Existing reinforcement bars in the concrete removal are extending in new construction shall be cleaned and incorporated into the new construction.
 Cost included in Concrete Removal.
 Any reinforcement bars that are damaged during concrete removal operations shall be repaired or replaced using an approved bar splicer or anchorage system, in accordance with IDOT Standard Specifications Article 501.03. Cost included in Concrete Removal.
- 4. See Sheet 2 of 8 for Stage Construction Details.
 5. Overlay removal is included in cost of Concrete Removal.

BILL OF MATERIAL

Item	Unit	Total					
Concrete Removal	Cu. Yd.	19.8					

CONCRETE REMOVAL STRUCTURE NO 016-0375

<u>31/100/01/E NO. 010 03/3</u>						
LIN ENGINEERING,LTD. Consulting Engineers Cital Park, Birols 8 SHEETS	SHEET NO. 4	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		290	(531-3 .1, 0305-302K)RS-5	COOK	314	211
			CONTRACT	NO. 6	0138	
Designed By: KHH Checked By: MTH Drawn By: KHH Date: 12/2009 File: 016-0375.dgn		FED. RO	DAD DIST. NO ILLINOIS FED. A	ID PROJECT		