SHEET NO.	TITLE
1	TITLE SHEET
2	GENERAL NOTES, STATE STANDARDS AND INDEX OF SHEETS
3-4	SUMMARY OF QUANTITIES
5	TYPICAL SECTIONS
6	STAGING TYPICAL SECTIONS
7	CONSTRUCTION STAGING PLAN - STAGE 1
8	CONSTRUCTION STAGING PLAN - STAGE 2
9	ROADWAY RESURFACING AND APPROACH OVERLAY PLAN
10	PAVEMENT MARKING PLAN
11- 16	STRUCTURAL PLANS
17	BUTT JOINT AND HMA TAPER DETAILS
18	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTION AND DRIVEWAYS
19	RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)
20	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
21	ARTERIAL ROAD INFORMATION SIGN
	HIGHWAY STANDARDS

STATE STANDARDS

SHEET NO.	<u>TITLE</u>
000001 -05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001 - 02	AREAS OF REINFORCEMENT REBARS
606306 -03	CORRUGATE PC CONCRETE MEDIAN
701602 -04	URBAN LANE CLOSURE, MULTILANE, 2W WITH BIDIRECTIONAL LEFT TURN LANE
701606 -06	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701 -06	URBAN LANE CLOSURE MULTILANE INTERSECTION
701901 - 01	TRAFFIC CONTROL DEVICES
704001 -06	TEMPORARY CONCRETE BARRIER

GENERAL NOTES

ALL ELEVATIONS ARE BASED ON UNITED STATES COAST AND GEODETIC SURVEY DATUM.

DIMENSIONS ARE IN ENGLISH UNITS UNLESS OTHERWISE NOTED.

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES (48 HOURS NOTIFICATION IS REQUIRED).

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.

ANY REFERENCE TO STANDARDS IN THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT LISTED IN THE PLANS WITH THE LATEST NUMBERS.

WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING PROPERTIES.

THE RESIDENT ENGINEER SHALL CONTACT MR. DON CHIARUGI,
AREA TRAFFIC ENGINEER, AT (847) 741-9857 AT A MINIMUM
OF 2 WEEKS PRIOR TO THE PLACEMENT OF PERMANENT
PAVEMENT MARKING.

THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.

ALL WORK IS TO BE COMPLETED BY THE COMPLETION DATE. THE COMPLETION DATE FOR THIS CONTRACT IS SEPTEMBER 24, 2010

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORED FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFELCTIVE MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATINOS OF ALL PAVEMENT MARKINGS SHALL BE DIRECTED BY THE ENGINEER.

		7777		
	CONSULTING ENGINEERS 1560 WALL ST, SUITE 222 NAPERVILLE, ILLINOIS 60563 PM; (630) 577-9100		DESIGNED - MJY	REVISED -
			DRAWN - ST, TSC	REVISED -
			CHECKED - MJY, DC	REVISED -
			DATE - 01/29/2010	REVISED -

STATE	OF	ILLINOIS
DEPARTMENT (OF 1	TRANSPORTATION

GENERAI	NOTES STATE STANDARI	OS AND INDEX OF SHEETS	F.A.P RTE.	· SECT	TION		COUNTY	TOTAL	SHEE
			351	539	B-1		COOK	21	2
US 6 (159th STREET) OVER CALUMET UNION DITCH			D-91-226-10				CONTRACT	NO.	60J36
SCALE: NONE	SHEET NO. 2 OF 21 SHEETS	STA. 91+81.22 TO STA. 92+79.51	FED.	ROAD DIST. NO.	ILLINOIS F	ED. AII	D PROJECT		