
## STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

EXISTING DECK BEAM



## NOTES

Detail I - With Bar Splicer or Couplers:

Connect one (I) I''XI'''XI''' steel I' to the top layer of coupler with  $2-5_8$ ''  $\phi$  bolts screwed to coupler at approximate  $\hat{V}$  of each barrier panel.

Detail II - With Extended Reinforcement Bars:

Connect one (1) 1"x7"x 10" steel £ to the concrete slab or concrete wearing surface with 2-5g" \$\phi\$

Expansion Anchors or cast in place inserts spaced between the top layer of reinforcement at approximate £ of each barrier panel.

Cost of anchorage is included with Temporary Concrete Barrier.


The 1" x 7" x 10" plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready to be placed.

## SECTIONS THRU SLAB OR DECK BEAM

EXISTING SLAB

- \*\*\* Dimension shown is minimum required embedment into concrete.

  If hot-mix asphalt wearing surface is present, minimum embedment shall be in addition to wearing surface depth.
- \*\*\*\* If existing deck beam is to remain in place after stage construction, embedment shall only be into wearing surface and not into existing deck beam concrete.



NEW SLAB

DETAIL I

EXAMINED

PASSED


11-1-09

ENGINEER OF STRUCTURAL SERVICES

DESIGNED JWK


CHECKED JMH

CHECKED JWK
R-27



\*\* Wood blocks may be omitted when required to provide minimum stage traffic lane width. When the wood blocks are omitted, the concrete barrier shall be in direct contact with the steel retainer plate.

"W" = Top bars spacing + 4"



## STEEL RETAINER P 1" x 7" x 10"

\* Required only with Detail II

TEMPORARY CONCRETE BARRIER

FOR STAGE CONSTRUCTION

STRUCTURE NO. 016-0919

SHEET NO. S6	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
OF .	1631	2009-123I	COOK	12	10
S6 SHEETS			CONTRACT	NO. 60	J77
	ILLINOIS FED. AID PROJECT				