

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

REVISED	- R. MIRS 09-15-	97
REVISED	- R. MIRS 12-11-9	7
REVISED	-T. RAMMACHER 02-	02-99
REVISED	- C. JUCIUS 01-3	1-07

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.

ARTERIAL ROAD INFORMATION SIGN

	USER NAME = \$USER\$	DESIGNED - MJY		STATE OF ILLINOIS	DISTRICT ONE DETAIL SHEETS	F.A.U. RTE. SECTION	COUNTY TOTAL SHEETS NO.
		DRAWN - ST, TSC	REVISED -		YORK ROAD AT IL ROUTE 38 (1.5 MI EAST OF IL ROUTE 83)	2678 163 HB-I-1	DUPAGE 31 31
CONSULTING ENGINEERS 1560 WALL ST, SUITE 222	PLOT SCALE = \$SCALE\$	CHECKED - MJY	REVISED -	DEPARTMENT OF TRANSPORTATION	TORK HOME AT IL HOUTE 30 (1.5 MILEAST OF IL HOUTE 05)	D-91-275-10	CONTRACT NO. 60J85
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100	PLOT DATE = \$DATE\$	DATE - 01/29/2010	REVISED -		SCALE: NONE SHEET NO. 31 OF 31 SHEETS STA. 58+35 TO STA. 61+67	FED. ROAD DIST. NO. ILLINOIS FED.	AID PROJECT