ROUTE NO.	SECTION	COUNTY		YOTAL SHEETS	SHEET NO.	SHEET NO. 2	
FAI 55	*			72	49	9	SHEETS
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-				

Contract #62930

\* 88(B&B-1)BR

## INDEX OF SHEETS

- 1 PLAN AND ELEVATION
- 2 GENERAL NOTES AND TOTAL BILL OF MATERIAL
- 3 CROSS SECTION
- 4 CONTINUOUS SEAL NEOPRENE EXPANSION JOINTS
- 5-6 DECK SLAB REPAIR
- 7 CONCRETE BRACKETS AT PIERS
- 8 PIER REPAIRS
- 9 ABUTMENT AND PIER REPAIRS

## GENERAL NOTES

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

THE CONTRACTOR SHALL ENSURE THAT NO CONCRETE WILL BE ALLOWED TO DROP INTO THE RIVER. CONCRETE SHALL BE CAUGHT ON A FLOATING PLATFORM OR OTHER MEANS APPROVED BY THE ENGINEER. COST INCLUDED WITH DECK SLAB REPAIR (FULL DEPTH, TYPE II).

REINFORCEMENT BARS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A 760 GR 60. SEE SPECIAL PROVISIONS.

REINFORCEMENT BARS DESIGNATED (E) SHALL BE EPOXY COATED.

## TOTAL BILL OF MATERIAL

UNIT	SUPER	SUB	TOTAL
Sq Yd	4449		4449
Sq Yd	4449		4449
Foot	97		97
Foot	97		97
Foot		275	275
Sa Et		90	90
34 11		90	
Cu Yd		8.0	8.0
Cu Yd		<i>29.</i> 5	29.5
Pound		3,090	3,090
Cu Ft	0.5		0.5
Sq Yd	1		1
Sq Yd	4219		4219
Sq Yd	4449		4449
	Sq Yd Sq Yd Foot Foot Sq Ft Cu Yd Cu Yd Pound Cu Ft Sq Yd Sq Yd	Sq Yd         4449           Sq Yd         4449           Foot         97           Foot         97           Foot         97           Sq Ft         Cu Yd           Cu Yd         Pound           Cu Ft         0.5           Sq Yd         1           Sq Yd         4219	Sq Yd         4449           Sq Yd         4449           Foot         97           Foot         97           Foot         275           Sq Ft         90           Cu Yd         8.0           Cu Yd         29.5           Pound         3.090           Cu Ft         0.5           Sq Yd         1           Sq Yd         4219

ILLINOIS DEPARTMENT OF TRANSPORTATION GENERAL NOTES AND TOTAL BILL OF MATERIAL I-55 SB OVER KANKAKEE RIVER FAI ROUTE 55, SECTION 88(B&B-1)BR WILL COUNTY ORAWN BY TFG/CFC CHECKED BY MCB/KPS DRAWING NO. SN 099-0002 COOMBE-BLOXDORF P.C. Engineers / Land Surveyors Springfield, Illinois Design Firm License No. 184-002703 OF 9 SHTS