



BOLT LOCATIONS

CABINET - BASE BOLT PATTERN





CABLE HOOKS
REQUIRED, ALL
HANDHOLES

TO CONTROLLER
DOUBLE HANDHOLE

TO POLE OR
POST AS REO'D.

GREEN

TO POLE OR
POST AS REO'D.

HANDHOLE COVER & FRAME – GROUNDING DETAIL

(NOT TO SCALE)

(2) 1/2" x 1 1/4" STAINLESS STEEL BOLT WITH SPLIT LOCK
WASHER AND NYLON INSERT LOCKOUT WELDED TO
FRAME AND TO COVER, (TYPICAL)

HEAVY DUTY COPPER COMPRESSION
GROUNDING TERMINAL. (TYPICAL)

EXISTING HANDHOLE
FRAME AND COVER (PAID FOR SEPARATELY)

EXISTING HANDHOLE COVER & FRAME - GROUNDING DETAIL

(NOT TO SCALE)

NOTES:

GROUNDING SYSTEM

(847) 705-4139.

C-91-405-08

THE GROUNDING SYSTEM SHALL CONSIST OF AN INSULATED CONDUCTOR

TYPE XLP, NO. 6 A.W.G., STRANDED COPPER TO BE INSTALLED IN

RACEWAYS. THE GROUNDING CABLE SHALL BE INSTALLED

IN A CONTINUOUS MANNER AS SHOWN ON THE CABLE PLAN PROVIDED.

ALL GROUNDING CONDUCTORS SHALL BE BONDED TO METAL ENCLOSURE

(HANDHOLE, POST, MAST ARM, CONTROLLER, ETC.), GROUND ROD SHALL BE

3/4" DIA. × 10'-0" (20mm × 3.0m) LONG, COPPER CLAD. ONE GROUND ROD

SHALL BE INSTALLED AT ALL POST FOUNDATIONS, POLE FOUNDATIONS,

CONTROLLER CABINET FOUNDATION AND ELECTRICAL SERVICE INSTALLATION


AS INDICATED ON THE CABLE PLAN. IF THERE ARE ANY SPECIAL CONDITIONS

SUCH AS SUB-SURFACE CONDITIONS OR INSTALLATION PROBLEMS, THE RESIDENT

ENGINEER SHALL BE NOTIFIED OR CONTACT THE BUREAU OF TRAFFIC,

ILLINOIS DEPARTMENT OF TRANSPORTATION DISTRICT ONE AT

- THE NEUTRAL CONDUCTOR AND THE GROUND CONDUCTOR SHALL BE CONNECTED IN THE SERVICE INSTALLATION. AT NO OTHER POINT IN THE TRAFFIC SIGNAL SYSTEM SHALL THE NEUTRAL AND GROUND CONDUCTORS BE CONNECTED.
- 3. ALL EQUIPMENT GROUNDING CONDUCTORS SHALL TERMINATE AT THE GROUND BUS IN THE CONTROLLER CABINET.
- 4. THE CONTRACTOR SHALL PROVIDE A GROUND CABLE WITH CONNECTORS BETWEEN THE HANDHOLE COVER AND HANDHOLE FRAME.








3/4" (20mm) HEAVY-DUTY GROUND ROD CLAMP (BURNDY TYPE GRC OR APPROVED EUAL)

NOTES:

• ALL CLAMPS SHALL BE BRONZE OR COPPER, UL APPROVED.
• GROUND CABLE SHALL BE LOOPED OVER HOOKS IN THE HANDHOLES
6.5' (2.0m) SLACK SHALL BE PROVIDED IN SINGLE HANDHOLES
13' (4.0m) OF SLACK SHALL BE PROVIDED IN DOUBLE HANDHOLES.
5' (1.4m) OF SLACK SHALL BE PROVIDED BETWEEN FRAME AND COVER.



REVISIONS
NAME DATE

DISTRICT 1

STANDARD TRAFFIC SIGNAL

DESIGN DETAILS

SCALE; VERT, NONE DESIGNED BY: DAD CHECKED BY: DAZ DATE 1-01-02 SHEET 3 OF 4

TS05