PROP. PAY LIMIT OF HMA SURF. REMOVAL FULL THICKNESS OF MILLING TEMP. RAMP (NOTE "E") PROP. HMA SURFACE REMOVAL-EXIST. PAVEMENT MILLED TEMPORARY RAMP (FOR BUTT JOINT AND HMA TAPER SEE DETAIL BELOW) OPTION 1 PROP. PAY LIMIT OF HMA SURF. REMOVAL FULL THICKNESS OF MILLING SAW CUT (INCLUDED IN THE COST TEMP. RAMP OF HMA SURFACE PROP. HMA SURFACE REMOVAL REMOVAL - BUTT JOINT) (NOTE "E") 13/4 (45) FOR E AND F MIX 11/2 (40) FOR C AND D MIX (NOTE "D") (NOTE "F") EXIST. HMA SURF. EXIST. PAVEMENT HMA CONSTRUCTED TEMPORARY RAMP (FOR BUTT JOINT AND HMA TAPER SEE DETAIL BELOW) OPTION 2 TYPICAL TEMPORARY RAMP HMA TAPER LENGTH SAW CUT (INCLUDED IN THE COST OF HMA SURFACE PROP. HMA SURF. CRSE. REMOVAL - BUTT JOINT) 4'-6" (1.35 m) PROP. HMA BINDER CRSE. VARIES 13/4 (45) FOR E AND F MIX PAY LIMIT FOR BUTT JOINT (NOTE "D") 11/2 (40) FOR C AND D MIX EXIST. HMA SURF. EXIST. PAVEMENT HMA SURF. REMOVAL - BUTT JOINT BUTT JOINT AND HMA TAPER

TYPICAL BUTT JOINT AND HMA TAPER

FOR MILLING AND RESURFACING

RTE. SECTION COUNTY TOTAL SHEETS NO. 2802/ 09-00032-00-RS COOK 18 17 TO STA, 37+87.89 FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT PROP. HMA OR PCC
SURFACE REMOVAL - BUTT JOINT
30'-0" (9.0 m) (NOTE "A") SAW CUT (INCLUDED IN THE COST OF HMA OR P.C.C. SURFACE REMOVAL EXIST. HMA OR PCC SURFACE 15'-0" (4.5 m) (NOTE "B") - BUTT JOINT) (NOTE "D") $1\frac{3}{4}$ (45) FOR E AND F MIX $1\frac{1}{2}$ (40) FOR C AND D MIX * * EXIST. PAVEMENT BUTT JOINT DETAIL TAPER LENGTH * * VARIES PROP. HMA SURF. CRSE. 13/4 (45) FOR E AND F MIX PROP. HMA BINDER CRSE. 11/2 (40) FOR C AND D MIX * * EXIST. PAVEMENT HMA TAPER DETAIL TYPICAL BUTT JOINT AND HMA TAPER FOR RESURFACING ONLY * * PC CONCRETE, HMA OR HMA RESURFACED PAVEMENT. NOTES A: MAINLINE ROADWAYS AND MAJOR SIDE ROADS. B: MINOR SIDE ROADS. C: THE TEMP. RAMP SHALL BE CONSTRUCTED IMMEDIATELY UPON REMOVAL OF THE EXISTING HMA SURFACE. D: THE BUTT JOINT SHALL BE CONSTRUCTED IMMEDIATELY PRIOR TO PLACING THE PROPOSED HMA COURSES.

- E: TAPER THE TEMP. RAMP AT A RATE OF 3'-0" (900 mm) PER 1 INCH (25 mm) OF MILLING THICKNESS.
- F: INSTALLATION AND REMOVAL OF THE 4'-6" (1.35 m) TEMP. RAMP IS INCLUDED IN COST OF HMA SURFACE REMOVAL - BUTT JOINT
- G: SEE ARTICLE 406.08 AND 406.14 OF THE STANDARD SPECIFICATIONS FOR "HMA AND/OR PCC SURFACE REMOVAL, BUTT JOINT".
- * SEE TYPICAL SECTIONS FOR MILLING THICKNESS.
- ** ** 20'-0" (6.1 m) PER 1 (25) RESURFACING (NOTE "A") 10'-0" (3.0 m) PER 1 (25) RESURFACING (NOTE "B")

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

ILLINOIS DEPARTMENT OF TRANSPORTATION

BASIS OF PAYMENT:

THE BUTT JOINT WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE YARD (SQUARE METER) FOR "HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT" OR FOR "PORTLAND CEMENT CONCRETE SURFACE REMOVAL- BUTT JOINT".

09/09/

BUTT JOINT AND HMA TAPER

DETAILS

DRAWN BY

DATE NAME SCALE NAME

(hbe) Hoefferle-Butler Engineering, Consulting Civil Engineers - Land Surveyors PRESSINAL ESTAN IN INCOMENS. AND INCOMENS. ONCY MILLS, ILLINGS 60677 (DRS 599-679)

SCALE: VERT. NONE

CHECKED BY BD400-05 (VI=BD32)

CONTRACT NO. 63410