## EVERETT ROAD & RIVERWOODS ROAD ROUNDABOUT

## TRAFFIC CONTROL AND PROTECTION GENERAL NOTES

1. APPLICABLE STANDARDS

OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' (4.5 m) AWAY
OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE 701006-03 OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY LANE CLOSURE, 2L, 2W, SHORT TERM OPERATIONS LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY FOR SPEEDS >= 45 MPH 701311-03 LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS-DAY ONLY 701331-03 LANE CLOSURE, 2L, 2W, WITH RUN-AROUND FOR SPEEDS >= 45 MPH 701501-05 URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED 701701-06 URBAN LANE CLOSURE, MULTILANE INTERSECTION 701801-04 LANE CLOSURE, MULTILANE, 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE 701901-01 TRAFFIC CONTROL DEVICES 704001-06 TEMPORARY CONCRETE BARRIER 720001-01 SIGN PANEL MOUNTING DETAILS 720006-02 SIGN PANEL ERECTION DETAILS 720011-01 METAL POSTS FOR SIGNS, MARKERS & DELINEATORS

APPLICABLE DETAILS

728001-01

LC7200 DIRECTION INDICATOR BARRICADES
LC7202 SHOULDER CLOSURE AND TAPER FOR CHANGEABLE MESSAGE SIGN

TELESCOPING STEEL SIGN SUPPORT

- 2. The permanent traffic control depicted hereon is the minimum requirement. Additional traffic control devices as specified by the above Highway Standards and the Special Provisions shall be placed by the contractor to the satisfaction of the engineer. All traffic control devices shall be included in the cost of the lump sum pay item "TRAFFIC CONTROL AND PROTECTION, (SPECIAL)" unless otherwise indicated in the plans or special provisions.
- All traffic control warning signs and associated signing mounted with the warning signs shall have black legends and borders on fluorescent orange reflective sheeting.
- 4. All construction signs, barricades and other devices required to control traffic shall be furnished, installed and maintained by the contractor.
- 5. All traffic control devices shall be removed, covered or turned away from traffic immediately when they are no longer necessary. When a sign is covered, the post shall have a reflective 3 inch x 6 inch delineator installed.
- 6. The sign spacing for the above Highway Standards shall be in accordance with the Sign Spacing Table shown herein this Traffic Control Plan.
- 7. Road name plates shall be installed on the "ROAD WORK AHEAD" signs at the intersections shown in this Traffic Control Plan. The road name plates shall be 9 inch blanks with 6 inch uppercase and 5 inch lowercase lettering. The road name plates shall be furnished by the contractor.
- "ROAD WORK AHEAD" signs shall be equipped with mono-directional Type A amber flashing lights.
- 9. CONSTRUCTION MUST BE STAGED IN ORDER TO MAINTAIN ACCESS TO PEDESTRIAN/BIKE PATH.


  The cost of this work is included in the lump sum pay item "TRAFFIC CONTROL AND PROTECTION, (SPECIAL)" and no additional compensation will be allowed.
- 10. PROPER PROTECTION MUST BE PROVIDED TO ENSURE SAFETY OF PEDESTRIANS AND BICYCLISTS DURING CONSTRUCTION.

POSTED SPEED LIMIT EVERETT ROAD - 45 MPH RIVERWOODS ROAD - 45 MPH (NORTH LEG) RIVERWOODS ROAD - 40 MPH (SOUTH LEG) ADVANCE WARNING SIGN SPACING TABLE DISTANCE BETWEEN SIGNS POSTED SPEED Δ R 40 MPH OR LESS 200 FT. 45-50 MPH 400 FT. 350 FT. 55 MPH 500 FT. 500 FT.

LEG	POSTED SPEED	TAPEN NATE
NORTH, WEST, EAST	45 MPH	25:1
SOUTH	40 MPH	15:1

TAPER RATE TABLE

DENOTES ITEMS AND WORK NOT PAID FOR SEPARATELY







			(	63415	
GENERAL NOTES	ROUTE	SECTION	SECTION NUMBER	SHEET	SHEET
	F0/F0	100	04 0010C 0C CTT	21	105
TRAFFIC CONTROL PLAN	58/52	136	04-00136-06-CH	OT.	107