

SEQUENCE OF CONSTRUCTION:

- 1. CLOSE EXISTING VALVE.
- 2. REMOVE EXISTING HYDRANT.
- 3. INSTALL HYDRANT EXTENSION AND NEW VALVE.
- 4. RELOCATE EXISTING HYDRANT.
- 5. OPEN EXISTING VALVE, REMOVE BOX.
- 6. BACKFILL.
- 7. FLUSH AND TEST FOR CHLORIDE RESIDUAL AND PROVIDE TEST.

ALL WORK TO BE DONE IN ACCORDANCE WITH ARTICLE 564 OF THE STANDARD SPECIFICATIONS. NEW VALVE AND BOX SHALL BE SAME MAKE AND MODEL AS EXISTING.

## FIRE HYDRANT TO BE MOVED

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = gaglianobt	DESIGNED -	REVISED - R. SHAH 09-09-94  REVISED - R. SHAH 10-25-94	STATE OF ILLINOIS	FIRE HYDRANT TO BE MOVED	RTE.	SECTION	COUNTY	TOTAL	AL SHEET TS NO.
	PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED - R. SHARI 10-25-94	DEPARTMENT OF TRANSPORTATION	C was	347	09-00248-00-RS BD-36	CONTRAC	274	1 265
	PLOT DATE = 1/4/2008	DATE -	REVISED -		SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED. R	OAD DIST. NO. 1 ILLINOIS FED. A	ID PROJECT	, I NU.	